1. Zoning Board Of Appeals Agenda 3/6/25

    Documents:

        ZONING_BOARD_AGENDA_030625.PDF

2. Case No. 25-001 - Tedford Appeal Staff Memo

    Documents:

        CASE NO. 25-001 - TEDFORD APPEAL STAFF MEMO.PDF

2.I. Case No. 25-001 - Attachments

    Documents:

        CASE NO. 25-001 - ATTACHMENTS.PDF

2.II. Case No. 25-001 - Additional Communication

    Documents:

        APPELLANT_COMMUNICATION MARCH 2, 2025 5.07 PM.PDF
        APPELLANT_COMMUNICATION MARCH 3, 2025 10.58 AM.PDF
        TEDFORD HOUSING RESPONSE TO APPEAL FEBRUARY 27, 2025 1.04 PM.PDF

Town of Brunswick, Maine
INCORPORATED 1739
DEPARTMENT OF PLANNING
AND CODES
85 UNION STREET
BRUNSWICK, MAINE 04011-2418
TELEPHONE 207-725-6660
FAX 207-725-6663

Zoning Board of Appeals Agenda
Brunswick Town Hall
Council Chambers
85 Union St
Thursday, March 6, 2025 @7:30 PM

There is an opportunity to attend this meeting in person or via Zoom.

How to watch and comment via Zoom:
https://www.brunswickme.org/313/Brunswick-Cable-TV3

How to watch via TV3 or Live Stream:

The link to view or listen to the meeting on TV3 (Channel 3 on Comcast) or via live stream from the Town's website: http://tv3hd.brunswickme.org/CablecastPublicSite/watch/1?channel=1

All votes to be taken via roll call.

The public may provide digital or hard-copy comment OR they may provide live comment at the meeting via Zoom or in person. Digital comment may be sent via email (jdealaman@brunswickme.gov) and written comment may be mailed to: Planning & Development, 85 Union Street, Brunswick, ME 04011. (Please note: written comment must be received no later than noon of the day of the meeting) For any questions, please call: 207-721-4026.

1. **Case No. 25-001 -65 Thomas Point Road:** The Zoning Board of Appeals will hold a **PUBLIC HEARING** in accordance with Section 5.2.7.A of the Brunswick Zoning Ordinance; to consider an appeal submitted by Jennifer Navarro to appeal the Brunswick Planning Board's approval of Case No. 24-076 Extension Request for Tedford Housing Homeless Shelter, Resource Center Site Plan Major Development Review (Final Plan) Approval. The subject property is located at 65 Thomas Point Road (Map 42 Lot 8) and within the Growth Mixed-Use 4 (GM4) Zoning District.

2. Other Business

3. Adjourn

Town of Brunswick, Maine

DEPARTMENT OF PLANNING AND CODES

MEMORANDUM

TO: Zoning Board of Appeals (ZBA)

FROM: James Dealaman, Principal Planner

DATE: March 6, 2025

SUBJECT: Case No. 25-001; Tedford Shelter Town's Summary of Appeal

I. BACKGROUND INFORMATION:

On January 28, 2025, the Planning Board approved a Site Plan (Final Plan) Approval Extension [Exhibit A] for Case# 21-070 Tedford Housing Homeless Shelter, Resource Center which was originally approved on January 11, 2022. The project is located at 65 Thomas Point Road (Map 42 Lot 8).

On February 4, 2025, Jennifer Navarro, of 90 Thomas Point Road, (hereafter referred to as "the Appellant") filed a Zoning Board of Appeals Appeal Form [See Exhibit B] with the Town Planning and Codes office pursuant to Section 5.2.7.A(1) stating alleged erroneous decision/inaction of Planning Board.

Among the justifications described in the appeal, staff has summarized the following points provided by the Appellant:

a) Was the extension filed before the site permit expiration, and the site plan expired January 11, 2025 (preceding the meeting date).
b) HUD & Federal/State grants withheld and there is a lack of funding for the project;
c) [The Appellant was] not made aware or notified of the extension application reviewed at the January 28, 2025 Planning Board meeting.

II. FACTS OF CASE:

For the Zoning Board of Appeals' reference, Town staff has examined the submitted appeal and are providing general information about Case#21-070 as well as relevant codes contained in the Brunswick Zoning Ordinance.

a) Site Plan Expiration Date & Extension Requests
Section 5.2.9.Q(1) of the Brunswick Zoning Ordinance states that *"c. The applicant may, at any time before the date of expiration, make a written request to the Review Authority for a time extension. This request shall explain the reasons why the improvements or fulfillment of conditions have not been completed and indicate how the applicant expects to complete the development if the Review Authority grants a time extension."*

Section 5.2.9.Q(2) further clarifies that, *"Except when otherwise stipulated in an approved phasing plan, Site Plan approval shall expire three (3) years from date of approval, unless the applicant has submitted a written request for an approval extension no less than 14 days prior to applicable Review Authority consideration. The Review Authority may extend the expiration of an approved Site Plan."*

The Planning Department received a letter requesting the extension from the applicant on December 30, 2024, prior to the site plan's date of expiration (January 11, 2025) and more than 14 prior to the Planning Board's review that occurred on January 28, 2025. As required, the letter [Exhibit C] details the reasons for the extension request with the applicant citing fundraising to support the project as a major case for the delay. Currently, there is no requirement in the ordinance that extensions must be granted before the site plan's expiration date.

b) Financial Capacity
Section 4.16.2 of the Brunswick Zoning Ordinance states that *"B. The applicant must show documentation from an independent third-party as to applicant's financial capacity."*

When the project was reviewed by the Planning Board on January 11, 2022, the application provided a letter [Exhibit D] from Bath Savings Institution, dated November 22, 2021, indicating the applicant's financial capacity to complete the project. Currently, there is no requirement in the ordinance that extension requests must be reviewed under standards that were reviewed and approved as part of the original approval process. Staff will note that at the January 28th Planning Board meeting, the Board inquired if project funding was impacted by the federal government recently curtailing funding, and the applicant responded that they have confirmed that funding is in place for the project.

c) Public Notice
Section 5.1.3.B of the Brunswick Zoning Ordinance states that *"When an application for Development Review is received, Town staff shall notify the owners of all property as follows: …c. For all other Development Review applications, all property owners located within a 300-foot radius of the parcel…. Notification shall provide a general description of the project and location by street address and tax map and lot designation. Town staff shall mail notifications via first class mail between 15 and ten (10) days prior to a scheduled review for which it is required. If the application is for property located within an Aquifer Protection Overlay Zone, notice shall also be sent to the Brunswick and Topsham Water District. In addition, notification in digital form shall be posted on the Town's website. Failure of any property owner to receive a notice shall not necessitate another hearing or invalidate any action by the Review Authority."*

A list of abutters (within 300 feet of the subject property) was populated by Planning Staff on January 17, 2025 [Exhibit E] using the Town's Geographical Information

Systems (GIS) software. Abutter notices were sent via the United States Postal System on January 17, 2025 in accordance with 5.1.3.B. The Appellant's property falls outside the 300-foot radius, therefore she was not sent notice.

III. EXHIBITS

A. Town of Brunswick Memo for Site Plan Extension (Case# 24-076), dated January 30, 2025
B. Zoning Board of Appeals Appeal Form, dated February 4, 2025
C. Applicant Extension Request, dated December 30, 2024
D. Financial Capacity Letter, dated November 22, 2021
E. List of abutters (within 300 feet of the subject property), dated January 17, 2025
F. Case #24-076 Application Packet, dated January 28, 2025
G. January 28th, 2025 Planning Board Meeting Draft Minutes
H. Appellant Communications with Town Staff Since February 4, 2025

Town of Brunswick, Maine

DEPARTMENT OF PLANNING & DEVELOPMENT

MEMORANDUM

TO: St. Clair Associates
Tedford Housing

FROM: Matt James, Land Use Planner

DATE: January 30, 2025

SUBJECT: Tedford Site Plan Extension

At the January 28, 2025, meeting of the Brunswick Planning Board, the Board approved a request from St. Clair Associates, by unanimous vote, to extend the site plan approval for the Tedford Housing Homeless Shelter, Resource Center (Case# 21-070) until January 11, 2027.

Construction must be substantially complete by this date, or an extension request must be submitted to the Planning Board prior to the date of expiration. All agreed upon conditions of the initial approval remain in effect.

Good luck with your project,

Matt James
Land Use Planner

APPEAL

BRUNSWICK ZONING BOARD OF APPEALS

CODES ENFORCEMENT OFFICE

Town of Brunswick

85 UNION STREET
BRUNSWICK, MAINE 04011
(207) 725-6650 FAX (207) 725-6663

For Office Use
Case# 25-001
Date 2/4/25
Fee $75.00 PAID
MAP 42
LOT 8 + 11

PROPERTY ADDRESS, MAP & LOT
Map42 lot 8&11 tedford shelter 56 Thomas Point Rd

APPELLANT
NAME Jennifer Navarro
ADDRESS 90 Thomas Pt. Rd
CITY, STATE, & ZIP Brunswick, ME 04011
TELEPHONE 305 608 3167

PROPERTY OWNER ☐ SAME AS APPLICANT
NAME Tedford St Clair associates
ADDRESS 56 Thomas Pt. Rd.
CITY, STATE & ZIP Brunswick ME 04011
TELEPHONE 0000

TYPE OR APPEAL

_____ DIMENSIONAL VARIANCE (5.2.7.B(2))
_____ DIMENSIONAL VARIANCE-SINGLE FAMILY DWELLING SETBACK (5.2.7.B(3))
_____ DISABILITY VARIANCE (5.2.7.B(4))
__✓__ ALLEGED ERRONEOUS DECISION/INACTION OF PLANNING BOARD (5.2.7.A(1))
_____ ALLEGED ERRONEOUS DECISION/INACTION OF VILLAGE REVIEW BOARD (5.2.7.A(1))
_____ ALLEGED ERRONEOUS DECISION/INACTION BY CODES ENFORCMENT OFFICER (5.2.7.A(1))
_____ DIMENSIONAL VARIANCE – SHORELAND PROTECTION OVERLAY DISTRICT (5.2.7.B(6)a)
_____ DIMENSIONAL VARIANCE – FLOOD PROTECTION OVERLAY DISTRICT (5.2.7.B(6)b)

JUSTIFICATION

STATE THE SPECIFIC GROUNDS FOR THIS APPEAL
(CONTINUE ON ADDENDUM IF NECESSARY)

Was extension filed before site permit expiration?
HUD & Federal/State grants withheld, lack of funds?
I'm @ 325 feet away, conditional use 300 feet notice.
I wasn't made aware or notified of
lack of notification on tedford public notice.
site expiration 1/11/25 site expiration

APPELLANT SIGNATURE Jennifer Navarro **DATE** 2/4/25

Town of Brunswick, Maine

DEPARTMENT OF PLANNING & DEVELOPMENT

MEMORANDUM

TO: Planning Board

FROM: Julie Erdman, Director of Planning and Development

DATE: January 28, 2025

SUBJECT: Tedford Site Plan Extension

A Site Plan Approval Extension has been requested by St. Clair Associates on behalf of Tedford Housing, for Case# 21-070 Tedford Housing Homeless Shelter, Resource Center which was approved by the Planning on Board on January 11, 2022. Pursuant to 5.2.9.Q. of the Brunswick Zoning Ordinance, a letter requesting the extension was received by the Planning Department on December 30, 2024; prior to site plan's date of expiration (January 11, 2025). As required, the letter details the reason for the request with the applicant citing fundraising to support the project as the major cause for delay.

The applicant intends to make minor changes to the approved plan which are stipulated in the attached letter. These revisions have been reviewed by staff and qualify as minor modifications. The applicant has been advised that the Planning Department may proceed with review of the minor modification application if the site plan extension is granted by the Planning Board.

The Brunswick Zoning Ordinance states the review authority may extend approval of a site plan but is not specific on the time constraints, consequently I advise the Planning Board to place an expiration on the extension should it choose to approve the request. The applicant states their intention to have the project completed later this calendar year, therefore an extension of one year should be adequate to complete substantial improvements as specified in Subsection 5.2.9.Q. The site plan and final findings of fact are attached for your reference.

DRAFT MOTION
TEDFORD HOUSING HOMELESS SHELTER, RESOURCE CENTER APPROVAL EXTENSION REQUEST
CASE NUMBER: 24-076

Motion 1: That the Tedford Housing Homeless Shelter, Resource Center (Case# 21-070) Approval is extended until January 11, 2026 with the following conditions:

1. All agreed upon conditions of the initial January 11, 2022 approval remain in effect.

St.Clair Associates
Land Surveying and Civil Engineering
34 Forest Lane
Cumberland, Maine 04021

21012 December 30, 2024

Julie Erdman, Director of Planning Development
Town of Brunswick Planning and Development
85 Union Street
Brunswick, ME 04011

Request for Site Plan Approval Extension and
Request for Minor Modification
Major Development Plan & Conditional Use
Tedford Housing Building (Case # 24-020)
65 Thomas Point Road
Assessor's Map 42, Lots 8 and 11
Brunswick, ME

Dear Ms. Erdman,

On behalf of Tedford Housing, we have prepared this two-part application to seek an extension of Site Plan Approval and Minor Site Revisions to address further detailing associated with site construction. We offer the following for your review:

Request for Site Plan Approval Extension

As you know, on May 14, 2024 the Brunswick Planning Board issued a re-approval of the Conditional Use Permit for Tedford Housing's new facility on Thomas Point Road. Previously, on January 11, 2022 the Brunswick Planning Board granted unanimous approvals of a Conditional Use Permit and the Final Major Development Review for Tedford Housing on Thomas Point Road. At the time of re-approval of the Conditional Use Permit, the Site Plan Approval had not lapsed (and will not lapse until January 11, 2025) and did not require re-approval.

We are respectfully requesting that the staff and Planning Board consider this request for extension of the Applicant's Site Plan Approval (Final Major Development Review), given the fact that the building is currently under construction but will not be ready for

occupancy by the date associated with the original Site Plan Approval (January 11, 2025).

As you may be aware, subsequent to the original Approvals in 2022, the Applicant continued its Capital Campaign to raise funds to support the construction of this new facility, including pursuit of Federal funding support. The fundraising process has been lengthy but finally reached the point to allow construction to proceed this fall. However, given the timing of this process, including the time necessary to complete the Federal level reviews, the construction will not be sufficiently complete to allow building occupancy by January 11, 2025. It is anticipated that the building will be completed for occupancy in late 2025. Given this timing, we are respectfully requesting an extension of the Applicant's Site Plan Approval (Final Major Development Review).

Request for Minor Modification

In addition, we have prepared the enclosed materials in support of a proposed Minor Modification to the Tedford Housing Site Plan. We have prepared the enclosed Minor Modification Application to accompany the revised plans associated with this site.

It is our understanding that as part of this process, you will and other staff members will evaluate the materials to determine whether the proposed changes qualify for a staff-level review process, or whether the proposed changes warrant a return to the Planning Board.

It is important to note that the building's size and location on the lot have not changed, the amount of parking spaces have not changed and the driveway location has not moved. The following section describes the proposed minor modifications in further detail.

Proposed Minor Changes

- Sheet naming and numbering revisions on the Site Plan drawings:

  To support the bidding and construction process these minor revisions were made. Since the Site Plan drawings are now included in a larger construction set which includes all the drawings associated with the architectural, structural, mechanical, electrical, and plumbing drawings these naming and numbering changes were made. Additional details and clarifications have also been added to address contractor questions during

the bidding process. These changes were made to clarify and further detail the design of the site elements with no changes to the overall design intent.

- Addition of walkway to mechanical room:

  As part of the conditional use review and reapproval of the project, in May of this year, the Fire Department requested that a paved walkway be added from Thomas Point Road to the mechanical room located along the front of the building. This short, paved walkway has been added, as requested.

- Paving of walkway through rear of site:

  As you know the original Site Plan included a walkway through the rear of the site to provide pedestrian access to the abutting Walmart property. The surface of this walkway had been proposed as mulch on the previously approved plan. The Applicants have proposed that the surface of this walkway be a material that can be maintained year-round. Accordingly, the Applicants are proposing that this walkway be paved. There are no proposed changes to the route of the walkway.

- Pedestrian Scale Walkway Lighting:

  In order to facilitate safe pedestrian use of the walkway, pedestrian scale lighting has been added along the walkway through the rear of the site. An updated lighting and photometrics plan has been prepared to demonstrate compliance with the local lighting criteria. A copy of this updated lighting plan is enclosed.

- Sewer Service Revisions:

  The building's proposed sewer service has been modified to address the connection to the discharge point for the internal plumbing. In addition, when the contractor excavated the existing manhole in Thomas Point Road, it was discovered that the existing manhole structure would not allow connection at the original design invert. The invert was modified and the service slope was adjusted to accommodate this existing condition. The proposed sewer service modifications were reviewed with the Brunswick Sewer Department and found to be acceptable.

- Addition of Door at Easterly Wall:

  As part of the further detailing of the interior floor plans for the building, an egress door and threshold were added along the easterly wall. This door is located at the end of a hall in the office area and will allow an additional exit from the office area, if needed. This door is not a public access and is not available for the residents' use.

- Mechanical Unit Locations:

  As part of the detailed mechanical systems design for the building there are a series of small exterior pad mounted mechanical units that are placed along the outer edges of the building. These unit locations have been added to the plan.

- Proposed future generator pad:

  As part of the original design there was a rectangular paved area off the northeasterly edge of the parking lot. This rectangular area was intended to provide access to the previously proposed gravel wetlands in the area for maintenance. With the prior elimination of this BMP (as approved in the prior modifications in late 2023) this pad area was not being used. This paved pad has been converted to a proposed concrete pad to allow for future placement of a backup generator.

Review Criteria for Minor Changes

It is our understanding that a minor modification is allowed under certain conditions which are established in the Brunswick Zoning Ordinance in Chapter 5.2.10.B. We have addressed each of the 6 bulleted items contained in the Ordinance below. For ease of review, the criteria are shown in *italics*, along with our response, as follows:

- *Does not materially alter the layout or scale of the development or its impact on its surroundings;*

As noted above, the overall site layout and scale are not materially altered by these proposed minor changes. The building location, orientation, size and overall program elements remain as previously approved. No changes are proposed to the site entrance, parking layout and number of parking spaces.

- *Does not increase the number of lots or dwelling units;*

There are no proposed changes with regard to lots or dwelling units.

- *Does not violate provisions of any Town Ordinance;*

The proposed changes have been designed in accordance with the applicable Ordinance standards.

- *Does not reduce the effectiveness of the approved landscaping, screening, or buffering of the site;*

The proposed minor changes do not modify the provisions of landscaping, screening or buffering of the site included in the prior approved plans.

- *Does not significantly alter on-site vehicular circulation; and*

No changes are proposed to the vehicular circulation patterns on the site. The previously approved parking layout remains unchanged, no changes are proposed with regard to the driveway location or width or number of parking spaces on the site.

- *Does not significantly alter drainage patterns.*

As noted above, the proposed site changes include modifications to the walkway surface material through the rear of the site. No grading changes were made as part of this modification. As such, no changes to the overall site drainage patterns occurred. Our office also evaluated the change in impervious cover associated with the conversion of the walkway surface to pavement. This increase in impervious cover did not alter the overall curve number (CN) of the subcatchment that includes the walkway. As such, there are no anticipated increases in peak discharge for this subcatchment.

Application Materials

We have included five copies of the following materials in support of the applicant's request for an extension of the project's Site Plan Approval and Minor Modification to the previously approved Final Major Development/Conditional Use for Tedford Housing:

- Cover Letter/Project Description
- Minor Modification Application Form
- Revised Site Plan Set (including a revised Photometric Plan)

Please note that in addition to the plan information cited above, a check for the Minor Modification Application fee, in the amount of $250.00, is being delivered directly by the Applicant, under separate cover, to be included as part of this submittal package.

Closure

With the submittal of the materials listed above, we are respectfully requesting staff consideration of this request for an extension of the project's Final Major Development Review approval and approval of these proposed Minor Site Plan changes under the Brunswick Ordinance provisions for a Minor Modification to the Planning Board's prior approval for Final Major Development/Conditional Use review for this project, as described above.

As the enclosed Plans, and this letter demonstrate, the Applicant is proposing minor modifications to the site that are intended to allow the project to be constructed while still maintaining the integrity of the previously approved plans.

We are confident that you and other staff members will concur with our assessment that the enclosed Plan revisions are within the criteria for review as a Minor Modification.

We are available to meet with you if you have any additional questions as you review the enclosed materials. We look forward to hearing from you after you have had a chance to further review these requests.

We look forward to hearing from you.


Sincerely,

ST.CLAIR ASSOCIATES

Nancy J. St.Clair, P.E.
Vice President
NJS:njs

Andrew Lardie, Executive Director Tedford Housing
Danielle Triffitt, Director of Administration, Tedford Housing
Tim Schneider, Sage Stone Consulting


SITE PLAN
TEDFORD HOUSING



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.



LOCATION MAP N.T.S.

APPLICANT:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

CIVIL ENGINEER:
ST.CLAIR ASSOCIATES
34 FOREST LANE
CUMBERLAND, ME 04021

LANDSCAPE ARCHITECT:
ACETO LANDSCAPE
ARCHITECTS
LANDSCAPE
ARCHITECTURE
PORTLAND, ME

SHEET INDEX:


SHEET	DESCRIPTION
C-100	COVER SHEET
C-200	EXISTING CONDITIONS PLAN
C-300	SITE PLAN
C-400	GRADING PLAN
L1-00	LANDSCAPE PLAN
L2-00	LANDSCAPE DETAILS
L2-01	LANDSCAPE DETAILS
L3-00	PHOTOMETRICS PLAN
C-700	DETAILS
C-701	DETAILS
C-702	DETAILS
C-703	DETAILS
C-800	PRE DEVELOPMENT WATERSHED MAP
C-900	POST DEVELOPMENT WATERSHED MAP



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.



LOCATION MAP N.T.S.

GENERAL NOTES

1) THE RECORD OWNER OF THE PROPERTY IS TEDFORD HOUSING AS DESCRIBED IN A DEED RECORDED AT THE CUMBERLAND COUNTY REGISTRY OF DEEDS IN BOOK 39438 PAGE 307.

2) THE PROPERTY IS SHOWN ON THE TOWN OF BRUNSWICK TAX MAP 42 BEING SHOWN AS LOT 8.

3) THE BEARINGS AND NORTH ORIENTATION IS BASED UPON GRID NORTH, NORTH AMERICAN DATUM OF 1983 MAINE WEST ZONE. THE CONTOURS AND ELEVATIONS SHOWN HEREON ARE REFERENCED TO NORTH AMERICAN VERTICAL DATUM OF 1988.

4) PLAN REFERENCES:

A) PLAN OF STANDARD BOUNDARY SURVEY FOR C C LAND DEVELOPERS, ETAL DATED MAY 20, 1993 BY PAUL H. RUOPP JR., PLS AND RECORDED IN PLAN BOOK 194 PAGE 62.

5) THE PROPERTY SHOWN HEREON IS SUBJECT TO AND BENEFITED ALL MATTERS OF RECORD ON FILE AT THE CUMBERLAND COUNTY REGISTRY OF DEEDS.

6) ALL GRADING AND UTILITIES SHOWN HEREON ARE SCHEMATIC ONLY AND ALL PROPOSED INVERTS AND SPOT ELEVATIONS ARE SUBJECT TO CHANGE UPON FURTHER DETAILED SITE DESIGN.

7) A WETLAND DELINEATION WAS COMPLETED BY MARK HAMPTON ASSOCIATES, INC. AS STATED IN A LETTER DATED AUGUST 3, 2021. THE LETTER STATES NO WETLANDS WERE FOUND ON THE PROPERTY.

8) THE LOCATION OF EXISTING TREES 10" IN DIAMETER OR GREATER HAVE BEEN DEPICTED ON THIS SURVEY PLAN.

9) DURING THE FIELD SURVEY, DEBRIS AND TRASH WAS OBSERVED ON THE PROPERTY INCLUDING CHUNKS OF CONCRETE.

10) THIS PLAN IS BASED UPON A BOUNDARY SURVEY PERFORMED IN ACCORDANCE WITH THE STATE OF MAINE BOARD OF LICENSURE FOR PROFESSIONAL LAND SURVEYORS STANDARDS OF PRACTICE WITH THE EXCEPTION THAT NO REPORT OF SURVEY HAS BEEN PREPARED, NO NEW LEGAL DESCRIPTION HAS BEEN PREPARED AND THAT THE PROPOSED MONUMENTATION SHOWN HEREON HAS NOT BEEN SET AT THE ISSUANCE OF THIS PLAN.

SPACE & BULK REQUIREMENTS

THE PROPERTY IS LOCATED IN THE TOWN OF BRUNSWICK GROWTH MIXED-USE 4 (GM4). THE SPACE AND BULK REQUIREMENTS FOR THE GM4 ZONING DISTRICT ARE AS FOLLOWS:

	REQUIRED
MINIMUM LOT SIZE:	7,000 S.F.
MINIMUM FRONT YARD SETBACK:	0 FEET
MINIMUM SIDE YARD SETBACK:	0 FEET
MINIMUM REAR YARD SETBACK:	15 FEET
MAXIMUM BUILDING HEIGHT:	60 FEET
MAXIMUM IMPERVIOUS COVER:	80%

SOILS LEGEND

1) SOILS TYPE

LABEL	SOIL NAME	SLOPE	HYDROLOGIC SOIL GROUP
Au	AU GRES LOAMY SAND	0% TO 3% SLOPES	HSG A
Wa	WALPOLE FINE SANDY LOAM	0% TO 3% SLOPES	HSG A

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	●
	BUILDING	
	EDGE PAVEMENT	
	TRAIL	
--122--	CONTOURS	--120--
30.20	SPOT GRADE	
S	SEWER	
Ⓢ	SEWER MH	
	TREELINE	
	CULVERT	
	SOILS BOUNDARY	
OHE	OVERHEAD ELEC. & TEL.	
	UTILITY POLE	
	DECIDUOUS TREE	
	CONIFEROUS TREE	

DAVID C. ST. CLAIR, JR. 2317 PROFESSIONAL LAND SURVEYOR STATE OF MAINE

REV:	BY:	DATE:	STATUS:
E	DCS	12-30-2024	FOR TOWN REVIEW
4	DCS	05-03-2024	ASI-001
D	DCS	10-20-2023	REVISED PLAN FOR TOWN REVIEW
C	DCS	02-03-2022	CONDITIONS OF APPROVAL
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland Foreside, ME 04021
Tel (207) 829-5558


PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST

EXISTING CONDITIONS PLAN
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET C-200

21012S TAB 21012EC




GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)

1 inch = 30 ft.



LOCATION MAP N.T.S.

GENERAL NOTES

1) THE RECORD OWNER OF THE PROPERTY IS TEDFORD HOUSING AS DESCRIBED IN A DEED RECORDED AT THE CUMBERLAND COUNTY REGISTRY OF DEEDS IN BOOK 39438 PAGE 307.

2) THE PROPERTY IS SHOWN ON THE TOWN OF BRUNSWICK TAX MAP 42 BEING SHOWN AS LOT 8.

3) THE BEARINGS AND NORTH ORIENTATION IS BASED UPON GRID NORTH, NORTH AMERICAN DATUM OF 1983 MAINE WEST ZONE. THE CONTOURS AND ELEVATIONS SHOWN HEREON ARE REFERENCED TO NORTH AMERICAN VERTICAL DATUM OF 1988.

4) PLAN REFERENCES:

A) PLAN OF STANDARD BOUNDARY SURVEY FOR C C LAND DEVELOPERS, ETAL DATED MAY 20, 1993 BY PAUL H. RUOPP JR., PLS AND RECORDED IN PLAN BOOK 194 PAGE 62.

5) THE PROPERTY SHOWN HEREON IS SUBJECT TO AND BENEFITED ALL MATTERS OF RECORD ON FILE AT THE CUMBERLAND COUNTY REGISTRY OF DEEDS.

6) A WETLAND DELINEATION WAS COMPLETED BY MARK HAMPTON ASSOCIATES, INC. AS STATED IN A LETTER DATED AUGUST 3, 2021. THE LETTER STATES NO WETLANDS WERE FOUND ON THE PROPERTY.

7) THE LOCATION OF EXISTING TREES 10" IN DIAMETER OR GREATER HAVE BEEN DEPICTED ON THIS SITE PLAN.

8) THE PROPOSED DEVELOPMENT SHALL BE SERVICED BY PUBLIC WATER AND PUBLIC SEWER, AND UNDERGROUND ELECTRIC, TELEPHONE AND CABLE TV SERVICES.

9) THE TOWN OF BRUNSWICK ENGINEERING DEPARTMENT RESERVES THE RIGHT TO REQUEST ADDITIONAL WORK BEYOND WHAT IS SHOWN ON THE PLAN DUE TO UNKNOWN SITE CONDITIONS. ANY CHANGES MADE DURING CONSTRUCTION SHALL BY COORDINATED WITH THE TOWN OF BRUNSWICK ENGINEERING DEPARTMENT.

10) A PRECONSTRUCTION MEETING IS REQUIRED BEFORE START OF CONSTRUCTION. THE MEETING SHALL INCLUDE APPROPRIATE TOWN STAFF, THE DEVELOPER AND HIS CONTRACTOR, AND UTILITY COMPANY REPRESENTATIVES. ANY PLAN REVISIONS REQUIRED AS A RESULT OF THE MEETING SHALL BE PROVIDED TO ALL PARTIES ASSOCIATED WITH THE PROJECT.

11) THE PROPERTY SHOWN ON THE APPROVED SITE PLAN MAY BE DEVELOPED AND USED ONLY AS SHOWN ON THE PLAN. ALL ELEMENTS AND FEATURES OF THE PLAN AND ALL REPRESENTATIONS MADE BY THE APPLICANT WHICH APPEAR IN THE RECORD OF THE PLANNING BOARD PROCEEDINGS ARE CONDITIONS OF APPROVAL. NO CHANGE FROM THE CONDITIONS OF APPROVAL IS PERMITTED UNLESS AN AMENDED SITE PLAN IS APPROVED BY THE PLANNING BOARD.

12) ALL POLE MOUNTED AND BUILDING MOUNTED LIGHT FIXTURES SHALL BE EQUIPPED WITH PHOTOCELLS THAT CONTROL THE SITE LIGHTING TO TURN ON AT DUSK AND WILL DIM AT 7 PM. ONLY SECURITY LIGHTING WILL REMAIN ON OVERNIGHT. ALL LIGHTING WILL TURN OFF AT DAWN.

13) SNOW STORAGE IS ONLY ALLOWED IN THE DESIGNATED AREAS SHOWN HEREON. SNOW STORAGE MAY NEED TO BE REMOVED FROM THE SITE AS NECESSARY. NO SNOW STORAGE IS ALLOWED IN STORMWATER MANAGEMENT STRUCTURES.

14) SEE LANDSCAPE ARCHITECT PLANS, RE: L100 FOR ANY PLANTING/ SEEDING AREA, INCLUDING GRAVEL WETLAND BASIN.

SPACE & BULK REQUIREMENTS

THE PROPERTY IS LOCATED IN THE TOWN OF BRUNSWICK GROWTH MIXED-USE 4 (GM4). THE SPACE AND BULK REQUIREMENTS FOR THE GM4 ZONING DISTRICT ARE AS FOLLOWS:

	REQUIRED	PROPOSED
MINIMUM LOT SIZE:	7,000 S.F.	133,075 S.F.
MINIMUM FRONT YARD SETBACK:	0 FEET	25 FEET
MINIMUM SIDE YARD SETBACK:	0 FEET	26.7 FEET
MINIMUM REAR YARD SETBACK:	15 FEET	106.16 FEET
MAXIMUM BUILDING HEIGHT:	60 FEET	1 STORY
MAXIMUM IMPERVIOUS COVER:	80%	28.34%
PROPOSED IMPERVIOUS SURFACE: (ONSITE BUILDING & PAVEMENT)		37,724 S.F.
PROPOSED IMPERVIOUS SURFACE: (OFFSITE BETWEEN ROW & THOMAS POINT RD)		837 S.F
TOTAL PROPOSED IMPERVIOUS SURFACE:		39,951 S.F.
TOTAL LANDSCAPE AREA:		52,608 S.F.
PROPOSED DEVELOPED AREA:		91,294 S.F.

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	
	BUILDING	
	EDGE PAVEMENT	
	EDGE OF GRAVEL	
	RAMP	R
--122-- --120--	CONTOURS	
30.20	SPOT GRADE	+30.20
-S-	SEWER	-S-
	SEWER MH	
	UNDERDRAIN	UD
	CATCH BASIN	
	UNDERGROUND ELEC. & TEL.	UGT/E
OHE	OVERHEAD ELEC. & TEL.	
	UTILITY POLE	
	GATE VALVE	
	HYDRANT	
	TREELINE	
	DECIDUOUS TREE	X
	CONIFEROUS TREE	X

REV:	BY:	DATE:
E	DCS	05-03-2024
4	DCS	03-26-2024
3	DCS	10-20-2023
D	DCS	05-05-2022
2	DCS	05-05-2022
1	DCS	02-03-2022
C	DCS	11-23-2021
B	DCS	10-05-2021
A	DCS	12-30-2024

STATUS: FOR TOWN REVIEW

ASI 001 CHANGE TRAIL MATERIAL TO PAVEMENT
ADD DOOR, ADJUST HVAC UNIT & SIDEWALK MATERIAL
REVISED PLAN FOR TOWN REVIEW
UPDATE GRADING
MOVE TRANSFORMER PAD, ADD HVAC PADS
CONDITIONS OF APPROVAL
FOR TOWN REVIEW
FOR TOWN REVIEW

THIS PLAN, SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

STATE OF MAINE — NANCY J. ST. CLAIR No. 6877 — REGISTERED LAND SURVEYOR — 12/30/2024

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland Foreside, ME 04021
Tel (207) 829-5558


PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST

SITE PLAN
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET C-300

21012S TAB 21012S



GENERAL NOTES

1) THE CONTRACTOR SHALL REVIEW AND FAMILIARIZE THEMSELVES WITH ALL THE GENERAL NOTES AND CONSTRUCTION NOTES WITHIN THE DESIGN PLAN SHEETS AND DETAILS SHEET OF THIS DESIGN PLAN SET.
2) THE PROPOSED STORMDRAIN PIPES SHALL BE HDPE SMOOTHBORE OR APPROVED EQUAL.
3) PROVIDE 2" RIGID STYROFOAM INSULATION IN ALL AREAS WHERE DEPTH OF COVER IS LESS THAN 4'.
4) UNLESS OTHERWISE NOTED, THE LIGHT POLES SHALL BE NO HIGHER THAN 12-FEET TO 16-FEET HIGH.
5) INSTALL INLET PROTECTION IN ALL CATCH BASIN AND STORM DRAIN INLETS.
6) PER ADA REQUIREMENTS, ALL BARRIER FREE PARKING SPACES AND ACCESS AISLES SHALL BE CONSTRUCTED WITH NO MORE THAN 2% SLOPES IN ANY DIRECTION. ANY CONFLICTS TO THIS REQUIREMENT AS A RESULT OF FIELD CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN ENGINEER FOR REVIEW AND FURTHER EVALUATION.
7) PER ADA REQUIREMENTS, ALL SIDEWALKS SHALL HAVE A MAXIMUM RUNNING SLOPE OF 5% WITH A MAXIMUM OF A 2% CROSS SLOPE. HANDICAP RAMPS SHALL NOT EXCEED A 1 IN 12 SLOPE (8.33%), WITH A 5 FOOT LONG LANDING AT EACH END. LANDING SLOPE SHALL NOT EXCEED 2%.
8) CONTRACTOR SHALL REFER TO THE LATEST APPLICABLE VERSION OF THE ADA REQUIREMENTS FOR ADDITIONAL INFORMATION.
9) WATER MAINS 4-INCH OR GREATER IN DIAMETER SHALL BE DUCTILE IRON, CLASS 52.
10) MINIMUM DEPTH OF COVER OVER WATER MAIN SHALL BE 5'-0"
11) MAINTAIN 10-FEET HORIZONTAL SEPARATION FROM SEWER AND GAS PIPELINES.
12) INSULATE WATER MAIN PIPE TRENCH WHERE MAIN CROSSES OR IS LOCATED WITHIN 5 FEET OF CULVERTS AND DRAINS.
13) WATER MAINS HAVING HYDRANT BRANCHES SHALL BE 8-INCH MINIMUM DIAMETER.
14) BLOWOFF SIZE SHALL BE 2-INCH FOR MAINS 4-INCHES OR LARGER IN DIAMETER.
15) DOMESTIC WATER SERVICE SHALL MEET THE BRUNSWICK & TOPSHAM WATER DISTRICT STANDARDS.
16) WATER MAIN MATERIALS SHOULD BE PURCHASED FROM THE BRUNSWICK & TOPSHAM WATER DISTRICT TO ENSURE MATERIALS MEET SPEC.
17) ALL FITTINGS, VALVES, BLOW OFFS AND HYDRANTS SHALL BE RESTRAINED.
18) SEE LANDSCAPE ARCHITECT PLANS, RE: L100 FOR ANY PLANTING/ SEEDING AREA, INCLUDING GRAVEL WETLAND BASIN.

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	
	BUILDING	
	EDGE PAVEMENT	
	EDGE OF GRAVEL	
--122--	CONTOURS	124
30.20	SPOT GRADE	+30.20
S	SEWER	S
Ⓢ	SEWER MH	Ⓢ
	UNDERDRAIN	UD
	UNDERGROUND ELEC. & TEL.	UGT/E
SD	STORM DRAIN	SD
	CATCH BASIN	
	GATE VALVE	
	HYDRANT	
	TREELINE	
	DECIDUOUS TREE	X
	CONIFEROUS TREE	X
	EC. BLANKET	
	FILTER BARRIER	FB
	RIPRAP	

GRAPHIC SCALE
30 0 15 30 60 120
(IN FEET)
1 inch = 30 ft.

REV:	BY:	STATUS:
G	DCS	12-30-2024 FOR TOWN REVIEW
4	DCS	05-03-2024 ASI-001 ADD TRASHTRACKS (2) OUTLETS, CHANGE TRAIL SURFACE TO PAVEMENT, ADD WALK TO SPRINKLER ROOM
3	DCS	03-26-2024 ADD DOOR, ADJUST HVAC UNIT & SIDEWALK ENTRANCE LOCATION
F	DCS	11-28-2023 REVISE GRADING AT DUMPSTER
E	DCS	10-20-2023 REVISED PLAN FOR TOWN REVIEW
2	DCS	06-29-2023 UPDATED SITE GRADING
1	DCS	05-05-2022 MOVE TRANSFORMER PAD, ADD HVAC PADS
D	DCS	02-03-2022 CONDITIONS OF APPROVAL
C	DCS	12-29-2021 REVISED PER CCSWCD COMMENTS
B	DCS	11-23-2021 FOR TOWN REVIEW
A	DCS	10-05-2021 FOR TOWN REVIEW

STATE OF MAINE
NANCY J. ST. CLAIR
No. 6877
REGISTERED PROFESSIONAL ENGINEER
12/30/2024

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland Foreside, ME 04021
Tel (207) 829-5558

PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012		DCS	DCS	NST
	ELECT.			


THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

GRADING & UTILITY PLAN
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET C-400

21012S TAB 21012G



NOTES:

1. BUFFERING ALONG WESTERLY PROPERTY LINE SHALL INCLUDE 5' TALL GREEN GIANT ARBORVITAE OR EQUIVALENT. ARBORVITAE SHALL BE MIXED WITH MINIMUM OF 2 ADDITIONAL COMPATIBLE PLANT SPECIES TO ADD DIVERSITY IN FORM AND/OR COLOR. ALL PLANTINGS SHALL BE DEER-RESISTANT. TYPICAL PLANT/GROUPING SPACING SHALL BE PER PLAN.
2. ALL PLANTING AND SEEDING SHOULD RECEIVE REGULAR WATERING FOR ESTABLISHMENT; ONE YEAR (FOR SEEDING) TWO YEARS MIN. (FOR SHRUBS AND TREES).

SITE FURNISHINGS SCHEDULE

QTY.	DESCRIPTION	VENDOR*
8	BENCH	SEE SHT. L2-00
4	BICYCLE RACK	SEE SHT. L2-00

*OR APPROVED EQUAL

PLANT SCHEDULE

SYMBOL	ABBR.	BOTANICAL NAME	COMMON NAME	QTY	SIZE	SPACING
TREES						
	AR	ACER RUBRUM 'KARPICK'	RED MAPLE	04	3" CAL	PER PLAN
	QR	QUERCUS RUBRA	NORTHERN RED OAK	19	3" CAL	PER PLAN
	BPW	BETULA POPULIFOLIA 'WHITESPIRE'	GRAY BIRCH (MULTI STEM)	17	10-12' B&B	PER PLAN
	AB	ABIES BALSAMEA	BALSAM FIR	06	8'-10' HEIGHT	PER PLAN
	TP	THUJA PLICATA 'GREEN GIANT'	GREEN GIANT ARBORVITAE	25	5' MIN. HT.	PER PLAN
	PM	PINUS MUGO	MUGO PINE	20	5' MIN. HT.	PER PLAN
	PS	PINUS STROBUS	EASTERN WHITE PINE	11	6-7' MIN.	PER PLAN
SHRUBS						
	AM	ARONIA MELANOCARPA 'LOW SCAPE MOUND'	LOW BLACK CHOKEBERRY	185	#3	PER PLAN
	CS	CORUS SERICEA	RED TWIG DOGWOOD	94	#5	PER PLAN
	DKO	DIERVILLA 'KODIAK ORANGE'	BUSH HONEYSUCKLE	59	#5	PER PLAN
	RA	RHUS AROMATICA	GRO LOW SUMAC	60	#2	PER PLAN
ORNAMENTAL GRASSES & PERENNIALS						
	CA	CALAMAGROSTIS X ACUTIFLORA 'KARL FOERSTER'	FEATHER REED GRASS	125	#1	30" O.C.
	PV	PANICUM VIRGATUM 'SHENANDOAH'	SWITCH GRASS	470	#1	30" O.C.
	SS	SCHIZACHYRIUM SCOPARIUM 'PRAIRIE BLUES'	LITTLE BLUESTEM	65	#1	24" O.C.

SEED MIXES

LAWN (SEED MIX) (WILDFLOWER FARM'S ECO-LAWN GRASS SEED)
TOTAL AREA : +/- 4,700 SQ FT
ECO-LAWN IS A DROUGHT-RESISTANT GRASS THAT REQUIRES MOWING ONLY ONCE PER MONTH. EACH 5 POUND BAG OF SEED COVERS 1,000 SQUARE FEET. A THICK HEALTHY LAWN IS THE BEST DEFENCE AGAINST WEEDS, DISEASE, DROUGHT AND INSECT DAMAGE.

GROUP 'A' (SUBMERGENT ZONE)
NEW ENGLAND WETMIX (WETLAND SEED MIX)
SUPPLIER: NEW ENGLAND WETLAND PLANT, INC.
TOTAL AREA : +/- 3,300 SQ FT
APPLICATION RATE 18 LBS/ACRE | 2500 SQ FT/LB
SPECIES: FOX SEDGE (CAREX VULPINOIDEA), LURID SEDGE (CAREX LURIDA), BLUNT BROOM SEDGE (CAREX SCOPARIA), BLUE VERVAIN (VERBENA HASTATA), FOWL BLUEGRASS (POA PALUSTRIS), HOP SEDGE (CAREX LUPULINA), GREEN BULRUSH (SCIRPUS ATROVIRENS), CREEPING SPIKE RUSH (ELEOCHARIS PALUSTRIS), FRINGED SEDGE (CAREX CRINITA), SOFT RUSH (JUNCUS EFFUSUS), SPOTTED JOE PYE WEED (EUPATORIUM MACULATUM), RATTLESNAKE GRASS (GLYCERIA CANADENSIS), SWAMP ASTER (ASTER PUNICEUS), BLUEFLAG (IRIS VERSICOLOR), SWAMP MILKWEED (ASCLEPIAS INCARNATA), SQUARE STEMMED MONKEY FLOWER (MIMULUS RINGENS).

GROUP 'B' (RESTORATION ZONE)
NEW ENGLAND CONSERVATION/WILDLIFE MIX
SUPPLIER: NEW ENGLAND WETLAND PLANT, INC.
TOTAL AREA : +/- 20,000 SQ FT
APPLICATION RATE : 25LBS/ACRE | 1750 SQ FT/LB
SPECIES: SPECIES: VIRGINIA WILD RYE (ELYMUS VIRGINICUS), LITTLE BLUESTEM (SCHIZACHYRIUM SCOPARIUM), BIG BLUESTEM (ANDROPOGON GERARDII), RED FESCUE (FESTUCA RUBRA), SWITCH GRASS (PANICUM VIRGATUM), PARTRIDGE PEA (CHAMAECRISTA FASCICULATA), PANICLEDLEAF TICK TREFOIL (DESMODIUM PANICULATUM), INDIAN GRASS (SORGHASTRUM NUTANS), BLUE VERVAIN (VERBENA HASTATA), BUTTERFLY MILKWEED (ASCLEPIAS TUBEROSA), BLACK EYED SUSAN (RUDBECKIA HIRTA), COMMON SNEEZEWEED (HELENIUM AUTUNALE), HEATH ASTER (ASTERPILOSUS/SYMPHYOTRICHUM PILOSUM), EARLY GOLDENROD (SOLIDAGO JUNCEA), UPLAND BENTGRASS (AGROSTIS PERENNANS).

ACETO LANDSCAPE ARCHITECTS
207 221 3390 | ACETOLA.COM

SEAL

PROJECT TITLE

TEDFORD HOUSING
THOMAS POINT ROAD
BRUNSWICK, ME

PREPARED FOR

OWNER:

TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

REVISIONS | DATE

ISSUE DATE


CONSTRUCTION SET
MAY03, 2024

SHEET TITLE


LANDSCAPE PLAN

SHEET INFORMATION

L 1-00



2 BICYCLE RACK X.X
NTS





5 PRIVACY FENCE 6.2
NTS

627 Amersale Drive
Naperville, IL 60563
Phone: (800) 323-5664
sales@belson.com

Model # PBSC-6-W **Dimension Sheet**

PALISADE WOOD BENCH





www.belson.com

2 BENCH X.X
NTS

ACETO LANDSCAPE ARCHITECTS
207 221 3390 | ACETOLA.COM

SEAL

PROJECT TITLE

TEDFORD HOUSING
THOMAS POINT ROAD
BRUNSWICK, ME

PREPARED FOR

OWNER:

TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

REVISIONS DATE

ISSUE DATE


MAY 03, 2024

SHEET TITLE

LANDSCAPE
DETAILS

SHEET INFORMATION


L 2-00



1 DECIDUOUS TREE PLANTING

1":1'-0"

9.1




NOTES:
EVERGREEN PLANT MATERIAL SHOULD BE TREATED WITH "AGRI-GEL" (OR EQUIVALENT APPROVED BY LANDSCAPE ARCHITECT). DIP TREE ROOTS BEFORE PLANTING.

2 EVERGREEN TREE PLANTING

1":1'-0"


9.2



4 PERENNIAL & GRASS PLANTING

1":1'-0"

9.4



3 SHRUB PLANTING

1":1'-0"

9.3

NOTES:
1. ALL PLANTING AND SEEDING SHOULD RECEIVE REGULAR WATERING FOR ESTABLISHMENT; ONE YEAR (FOR SEEDING) TWO YEARS MIN. (FOR TREES).
2. TREES OUTSIDE OF IRRIGATION ZONES TO BE INSTALLED WITH DRIP IRRIGATION BAGS (BY GEWITT, TREEGATOR, OR APPROVED EQUAL) PER MANUFACTURER'S INSTRUCTIONS. CONTRACTOR AND/OR MAINTENANCE SHALL FILL BAGS AS OFTEN AS NECESSARY TO PREVENT FROM BEING EMPTIED.

ACETO LANDSCAPE ARCHITECTS
207 221 3390 | ACETOLA.COM

SEAL

PROJECT TITLE

TEDFORD HOUSING
THOMAS POINT ROAD
BRUNSWICK, ME

PREPARED FOR

OWNER:

TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

REVISIONS DATE

ISSUE DATE


CONSTRUCTION SET
MAY 03, 2024

SHEET TITLE

LANDSCAPE DETAILS


SHEET INFORMATION

L 2-01



Luminaire Schedule							
Symbol	Qty	Label	Mounting Height	LLF	Lum. Lumens	Lum. Watts	Description
	3	A4	25' - 0" ADF	0.900	21357	150	VP-2-320L-145-3K7-4W
	15	BO	3' - 6" AFG	0.900	1468	45	FN1-24LU-3K-DB
	2	DL	8' - 0" AFG	0.900	1030	12	LTR-4RD-H-SL10L-DM1_LTR-4RD-T-SL35K8XWS

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
Overall Area	Illuminance	Fc	0.35	13.7	0.0	N.A.	N.A.
Parking Lot	Illuminance	Fc	2.12	4.0	0.3	7.07	13.33



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)

1 inch = 30 - FT.

1. THIS LIGHTING DESIGN IS BASED ON LIMITED INFORMATION SUPPLIED BY OTHERS TO CURRENT LIGHTING. SITE DETAILS PROVIDED HEREON ARE REPRODUCED ONLY AS A VISUALIZATION AID. FIELD DEVIATIONS MAY SIGNIFICANTLY AFFECT PREDICTED PERFORMANCE. PRIOR TO INSTALLATION, CRITICAL SITE INFORMATION (POLE LOCATIONS, ORIENTATION, MOUNTING HEIGHT, ETC.) SHOULD BE COORDINATED WITH THE CONTRACTOR AND/OR SPECIFIER RESPONSIBLE FOR THE PROJECT.
2. LUMINAIRE DATA IS TESTED TO INDUSTRY STANDARDS UNDER LABORATORY CONDITIONS. OPERATING VOLTAGE AND NORMAL MANUFACTURING TOLERANCES OF LAMP, BALLAST, AND LUMINAIRE MAY AFFECT FIELD RESULTS.
3. CONFORMANCE TO FACILITY CODE AND OTHER LOCAL REQUIREMENTS IS THE RESPONSIBILITY OF THE OWNER AND/OR THE OWNER'S REPRESENTATIVE.

TITLE:

TEDFORD

BRUNSWICK, ME

SITE PHOTOMETRIC PLAN

REVISED FROM DRAWING NUMBER(S):	

DN BY: DHK	DATE: 11/24/21	CHK BY: N/A
REV. BY:	DATE:	SCALE: AS NOTED
QUOTE: N/A	DRAWING / DESIGN NO.: A240941	

EROSION & SEDIMENTATION CONTROL

BASIC STANDARDS - EROSION CONTROL MEASURES

THIS PLAN IDENTIFIES THE MINIMUM EROSION CONTROL MEASURES THAT SHALL BE IMPLEMENTED ON THIS SITE. THE CONTRACTOR WILL BE RESPONSIBLE TO MAINTAIN ALL COMPONENTS OF THE EROSION CONTROL PLAN UNTIL THE SITE IS FULLY STABILIZED. HOWEVER, BASED ON SITE AND WEATHER CONDITIONS DURING CONSTRUCTION, ADDITIONAL EROSION CONTROL MEASURES MAY NEED TO BE IMPLEMENTED. ALL AREAS OF INSTABILITY AND EROSION SHALL BE REPAIRED IMMEDIATELY DURING CONSTRUCTION AND SHALL BE MAINTAINED UNTIL THE SITE IS FULLY STABILIZED OR VEGETATION IS ESTABLISHED. THE CONTRACTOR SHALL MAINTAIN A CONSTRUCTION LOG TO DOCUMENT ALL EROSION AND SEDIMENTATION CONTROL INSPECTIONS AND MAINTENANCE AND REPAIRS.

A. POLLUTION PREVENTION AND GENERAL HOUSEKEEPING

1. MINIMIZATION OF EXPOSED SOIL AREAS: IN ORDER TO PROTECT DOWNGRADIENT AREAS AND BUFFERS, AND TO AVOID POTENTIAL EROSION OF ANY OPEN DRAINAGE CHANNELS, SWALES, OR OTHER NATURAL RESOURCES, THE CONTRACTOR SHALL SEQUENCE AND PHASE EARTHWORKS OPERATIONS TO LIMIT THE AMOUNT OF SITE DISTURBANCE AND/OR EXPOSED SOIL TO ONLY THOSE AREAS NECESSARY TO EFFECTIVELY CONSTRUCT THE PROPOSED IMPROVEMENTS. TO THE EXTENT PRACTICABLE, THE CONTRACTOR SHALL RETAIN NATURAL COVER, AND PERMANENTLY STABILIZE AREAS AS SOON AS EARTHWORKS ARE COMPLETED. LESS EXPOSED SOIL RESULTS IN FEWER EROSION CONTROLS TO INSTALL AND MAINTAIN. IF WORK WITHIN AN AREA IS NOT ANTICIPATED TO BEGIN WITHIN TWO WEEKS TIME, THE CONTRACTOR SHALL CONSIDER LEAVING THE AREA IN ITS NATURALLY EXISTING COVER.
2. SPILL PREVENTION: CONTROLS MUST BE USED TO PREVENT POLLUTANTS FROM BEING DISCHARGED FROM MATERIALS ON SITE, INCLUDING STORAGE PRACTICES TO MINIMIZE EXPOSURE OF THE MATERIALS TO STORMWATER, AND APPROPRIATE SPILL PREVENTION, CONTAINMENT, AND RESPONSE PLANNING AND IMPLEMENTATION.
3. GROUNDWATER PROTECTION: DURING CONSTRUCTION, LIQUID PETROLEUM PRODUCTS AND OTHER HAZARDOUS MATERIALS WITH THE POTENTIAL TO CONTAMINATE GROUNDWATER MAY NOT BE STORED OR HANDLED IN AREAS OF THE SITE DRAINING TO AN INFILTRATION AREA. AN "INFILTRATION AREA" IS ANY AREA OF THE SITE THAT BY DESIGN OR AS A RESULT OF SOILS, TOPOGRAPHY AND OTHER RELEVANT FACTORS ACCUMULATES RUNOFF THAT INFILTRATES INTO THE SOIL. DIKES, BERMS, SUMPS, AND OTHER FORMS OF SECONDARY CONTAINMENT THAT PREVENT DISCHARGE TO GROUNDWATER MAY BE USED TO ISOLATE PORTIONS OF THE SITE FOR THE PURPOSES OF STORAGE AND HANDLING OF THESE MATERIALS.
4. FUGITIVE SEDIMENT AND DUST: ACTIONS MUST BE TAKEN TO ENSURE THAT ACTIVITIES DO NOT RESULT IN NOTICEABLE EROSION OF SOILS OR FUGITIVE DUST EMISSIONS DURING OR AFTER CONSTRUCTION. OIL MAY NOT BE USED FOR DUST CONTROL. FOR OPERATIONS DURING WET MONTHS, THE CONTRACTOR SHALL SWEEP ROADWAYS OR PAVED AREAS AT LEAST ONCE A WEEK AND PRIOR TO SIGNIFICANT STORM EVENTS TO AVOID TRACKING OF MUD OFF THE SITE. WHERE CHRONIC MUD TRACKING OCCURS, A STABILIZED CONSTRUCTION ENTRANCE SHALL BE PROVIDED. FOR OPERATIONS DURING DRY MONTHS, THAT EXPERIENCE FUGITIVE DUST PROBLEMS, THE CONTRACTOR SHALL WET DOWN THE ACCESS ROADS WITH WATER ONCE A WEEK OR MORE FREQUENTLY, AS NEEDED.
5. DEBRIS AND OTHER MATERIALS: LITTER, CONSTRUCTION DEBRIS, AND CHEMICALS EXPOSED TO STORMWATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE.
6. NON-STORMWATER DISCHARGES: IDENTIFY AND PREVENT CONTAMINATION BY NON-STORMWATER DISCHARGES.

B. STRUCTURAL AND NON-STRUCTURAL MEASURES

1. SEDIMENT BARRIERS: PRIOR TO SOIL DISTURBANCE, THE CONTRACTOR SHALL PROPERLY INSTALL SEDIMENT BARRIERS ACROSS OR AT THE TOE OF A SLOPE AND AT THE DOWNGRADIENT EDGE OF ANY DISTURBED AREA. SEDIMENT BARRIERS SHALL BE INSTALLED IN LOCATIONS WHERE SEDIMENTATION MAY REDUCE THE CAPACITY OF STORMDRAIN SYSTEMS, UPSTREAM OF ADJACENT WETLANDS AND WATERCOURSES, AND OTHER AREAS THAT MAY BE AFFECTED BY SEDIMENT. SEDIMENT BARRIERS SHALL NOT BE USED IN AREAS OF CONCENTRATED FLOWS. SEDIMENT BARRIERS MAY BE SILT FENCE, OR A BERM OF EROSION CONTROL MIX, OR OTHER APPROVED FILTER MATERIALS.
   a. SILT FENCE: SILT FENCE IS GENERALLY A BETTER FILTER THAN HAY BALE BARRIERS. SILT FENCES CAN BE USED FOR 60 DAYS OR LONGER DEPENDING ON MANUFACTURER'S RECOMMENDATIONS. PROPER INSTALLATION OF SILT FENCE IS CRITICAL TO ITS FUNCTION (SEE DETAIL).
   b. EROSION CONTROL MIX BERMS: EROSION CONTROL MIX CAN BE MANUFACTURED ON OR OFF THE PROJECT SITE. EROSION CONTROL MIX SHALL CONTAIN A WELL-GRADED MIXTURE OF PARTICLE SIZES AND MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER. THE MIX COMPOSITION SHALL MEET THE MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION STANDARDS FOR ORGANIC MATTER AND PARTICLE SIZE BY WEIGHT, SOLUBLE SALTS AND pH LEVELS. EROSION CONTROL MIX MUST BE FREE OF REFUSE, CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH. THE EROSION CONTROL MIX BERM MUST BE PLACED ALONG A RELATIVELY LEVEL CONTOUR. CUT TALL GRASSES OR WOODY VEGETATION TO AVOID CREATING VOIDS AND BRIDGES THAT WOULD ENABLE FINES TO WASH UNDER THE BARRIER.
   c. CONTINUOUS CONTAINED BERMS (FILTER SOCK): A FILTER SOCK CAN BE INSTALLED. IN AREAS WHERE TRENCHING IS NOT FEASIBLE SUCH AS OVER FROZEN GROUND OR OVER PAVEMENT. A VEHICLE CAN EVEN PASS OVER IT.
   d. INSPECTION AND MAINTENANCE OF SEDIMENT BARRIERS: SEDIMENT BARRIERS ARE EFFECTIVE ONLY IF INSTALLED AND MAINTAINED PROPERLY. IF THERE IS EVIDENCE OF END FLOW ON PROPERLY INSTALLED BARRIERS, THE CONTRACTOR SHALL EXTEND BARRIERS UPHILL OR REPLACE THEM WITH TEMPORARY CHECK DAMS. THE CONTRACTOR SHALL INSPECT SEDIMENT BARRIERS IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. THEY SHALL BE REPAIRED BY THE CONTRACTOR IMMEDIATELY IF THERE ARE ANY SIGNS OF EROSION OR SEDIMENTATION BELOW THEM. IF THERE ARE SIGNS OF UNDERCUTTING AT THE CENTER OR THE EDGES OF THE BARRIER, OR IMPOUNDING OF LARGE VOLUMES OF WATER BEHIND THEM, SEDIMENT BARRIERS SHALL BE REPLACED WITH A TEMPORARY CHECK DAM. SHOULD THE FABRIC ON A SILT FENCE OR FILTER BARRIER DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL IS NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY. SEDIMENT BARRIERS SHALL BE REMOVED AFTER EACH STORM EVENT. SEDIMENT DEPOSITS SHALL BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER. FILTER BERMS SHOULD BE RESHAPED AS NEEDED. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED. THE CONTRACTOR SHALL MAINTAIN THE SEDIMENT BARRIERS UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED. SEDIMENT BARRIERS SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREAS HAVE BEEN PERMANENTLY STABILIZED.

2. TEMPORARY CHECK DAMS: MAY BE CONSTRUCTED OF EITHER STONE OR CONTAINED BERMS OF EROSION CONTROL MIX. TEMPORARY CHECK DAMS ALSO MAY TRAP SMALL AMOUNTS OF SEDIMENT BUT SHALL NOT BE USED IN PLACE OF SEDIMENT BARRIERS. THE DAM SHALL BE LEFT IN PLACE PERMANENTLY TO AVOID UNNECESSARY DISTURBANCE OF THE SOIL DURING REMOVAL. IF IT IS NECESSARY TO REMOVE A STONE CHECK DAM FROM A GRASS-LINED CHANNEL, WHICH WILL BE MOWED, THE CONTRACTOR SHALL ENSURE THAT ALL STONES ARE REMOVED, INCLUDING ANY STONES WASHED DOWNSTREAM.
   a. SIZING AND PLACEMENT: THE MAXIMUM HEIGHT OF THE CHECK DAM SHALL BE 2 FEET. THE CENTER OF THE CHECK DAM MUST BE AT LEAST 6 INCHES LOWER THAN THE OUTER EDGES. THE MAXIMUM SPACING BETWEEN THE DAMS SHALL BE SUCH THAT THE TOE OF THE UPSTREAM DAM IS AT THE SAME ELEVATION AS THE TOP OF THE DOWNSTREAM DAM. CHECK DAMS SHALL BE INSTALLED BEFORE RUNOFF IS DIRECTED TO THE SWALE OR DRAINAGE DITCH. STONE SHALL BE INSTALLED OF 2 TO 3 INCH STONE. HAND OR MECHANICAL PLACEMENT IS NECESSARY TO PROPERLY INSTALL (SEE DETAIL). THE CONTRACTOR SHALL PROPERLY INSTALL CHECK DAMS TO AVOID UNDERCUTTING AND BYPASS OF THE FLOW AROUND THE ENDS OF THE CHECK DAMS.
   b. INSPECTIONS AND MAINTENANCE: THE CONTRACTOR SHALL MAKE REGULAR INSPECTIONS TO ENSURE THAT THE CENTER OF THE DAM IS LOWER THAN THE EDGES. EROSION CAUSED BY HIGH FLOWS AROUND THE EDGES OF THE DAM SHALL BE CORRECTED IMMEDIATELY. IF EVIDENCE OF SILTATION IN THE WATER IS APPARENT DOWNSTREAM FROM THE CHECK DAM, THE CHECK DAM SHALL BE INSPECTED AND ADJUSTED IMMEDIATELY. CHECK DAMS SHALL BE CHECKED FOR SEDIMENT ACCUMULATION AFTER EACH SIGNIFICANT RAINFALL. SEDIMENT MUST BE REMOVED WHEN IT REACHES ONE HALF OF THE ORIGINAL HEIGHT OR BEFORE. IF IT IS POSSIBLE, LEAVE THE DAM IN PLACE PERMANENTLY. THE STONE MAY BE SPREAD ALONG THE DITCH INVERT TO PROVIDE ADDITIONAL PROTECTION.

3. STABILIZED CONSTRUCTION ENTRANCE/EXIT: PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL INSTALL A STABILIZED CONSTRUCTION ENTRANCE/EXIT AT ALL POINTS OF ACCESS TO THE EXISTING ROAD. THIS AREA SHALL CONSIST OF A STABILIZED PAD OF AGGREGATE UNDERLAIN WITH FILTER FABRIC. THE CONTRACTOR SHALL MONITOR PAVEMENT EDGES TO FOR CRACKING OR RAVELING OF THE EXISTING PAVEMENT EDGE IN THE AREA OF ANY UNPROTECTED ENTRANCE. IF THE EXISTING PAVEMENT EDGE SHOWS SIGNS OF IMPACT, THEN THE STABILIZED CONSTRUCTION EXIT SHALL BE USED FOR ALL ENTERING AND EXITING CONSTRUCTION VEHICLES. WOVEN OR NONWOVEN GEOTEXTILE FABRIC SHALL BE PLACED OVER THE ENTIRE AREA TO BE COVERED WITH AGGREGATE. THE STABILIZED CONSTRUCTION ENTRANCE/EXIT SHALL CONSIST OF A 10' WIDE (MINIMUM) BY 50' LONG (MINIMUM) 6" THICK PAD OF 2"-3" STONE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT. THE PAD SHALL EXTEND THE FULL WIDTH OF POINTS WHERE INGRESS OR EGRESS OCCURS. THE EXIT SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. WHEN THE STABILIZED PAD BECOMES INEFFECTIVE, THE STONE SHALL BE REMOVED ALONG WITH THE COLLECTED SOIL MATERIAL AND REDISTRIBUTED ON SITE IN A STABLE MANNER. A NEW ENTRANCE SHALL BE RECONSTRUCTED. THE CONTRACTOR SHALL SWEEP OR WASH PAVEMENT AT EXITS, WHICH HAVE EXPERIENCED MUD-TRACKING ON TO THE PAVEMENT OR TRAVELED WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH AGGREGATE, WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING STORM DRAINS, DITCHES, OR WATERWAYS.

4. SOIL STOCKPILES:

STOCKPILES OF SOIL OR SUBSOIL SHALL BE MULCHED WITH HAY OR STRAW AT A RATE OF 75 LBS/1,000 S.F. (1.5 TONS PER ACRE) OR WITH A FOUR-INCH LAYER OF EROSION CONTROL MIX. THIS SHALL BE DONE WITHIN 24 HOURS OF STOCKING AND RE-ESTABLISHED PRIOR TO ANY RAINFALL. PLACEMENT OF ANY SOIL STOCKPILES WITHIN 100 FEET FROM ANY NATURAL RESOURCES TO BE PRESERVED SHALL BE AVOIDED.

5. NATURAL RESOURCES PROTECTION:

ANY AREAS WITHIN 100 FEET FROM ANY NATURAL RESOURCES, IF NOT STABILIZED WITH A MINIMUM OF 75% MATURE VEGETATION CATCH, SHALL BE MULCHED USING TEMPORARY MULCHING WITHIN 7 DAYS OF EXPOSURE OR PRIOR TO ANY STORM EVENT. SEDIMENT BARRIERS SHALL BE PLACED BETWEEN ANY NATURAL RESOURCE AND THE DISTURBED AREA.

6. STORMDRAIN INLET PROTECTION: A SEDIMENT FILTER INSTALLED AROUND A STORM DRAIN DROP INLET OR CURB INLET TO PREVENT SEDIMENT FROM ENTERING A STORM DRAINAGE SYSTEM PRIOR TO PERMANENT STABILIZATION OF THE DISTURBED AREA. THE INLET PROTECTION DEVICE SHALL BE CONSTRUCTED IN A MANNER THAT WILL FACILITATE CLEAN-OUT AND DISPOSAL OF TRAPPED SEDIMENTS AND MINIMIZE INTERFERENCE WITH CONSTRUCTION ACTIVITIES. ANY RESULTANT PONDING OF STORMWATER MUST NOT CAUSE EXCESSIVE INCONVENIENCE OR DAMAGE TO ADJACENT AREAS OR STRUCTURES.
   a. MANUFACTURED SEDIMENT BARRIERS AND FILTERS: INCLUDE VARIOUS TYPES OF SYSTEMS SUCH AS THE "SILT SACK" OR OTHER MANUFACTURED MATERIALS. THESE MEASURES ARE ACCEPTABLE AS LONG AS THEY ARE INSTALLED, USED AND MAINTAINED AS SPECIFIED BY THE VENDOR OR MANUFACTURER.
   b. INSPECTION AND MAINTENANCE OF STORMDRAIN INLET PROTECTION: THE CONTRACTOR SHALL INSPECT STRUCTURES BEFORE AND AFTER EACH RAIN EVENT AND SHALL REPAIR AS NEEDED. IF THE FILTER BECOMES CLOGGED WITH SEDIMENT SO THAT IT NO LONGER ADEQUATELY PERFORMS ITS FUNCTION, THE THE CONTRACTOR SHALL CLEAN AND REPLACE THE FILTER. SEDIMENT SHALL BE REMOVED AND THE STORMDRAIN SEDIMENT FILTER RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE. SEDIMENT FILTERS SHALL BE REMOVED AND THE AREA STABILIZED AFTER THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED. THE CONTRACTOR SHALL CLEAN ALL CATCHBASINS AND STORMDRAIN INLETS AT THE END OF CONSTRUCTION AND AFTER THE SITE HAS BEEN FULLY STABILIZED.

7. STORMWATER CHANNELS: DITCHES, SWALES, AND OTHER OPEN STORMWATER CHANNELS SHALL BE CONSTRUCTED AND STABILIZED USING MEASURES THAT ACHIEVE LONG-TERM EROSION CONTROL. DITCHES, SWALES, AND OTHER OPEN STORMWATER CHANNELS SHALL BE CONSTRUCTED IN SECTIONS SO THAT THE GRADING, SHAPING, AND INSTALLATION OF THE PERMANENT LINING ON EACH SECTION CAN BE COMPLETED THE SAME DAY. IF A CHANNEL'S FINAL GRADING OR LINING INSTALLATION MUST BE DELAYED, THEN EITHER DIVERSION BERMS MUST BE USED TO DIVERT STORMWATER AWAY FROM THE CHANNEL, PROPERLY-SPACED CHECK DAMS MUST BE INSTALLED IN THE CHANNEL TO SLOW THE WATER VELOCITY, OR A TEMPORARY LINING SHALL BE INSTALLED ALONG THE CHANNEL TO PREVENT SCOURING.

8. TRENCH OR FOUNDATION DE-WATERING: ACCUMULATED WATER IN TRENCHES, FOUNDATIONS, PONDS, AND OTHER AREAS THAT RETAIN WATER AFTER EXCAVATION SHALL BE CAREFULLY REMOVED BY THE CONTRACTOR TO AVOID DOWNSTREAM IMPACTS DUE TO THE HEAVILY SILTED WATER. THE COLLECTED WATER SHALL BE REMOVED FROM THE PONDED AREA, EITHER THROUGH GRAVITY OR PUMPING, AND SHALL BE REMOVED TO AREAS THAT ARE SPECIFICALLY DESIGNED TO COLLECT THE MAXIMUM AMOUNT OF SEDIMENT POSSIBLE, LIKE A SEDIMENTATION BASIN OR DEVICE SUCH AS A "DIRT BAG" FILTER OR EQUAL. AVOID ALLOWING THE WATER TO FLOW OVER DISTURBED AREAS OF THE SITE. THE CONTRACTOR SHALL USE A NON-WOVEN GEOTEXTILE SEDIMENT CONTROL BAG SUCH AS A "DIRT BAG" OR EQUIVALENT AS A PREFERRED OPTION.

C. STABILIZATON MEASURES

1. TEMPORARY STABILIZATION: THE CONTRACTOR SHALL STABILIZE ANY EXPOSED SOILS THAT WILL NOT BE WORKED FOR MORE THAN 7 DAYS WITH MULCH OR OTHER NON-ERODABLE COVER. STABILIZE AREAS WITHIN 75 FEET OF A WETLAND OR WATERBODY WITHIN 48 HOURS OF THE INITIAL DISTURBANCE OF THE SOIL OR PRIOR TO ANY STORM EVENT, WHICHEVER COMES FIRST.

2. PERMANENT STABILIZATION: IF THE AREA HAS BEEN BROUGHT TO FINAL GRADE OR WILL NOT BE WORKED FOR MORE THAN ONE YEAR, THE CONTRACTOR SHALL PERMANENTLY STABILIZE THE AREA WITHIN 7 DAYS BY PLANTING VEGETATION, SEEDING, SOD, OR THROUGH THE USE OF PERMANENT MULCH, OR RIPRAP, OR PAVER SUBBASE. IF USING VEGETATION FOR STABILIZATION, AMEND AREAS OF DISTURBED SUBSOILS WITH TOPSOIL, COMPOST, OR FERTILIZERS; PROTECT SEEDED AREAS WITH MULCH OR, IF NECESSARY, EROSION CONTROL BLANKETS; AND SCHEDULE SODDING, PLANTING, AND SEEDING TO AVOID DIE-OFF FROM SUMMER DROUGHT AND FALL FROSTS. NEWLY SEEDED OR SODDED AREAS MUST BE PROTECTED FROM VEHICLE TRAFFIC, EXCESSIVE PEDESTRIAN TRAFFIC, AND CONCENTRATED RUNOFF UNTIL THE VEGETATION IS WELL-ESTABLISHED. IF GERMINATION IS SPARSE, PLANT COVERAGE IS SPOTTY, OR TOPSOIL EROSION IS EVIDENT THE CONTRACTOR SHALL RESEED AND MULCH THE AREAS. ONE OR MORE OF THE FOLLOWING SHALL APPLY TO A PARTICULAR SITE.
   a. SEEDED AREAS: FOR SEEDED AREAS, PERMANENT STABILIZATION MEANS A 90% COVER OF HEALTHY PLANTS WITH NO EVIDENCE OF WASHING OR RILLING OF THE TOPSOIL.
   b. SODDED AREAS: FOR SODDED AREAS, PERMANENT STABILIZATION MEANS THE COMPLETE BINDING OF THE SOD ROOTS INTO THE UNDERLYING SOIL WITH NO SLUMPING OF THE SOD OR DIE-OFF.
   c. PERMANENT MULCH: FOR MULCHED AREAS, PERMANENT MULCHING MEANS TOTAL COVERAGE OF THE EXPOSED AREA WITH AN APPROVED MULCH MATERIAL. EROSION CONTROL MIX MAY BE USED AS MULCH FOR PERMANENT STABILIZATION ACCORDING TO THE MDEP APPROVED APPLICATION RATES AND LIMITATIONS.
   d. RIPRAP: FOR AREAS STABILIZED WITH RIPRAP, PERMANENT STABILIZATION MEANS THAT SLOPES STABILIZED WITH RIPRAP HAVE AN APPROPRIATE BACKING OF A WELL-GRADED GRAVEL OR APPROVED GEOTEXTILE TO PREVENT SOIL MOVEMENT FROM BEHIND THE RIPRAP.
   e. PAVER AREAS: FOR PAVER AREAS, PERMANENT STABILIZATION MEANS THE PLACEMENT OF THE COMPACTED SUBBASE IS COMPLETED.
   f. DITCHES, CHANNELS, AND SWALES: FOR OPEN CHANNELS, PERMANENT STABILIZATION MEANS THE CHANNEL IS STABILIZED WITH A 90% COVER OF HEALTHY VEGETATION, WITH A WELL-GRADED RIPRAP LINING, OR WITH ANOTHER NON-EROSIVE LINING SUCH AS CONCRETE OR PAVEMENT. THERE MUST BE NO EVIDENCE OF SLUMPING OF THE CHANNEL LINING, UNDERCUTTING OF THE CHANNEL BANKS, OR DOWN-CUTTING OF THE CHANNEL.

3. REMOVAL OF STABILIZATION MEASURES: WITHIN 30 DAYS AFTER PERMANENT STABILIZATION IS ATTAINED THE CONTRACTOR SHALL REMOVE ANY TEMPORARY SEDIMENT CONTROL MEASURES (SUCH AS SILT FENCE, ETC.), REMOVE ANY ACCUMULATED SEDIMENTS AND STABILIZE THE AREA. SILT FENCE SHALL BE REMOVED BY CUTTING THE FENCE MATERIALS AT GROUND LEVEL TO AVOID ADDITIONAL SOIL DISTURBANCE.

A. TEMPORARY VEGETATION

THE FOLLOWING SHALL APPLY IN AREAS TO RECEIVE TEMPORARY SEEDING:
1. GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AND MULCH ANCHORING. INSTALL EROSION CONTROL MEASURES SUCH AS DIVERSIONS, GRADE STABILIZATION STRUCTURES, SEDIMENT BASINS AND GRASSED WATERWAYS TO PROTECT NEWLY SEEDED AREAS.

2. APPLY LIMESTONE AND FERTILIZER AT THE RATE OF 600 POUNDS PER ACRE OR 13.8 POUNDS PER 1,000 SQUARE FEET OF 10-10-10 (N-P2O5-K2O) OR EQUIVALENT. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE (138 LB. PER 1,000 SQUARE FEET). WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED.

3. SEEDING RATES AND DEPTHS SHALL BE AS SPECIFIED ON THE PLAN SET, OR AS IDENTIFIED IN THE TABLE BELOW. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED 10 % WHEN HYDROSEEDING.

4. APPLY MULCH OVER SEEDED AREA.

5. TEMPORARY SEEDING SHALL BE PERIODICALLY INSPECTED. AT A MINIMUM, 95% OF THE SOIL SURFACE SHOULD BE COVERED BY VEGETATION. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHALL BE MADE AND OTHER TEMPORARY MEASURES USED IN THE INTERIM (MULCH, FILTER BARRIERS, CHECK DAMS, ETC.).


TEMPORARY SEEDING TABLE

SEED	Lb./Ac.	SEEDING	DEPTHSEEDING	DATES	NOTES
WINTER RYE	112	(2 Bu)	1-1.5 IN	8/15-10/1	GOOD FOR FALL SEEDING, SELECT HARDY SPECIES SUCH AS AROOSTOOK RYE.
OATS	80	(2.5 Bu)	1-1.5 IN	4/1-7/1 (SPRING)	8/15-9/15 (FALL) BEST FOR SPRING SEEDING. FALL SEEDING REQUIRES MULCH
ANNUAL RYEGRASS	400		.25 IN	4/1-7/1	GROWS QUICKLY BUT IS OF SHORT DURATION, USE WHERE APPEARANCE IS IMPORTANT. CAN BE USED THROUGHOUT GROWING SEASON. IF MULCHED.
SUDANGRASS	40	(1.0 Bu)	0.5-1.0 IN	5/15-8/15	GOOD GROWTH DURING HOT SUMMER
PERENNIAL RYEGRASS	40	(2.0 Bu)	0.25 IN	8/15-9/15	GOOD COVER, LONGER LASTING THAN ANNUAL RYEGRASS. CAN BE USED THROUGHOUT GROWING SEASON, IF MULCHED.
TEMPORARY MULCH				10/1-4/1	REFER TO TEMPORARY MULCHING OR PERMANENT VEGETATION

E. TEMPORARY MULCHING

APPLY TEMPORARY MULCHING TO PROTECT THE EXPOSED SOIL SURFACE AND AID IN THE GROWTH OF VEGETATION.
1. IN SENSITIVE AREAS (WITHIN 100 FT OF STREAMS, WETLANDS AND IN LAKE WATERSHEDS) TEMPORARY MULCH MUST BE APPLIED WITHIN 7 DAYS OF EXPOSING SOIL OR PRIOR TO ANY STORM EVENT.
2. IN OTHER AREAS, THE TIME PERIOD CAN RANGE FROM 14 TO 30 DAYS, DEPENDING ON SITE CONDITIONS (SOIL ERODIBILITY, SEASON OF YEAR, EXTENT OF DISTURBANCE, PROXIMITY TO SENSITIVE RESOURCES, ETC.) AND THE POTENTIAL IMPACT OF EROSION ON ADJACENT AREAS.
3. AREAS WHICH HAVE BEEN TEMPORARILY OR PERMANENTLY SEEDED, SHALL BE MULCHED IMMEDIATELY FOLLOWING SEEDING.
4. AREAS WHICH CANNOT BE SEEDED WITHIN THE GROWING SEASON SHALL BE MULCHED FOR OVER-WINTER PROTECTION AND THE AREA SHALL BE SEEDED AT THE BEGINNING OF THE GROWING SEASON.
5. MULCH CAN BE USED IN CONJUNCTION WITH TREE, SHRUB, VINE, AND GROUND COVER PLANTINGS.
6. MULCH ANCHORING SHALL BE USED ON SLOPES GREATER THAN 5% IN LATE FALL (PAST SEPTEMBER 15), AND OVER-WINTER (SEPTEMBER 15 - APRIL 15).
7. WHEN MULCH IS APPLIED TO PROVIDE PROTECTION OVER WINTER (PAST THE GROWING SEASON), IT SHALL BE APPLIED TO A DEPTH OF FOUR INCHES (150-200 LBS. OF HAY PER 1000 SQ. FT OR DOUBLE STANDARD APPLICATION RATE). SEEDING CANNOT GENERALLY BE EXPECTED TO GROW UP THROUGH THIS DEPTH OF MULCH AND WILL BE SMOTHERED. IF VEGETATION IS DESIRED, THE MULCH WILL NEED TO BE REMOVED IN THE SPRINGTIME AND THE AREA RESEEDED AND MULCHED.
8. ALL MULCHES MUST BE INSPECTED PERIODICALLY BY THE CONTRACTOR, IN PARTICULAR AFTER RAINSTORMS, TO CHECK FOR RILL EROSION. IF LESS THAN 90% OF THE SOIL SURFACE IS COVERED BY MULCH, ADDITIONAL MULCH SHALL BE IMMEDIATELY APPLIED. NETS MUST BE INSPECTED AFTER RAIN EVENTS FOR DISLOCATION OR FAILURE. IF WASHOUT OR BREAKAGE OCCUR, RE-INSTALL THE NETS AS NECESSARY AFTER REPAIRING DAMAGE TO THE SLOPE. INSPECTIONS SHALL TAKE PLACE UNTIL GRASSES ARE FIRMLY ESTABLISHED (95% SOIL SURFACE COVERED WITH GRASS).
9. WHERE MULCH IS USED IN CONJUNCTION WITH ORNAMENTAL PLANTINGS, THE CONTRACTOR SHALL INSPECT PERIODICALLY THROUGHOUT THE YEAR TO DETERMINE IF MULCH IS MAINTAINED COVERAGE OF THE SOIL SURFACE. REPAIR AS NEEDED.
10. THE CHOICE OF MATERIALS FOR MULCHING SHALL BE BASED ON SOIL, SITE CONDITIONS AND SEASONS. RECOMMENDED MULCHES INCLUDE HAY AND STRAW OR EROSION CONTROL MIX.
11. HAY AND STRAW:
   a. ORGANIC MULCHES INCLUDING HAY AND STRAW MUST BE AIR-DRIED, FREE OF UNDESIRABLE SEEDS AND COARSE MATERIALS.
   b. APPLICATION RATE SHALL BE 2 BALES (70-90 POUNDS) PER 1000 SQ FT OR 1.5 TO 2 TONS (90-100 BALES) PER ACRE TO COVER 75 TO 90 % OF THE GROUND SURFACE. HAY MULCH IS SUBJECT TO WIND BLOWING UNLESS KEPT MOIST OR ANCHORED.
   c. ANCHORING METHODS INCLUDE NETTING OVER HAY WITH JUTE, WOOD FIBER OR PLASTIC NETTING ANCHORED TO THE SOIL SURFACE. STAPLE MATS ACCORDING TO MANUFACTURER'S RECOMMENDATION.
12. EROSION CONTROL MIX:
   a. EROSION CONTROL MIX CAN BE MANUFACTURED ON OR OFF THE PROJECT SITE. IT MUST CONSIST PRIMARILY OF ORGANIC MATERIAL AND WILL INCLUDE ANY OF THE FOLLOWING: SHREDDED BARK, STUMP GRINDINGS, COMPOSTED BARK OR OTHER ACCEPTABLE PRODUCTS BASED ON A SIMILAR RAW SOURCE. WOOD OR BARK CHIPS, GROUND CONSTRUCTION DEBRIS OR REPROCESSED WOOD PRODUCTS WILL NOT BE ACCEPTABLE AS THE ORGANIC COMPONENTS.
   b. EROSION CONTROL MIX SHALL CONTAIN A WELL-GRADED MIXTURE OF PARTICLE SIZES AND MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER.
   c. EROSION CONTROL MIX SHALL BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH. THE MIX COMPOSITION SHALL MEET THE MAINE DEP STANDARDS:
   d. WHEN USED AS MULCH, A MINIMUM 4" THICK LAYER OF EROSION CONTROL MIX SHALL BE USED AS A STAND-ALONE REINFORCEMENT:
      1. ON SLOPES 2 HORIZONTAL TO 1 VERTICAL OR LESS.
      2. ON FROZEN GROUND AND DORMANT SEEDED AREAS.
      3. AT THE EDGE OF GRAVEL PARKING AREAS AND AREAS UNDER CONSTRUCTION.
      4. OTHER REINFORCEMENT BMPS (I.E. RIPRAP) SHALL BE USED:
      a. ON STEEPER SLOPES GREATER THAN 2:1 AND
      b. SLOPES WITH EXPOSURE TO WIND.
      c. AT LOW POINTS WITH CONCENTRATED FLOWS AND
      d. IN GULLIES

5. THE MULCH MAY BE PLACED WITH A HYDRAULIC BUCKET, WITH A PNEUMATIC BLOWER OR BY HAND. IT SHALL BE PLACED EVENLY AND MUST PROVIDE 100 % SOIL COVERAGE, WITH THE SOIL TOTALLY INVISIBLE.
6. ANY REQUIRED REPAIRS SHALL BE MADE BY THE CONTRACTOR IMMEDIATELY, WITH ADDITIONAL EROSION CONTROL MIX PLACED ON TOP OF THE MULCH TO REACH THE RECOMMENDED THICKNESS. WHEN THE MIX IS DECOMPOSED, CLOGGED WITH SEDIMENT, ERODED OR INEFFECTIVE, IT SHALL BE REPLACED OR REPAIRED. EROSION CONTROL MIX MULCH SHOULD BE LEFT IN PLACE. VEGETATION ADDS STABILITY AND SHOULD BE PROMOTED. IF THE MULCH NEEDS TO BE REMOVED SPREAD IT OUT INTO THE LANDSCAPE.
13. SPRAY ON MULCHES:
   a. IF USING SYNTHETIC, SPRAY-ON EMULSIONS THAT ARE MIXED WITH WATER T



WITH TRENCHING WITHOUT TRENCHING

NOTES:

SILT FENCE AND FILTER BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.

SHOULD THE FABRIC ON A SILT FENCE OF FILTER BARRIER DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL IS NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.


SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.

ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, PREPARED AND SEEDED. THE TRENCH SHALL BE BACKFILLED AND THE SOIL COMPACTED OVER THE FILTER FABRIC.

SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY STABILIZED.

SILT-FENCE DETAIL

NOT TO SCALE



SECTION VIEW

NOTES:
1) THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT OF WAY. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES TO TRAP SEDIMENT


2) WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT OF WAY OR EXISTING PAVED AREAS.

3) WHEN WASHING IS REQUIRED, IT SHALL BE COMPLETED ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.

4) ADDITIONAL SWEEPING MAY ALSO BE REQUIRED.

CONSTRUCTION ENTRANCE DETAIL

NOT TO SCALE




NOTE:


NEENAH FOUNDRY #R-4353 OR APPROVED EQUAL

BEEHIVE GRATE

NOT TO SCALE




SILTSACK ®



PIPE INLET/OUTLET GRATE

NOT TO SCALE



WOOD WASTE COMPOST/BARK FILTER BERMS

A) EROSION CONTROL MIX MUST CONSIST PRIMARILY OF ORGANIC MATERIALS, SEPARATED AT THE POINT OF GENERATION, AND MAY INCLUDE: SHREDDED BARK, STUMP GRINDINGS, COMPOSTED BARK, OR ACCEPTABLE MANUFACTURED PRODUCTS. WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS OR REPROCESSED WOOD PRODUCTS ARE NOT ACCEPTABLE AT THE ORGANIC COMPONENT OF THE MIX. THE MIX SHALL CONFORM TO THE FOLLOWING STANDARDS:

B) EROSION CONTROL MIX SHALL CONTAIN A WELL -GRADED MIXTURE OF PARTICLE SIZES AND MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER. EROSION CONTROL MIX MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH. THE MIX COMPOSITION SHALL MEET THE FOLLOWING STANDARDS:

1) THE ORGANIC MATTER CONTENT SHALL BE BETWEEN 80% AND 100%, DRY WEIGHT BASIS.

2) PARTICLE SIZE BY WEIGHT SHALL BE 100% PASSING A 6" SCREEN AND A MINIMUM OF 70% MAXIMUM OF 85%, PASSING A 0.75" SCREEN

3) THE ORGANICS PORTION NEEDS TO BE FIBROUS AND ELONGATED.

4) LARGE PORTIONS OF SILTS, CLAYS OR FINE SANDS ARE NOT ACCEPTABLE IN THE MIX.

5) SOLUBLE SALTS CONTENT SHALL BE LESS THAN 4.0 MMHOS/CM.


6) THE pH SHOULD FALL BETWEEN 5.0 AND 8.0 THE COMPOSTED BERM SHALL BE PLACED, UNCOMPACTED, ALONG A RELATIVELY LEVEL CONTOUR.

NOTE: EROSION CONTROL MIX FILTER BERMS MAY BE USED IN COMBINATION WITH SILT FENCE TO IMPROVE SEDIMENT REMOVAL AND PREVENT CLOGGING OF THE EROSION CONTROL MIX BERM BY LARGER SEDIMENT PARTICLES. (SILT FENCE PLACED TO FILTER RUNOFF BEFORE BERM)

NOTE: EROSION CONTROL MIX FILTER BERM CAN BE USED IN LIEU OF SILT FENCE, CONTRACTOR'S CHOICE.

WOOD WASTE COMPOST/BARK FILTER BERM

NOT TO SCALE



1. SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICK AND GRASS, MATS/BLANKETS SHALL HAVE GOOD SOIL CONTACT.

2. APPLY PERMANENT SEEDING BEFORE PLACING BLANKETS.

3. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH.

4. CHOOSE MATERIAL BASED ON SLOPE, SOILS AND APPLICATION.

5. FOLLOW MANUFACTURER SPECIFICATIONS FOR STAPLE PLACEMENT


6. BLANKETS/MATS SHOULD BE INSTALLED VERTICALLY DOWNSLOPE

7. TURF REINFORCED MATS SHALL BE KEYED IN AT THE TOP AND DOWNGRADIENT ENDS AND SHALL BE INSTALLED PER MANUFACTURER RECOMMENDATIONS.

8. THE EROSION CONTROL MAT SHALL BE ADS GEOSYNTHETIC PPS-10 TURF REINFORCEMENT MAT OR APPROVED EQUAL

EROSION CONTROL MAT

NOT TO SCALE



TYPICAL DRAIN MANOLE DETAIL

NOT TO SCALE

STATE OF MAINE
NANCY J. ST. CLAIR
No. 6877
REGISTERED PROFESSIONAL ENGINEER
12/30/2024

REV:	BY:	DATE:	STATUS:
F	DCS	12-30-2024	FOR TOWN REVIEW
4	DCS	05-03-2024	ASI-001
E	DCS	10-20-2023	FOR TOWN REVIEW
D	DCS	02-03-2022	CONDITIONS OF APPROVAL
C	DCS	12-29-2021	REV. PER CCSWCD, FOR TOWN REVIEW
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland, ME 04021
Tel (207) 829-5558

PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST

DETAIL SHEET
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	NTS

SHEET C-701

21012S TAB 21012D-2

GRASSED UNDERDRAINED SOIL FILTER NOTES

GRASSED UNDERDRAINED SOIL FILTER CONSTRUCTION NOTES

GENERAL:

EROSION AND SEDIMENTATION FROM UNSTABLE CONSTRUCTION AREAS IS THE MOST COMMON REASON FOR FILTER FAILURE. THE SOIL FILTER MEDIA SHALL NOT BE INSTALLED UNTIL THE AREA THAT DRAINS TO IT HAS BEEN PERMANENTLY STABILIZED OR UNLESS THE RUNOFF IS DIVERTED AROUND THE FILTER. PERMANENT STABILIZATION SHALL MEAN THAT TRIBUTARY AREAS ARE EITHER STABILIZED WITH BASE PAVEMENT, 90% VEGETATION OR OTHER PERMANENT STABILIZATION MEASURES.

CONSTRUCTION COMPONENTS: UNDERDRAINED FILTERS CONSIST OF (FROM BOTTOM UP):

- A GEOTEXTILE FABRIC TO SEPARATE THE FILTER BASIN FROM THE NATURAL SOILS. AN IMPERMEABLE MEMBRANE MAY BE REQUIRED IN PLACE OF THE GEOTEXTILE FABRIC IF GROUNDWATER IMPACT OR CONTAMINATION IS A CONCERN, OR IF IT MAY INFLUENCE THE EFFECTIVENESS OF THE BASIN.
- A 12 TO 14-INCH BASE OF COARSE CLEAN STONE OR COARSE GRAVEL IN WHICH A 4-INCH TO 6-INCH PERFORATED UNDERDRAIN PIPE SYSTEM IS BEDDED.
- AN 18-INCH LAYER OF UNCOMPACTED SOIL FILTER MEDIA.
- A SURFACE COVER OF GRASS AND MULCH.

BASIN EXCAVATION: THE BASIN AREA MAY BE EXCAVATED FOR UNDERDRAIN INSTALLATION AND CAN BE USED AS A SEDIMENT TRAP DURING CONSTRUCTION. AFTER EXCAVATION OF THE BASIN, THE OUTLET STRUCTURE AND PIPING SYSTEM MAY BE INSTALLED IF PROTECTED WITH A SEDIMENT BARRIER.

SACRIFICIAL MULCH COVER: IF THE BASIN WILL BE USED AS A SEDIMENT TRAP, THE SIDES OF THE EMBANKMENTS MUST BE STABILIZED AND MAINTAINED TO PREVENT EROSION. THE BASIN WILL NEED TO BE RESTORED FOR ITS PLANNED PURPOSE AFTER CONSTRUCTION. BEFORE FINAL STABILIZATION OF THE DRAINAGE AREA TO THE BASIN, A 2-INCH TO 3-INCH LAYER OF SANDY LOAM (WITH LESS THAN 2% CLAY CONTENT) MAY BE SPREAD ON THE SURFACE OF THE SOIL FILTER MEDIA AS A SACRIFICIAL PROTECTION LAYER. THE SACRIFICIAL LAYER WILL NEED TO BE REMOVED AT THE END OF CONSTRUCTION, AND THE SOIL FILTER MEDIA WILL NEED TO BE SEEDED AND MULCHED.

COMPACTION OF SOIL FILTER: SOIL FILTER MEDIA AND UNDERDRAIN BEDDING MATERIAL SHALL BE APPLIED TO REACH A BULK DENSITY OF BETWEEN 90% AND 92% STANDARD PROCTOR. THE SOIL FILTER MEDIA SHOULD BE INSTALLED IN AT LEAST TWO LIFTS OF 9 INCHES TO PREVENT POCKETS OF LOOSE MEDIA. THE CONTRACTOR SHALL USE CAUTION TO AVOID OVER COMPACTION OF THE FILTER MEDIA.

REMEDIAL LOAM COVER: IF VEGETATION IS NOT ESTABLISHED WITHIN THE FIRST YEAR, THE BASIN MAY BE ROTOTILLED, RESEEDED AND PROTECTED WITH A WELL-ANCHORED EROSION CONTROL BLANKET. OR, A 2-INCH TO 3-INCH LAYER OF FINE SANDY LOAM MAY BE APPLIED BEFORE SEEDING AND MULCHING.

CONSTRUCTION OVERSIGHT: INSPECTION OF THE FILTER BASIN MUST BE PROVIDED FOR EACH PHASE OF CONSTRUCTION BY THE DESIGN ENGINEER, OR QUALIFIED INSPECTING ENGINEER, WITH REQUIRED REPORTING TO THE DEP. ALL MATERIAL INTENDED FOR THE FILTER BASIN MUST BE APPROVED BY THE INSPECTING ENGINEER AFTER TESTS BY A CERTIFIED LABORATORY SHOW THAT THE MATERIAL CONFORMS TO ALL DEP SPECIFICATIONS. THE CONTRACTOR SHALL PROVIDE THE OWNER AND INSPECTING ENGINEER WITH AN UP-TO-DATE CONSTRUCTION SCHEDULE TO ALLOW TIMELY INSPECTIONS DURING THE VARIOUS STAGES OF CONSTRUCTION. AT A MINIMUM, INSPECTIONS SHALL OCCUR:

- AFTER THE PRELIMINARY CONSTRUCTION OF THE FILTER GRADES AND ONCE THE UNDERDRAIN PIPES ARE INSTALLED (NOT BACKFILLED),
- AFTER THE DRAINAGE LAYER IS CONSTRUCTED AND PRIOR TO THE INSTALLATION OF THE SOIL FILTER MEDIA,
- AFTER THE SOIL FILTER MEDIA HAS BEEN INSTALLED, SEEDED AND MULCHED, AND
- AFTER ONE YEAR, TO INSPECT VEGETATION AND MAKE CORRECTIONS.

TESTING AND SUBMITTALS: THE SOURCE OF EACH COMPONENT OF THE SOIL FILTER MEDIA SHALL BE IDENTIFIED PRIOR TO CONSTRUCTION. SAMPLES OF EACH TYPE OF MATERIAL SHOULD BE BLENDED FOR THE FILTER MEDIA AND THE UNDERDRAIN BEDDING MATERIAL. SAMPLES MUST BE A COMPOSITE OF THREE DIFFERENT LOCATIONS (GRABS) FROM THE STOCKPILE OR PIT FACE. SAMPLE SIZE REQUIREMENTS WILL BE DETERMINED BY THE TESTING LABORATORY. A SIEVE ANALYSIS CONFORMING TO ASTM C136 SHALL BE PERFORMED ON EACH TYPE OF THE SAMPLE MATERIAL. TESTING THE PERMEABILITY OF THE SOIL FILTER MEDIA MIXTURE IS REQUIRED FOR THE MIXTURE AT A MEASURED BULK DRY DENSITY OF 90-92% BASED ON ASTM D698.

ALL GRADATION TESTS, INCLUDING HYDROMETER TESTING FOR CLAY CONTENT, AND PERMEABILITY TESTING OF THE SOIL FILTER MATERIAL, SHALL BE PERFORMED BY A QUALIFIED SOIL TESTING LABORATORY. THE CONTRACTOR SHALL SUBMIT FIELD AND LABORATORY RESULTS AND VERIFICATION OF SOIL TESTING COMPLIANCE TO THE OWNER AND THE INSPECTING ENGINEER FOR REVIEW AND APPROVAL BEFORE PLACEMENT. TESTING RESULTS SHALL BE INCLUDED AS PART OF THE INSPECTING ENGINEER'S REPORTING TO THE MDEP.

CONSTRUCTION OF GRASSED UNDERDRAINED SOIL FILTER:

GEOTEXTILE FABRIC: A GEOTEXTILE FABRIC SHALL BE PLACED BETWEEN THE SIDES OF THE FILTER LAYER AND ADJACENT SOIL TO PREVENT THE SURROUNDING SOIL FROM MIGRATING INTO AND CLOGGING THE FILTER OR CLOGGING THE OUTLET. SEAMS SHOULD BE OVERLAPPED A MINIMUM OF 12 INCHES. DO NOT WRAP FABRIC OVER THE PIPE BEDDING AS IT MAY CLOG AND PREVENT FLOWS OUT OF THE FILTER. THE GEOTEXTILE FABRIC SHALL BE MIRAFI 170N OR APPROVED EQUAL.

IMPERMEABLE LINER: AN IMPERMEABLE LINER MAY BE REQUIRED ON CERTAIN SITES, IF NOTED IN THE MDEP PERMIT, OR ON THE PLANS OR DETAILS. IF REQUIRED, THE IMPERMEABLE LINER SHALL BE INSTALLED IN LIEU OF THE GEOTEXTILE FABRIC NOTED ABOVE. THE LINER MUST SEAMLESSLY EXTEND UP THE SIDES OF THE BASIN AND BE ANCHORED INTO THE SUBGRADE. THE IMPERMEABLE LINER MATERIAL SHALL BE WATERPROOF WITH SEALED JOINTS SUCH AS 30MIL PVC OR HDPE, OR APPROVED EQUAL. ALL CROSSINGS OF THE LINER FOR PIPES OR OTHER STRUCTURES SHALL BE SEALED. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL CONFIRM WITH THE OWNER AND ENGINEER WHETHER AN IMPERMEABLE LINER IS REQUIRED FOR EACH BMP.

UNDERDRAIN LAYER: THE PERFORATED PIPING IN THE UNDERDRAIN LAYER SHALL BE BEDDED IN A MINIMUM OF 12 TO 14 INCHES OF UNDERDRAIN BACKFILL MATERIAL, WITH AT LEAST 4 INCHES OF MATERIAL BENEATH THE PIPE AND 4 INCHES ABOVE THE UNDERDRAIN PIPING. THE UNDERDRAIN MATERIAL SHALL CONSIST OF WELL-GRADED, CLEAN, COARSE GRAVEL MEETING THE MAINE DOT SPECIFICATION 703.22 UNDERDRAIN BACKFILL FOR TYPE B UNDERDRAIN.

PERFORATED UNDERDRAIN PIPING: THE PERFORATED UNDERDRAIN PIPING SHALL BE EITHER A 4" DIAMETER OR 6" DIAMETER (AS SPECIFIED ON THE PLANS) RIGID SCHEDULE 40 PVC OR SDR35 PIPE. THE UNDERDRAIN PIPING WITHIN THE FILTER BED SHALL BE SPACED NO FURTHER THAN 15' APART AND SHOULD HAVE A POSITIVE SLOPE TO THE OUTLET INVERT SHOWN ON THE PLANS. STRUCTURE JOINTS SHOULD BE SEALED AND WATER TIGHT. CLEAN OUTS SHALL BE INSTALLED AT THE UPSTREAM ENDS OF THE UNDERDRAIN PIPING. CLEAN OUTS SHALL INCLUDE SCREW CAPS SET NO MORE THAN 2" ABOVE GRADE.

SOIL FILTER BED: THE SOIL FILTER OVER THE GRAVEL UNDERDRAIN PIPE BEDDING MUST BE AT LEAST 18 INCHES DEEP AND MUST EXTEND ACROSS THE ENTIRE FILTER AREA. THIS SOIL MIXTURE SHALL BE A UNIFORM MIX, FREE OF STONES, STUMPS, ROOTS, OR OTHER SIMILAR OBJECTS LARGER THAN TWO INCHES. NO MATERIALS OR SUBSTANCES THAT MAY BE HARMFUL TO PLANT GROWTH CAN BE MIXED WITHIN THE FILTER. EXCEPT FOR AGRICULTURAL SOURCES, MOST ORGANIC SOURCES MAY BE ACCEPTABLE FOR THE ORGANIC COMPONENT OF THE MEDIA. THE MEDIA MIXTURE SHALL HAVE VERY LITTLE OR NO CLAY CONTENT AS TESTED VIA HYDROMETER TEST. SOILS WITH MORE THAN 2% CLAY CONTENT COULD CAUSE FAILURE OF THE SYSTEM AND ARE NOT PERMITTED FOR USE. THE FILTER MUST BE PERMEABLE ENOUGH TO INSURE DRAINAGE WITHIN 24 TO 48 HOURS, YET HAVE SUFFICIENT FINES TO INSURE THE FILTRATION OF FINE PARTICLES AND THE REMOVAL OF DISSOLVED POLLUTANTS.

OPTIONAL HAY LAYER: A LAYER OF HAY CAN BE PLACED TO SEPARATE THE UNDERDRAIN LAYER FROM THE FILTER LAYER ABOVE TO PREVENT SUBSIDENCE OR PLUGGING OF THE UNDERDRAIN LAYER AND/OR PIPE.

SOIL FILTER MEDIA - LAYERED SYSTEM WITH TOPSOIL: THE MEDIA SHALL CONSIST OF A LAYERED SYSTEM THAT TAKES ADVANTAGE OF THE CHARACTERISTICS OF NATURAL SOILS. THE DIFFERENT LAYERS FROM THE BOTTOM UP SHALL BE:

- FILTER LAYER: A 12-INCH LAYER OF LOAMY COARSE SAND WHICH IS LOOSELY INSTALLED AND MEETS THE GRAIN SIZE SPECIFICATION SHOWN IN THE FOLLOWING TABLE.

  LOAMY COARSE SAND SPECIFICATIONS

SIEVE #	%PASSING BY WEIGHT
NO. 10	85-100
NO. 20	70-100
NO. 60	15-40
NO. 200	8-15
200 (CLAY SIZE)	LESS THAN 2.0

- TOPSOIL: THE SURFACE OF THE BASIN SHALL BE COVERED WITH 6 INCHES OF NON-CLAYEY, LOAMY TOPSOIL SUCH AS USDA LOAMY SAND TOPSOIL WITH 5 TO 8% HUMIFIED ORGANIC CONTENT. TOPSOIL FROM THE DEVELOPMENT SITE MAY BE APPROPRIATE BUT IT SHALL BE TESTED FOR ORGANIC CONTENT AND CLAY CONTENT (HYDROMETER TEST) BEFORE APPROVAL FOR INSTALLATION. THE SOIL MUST BE SCREENED, LOOSE, FRIABLE, AND SHALL BE FREE FROM ADMIXTURES OF SUBSOIL, REFUSE, STONES (GREATER THAN 2 INCHES IN DIAMETER), CLUMPS, ROOT AND OTHER UNDESIRABLE FOREIGN MATTER. THE TOPSOIL SHALL BE GENTLY MIXED WITHIN THE FILTER LAYER TO PROVIDE CONTINUITY FOR DEEP ROOT PENETRATION. THE TEETH OF A BACKHOE, A HAND RAKE, A SHOVEL OR ROTOTILLING 2-3 INCHES MAY BE USED TO CREATE A LOOSENED TRANSITION.

SEEDING AND MULCHING: THE FILTER BED SHALL BE SEEDED WITH A DROUGHT TOLERANT GRASS MIX AND MULCHED. WATERING IS RECOMMENDED TO ESTABLISH A HEALTHY VEGETATION BASE. THE FOLLOWING SEED MIX IS RECOMMENDED:


SEED MIX SHALL CONTAIN THE FOLLOWING:

CREEPING RED FESCUE	20 LBS/ACRE
TALL FESCUE	20 LBS/ACRE
BIRDSFOOT TREFOIL	8 LBS/ACRE
TOTAL	48 LBS/ACRE


UPON SEEDING, MULCH WITH HAY OR EROSION CONTROL BLANKET, DO NOT FERTILIZE.

ADDITIONAL INFORMATION:


ADDITIONAL DETAILED INFORMATION IS OUTLINED IN THE MAINE STORMWATER MANAGEMENT DESIGN MANUAL (BEST MANAGEMENT PRACTICES MANUAL VOLUME III DATED MARCH 2016 WITH SUBSEQUENT REVISIONS).



PLAN VIEW




CROSS SECTION



DETAIL


NOTE: SEE GRASSED UD SOIL FILTER NOTES FOR ADDITIONAL INFORMATION.

GRASSED UD SOIL FILTER BMP




ROOF DRIPLINE BMP SECTION

NOT TO SCALE




INFILTRATION TRENCH

NOT TO SCALE



SECTION VIEW



PLAN VIEW

STONE RESERVOIR BENEATH PARKING LOT

NOT TO SCALE

CONSTRUCTION OVERSIGHT

THE APPLICANT WILL RETAIN THE SERVICES OF A PROFESSIONAL ENGINEER TO INSPECT THE CONSTRUCTION AND STABILIZATION OF ALL STORMWATER MANAGEMENT STRUCTURES. IF NECESSARY, THE INSPECTING ENGINEER WILL INTERPRET THE BMP'S CONSTRUCTION PLAN FOR THE CONTRACTOR. ONCE ALL STORMWATER MANAGEMENT STRUCTURES ARE CONSTRUCTED AND STABILIZED, THE INSPECTING ENGINEER WILL NOTIFY THE DEPARTMENT IN WRITING WITHIN 30 DAYS TO STATE THAT THE SITEWORK HAS BEEN COMPLETED. ACCOMPANYING THE ENGINEER'S NOTIFICATION MUST BE A LOG OF THE ENGINEER'S INSPECTIONS GIVING THE DATE OF EACH INSPECTION THE TIME OF EACH INSPECTION AND THE ITEMS INSPECTED ON EACH VISIT, AND INCLUDE ANY TESTING DATA OR SIEVE ANALYSIS DATA OF EVERY MINERAL SOIL AND SOIL MEDIA SPECIFIED IN THE PLANS AND USED ON SITE.

CONSTRUCTION OVERSIGHT: INSPECTION BY A PROFESSIONAL ENGINEER WILL OCCUR AT A MINIMUM:

- AFTER THE PRELIMINARY CONSTRUCTION OF THE FILTER GRADES AND ONCE THE UNDERDRAIN PIPES ARE INSTALLED BUT NOT BACKFILLED,
- AFTER THE DRAINAGE LAYER IS CONSTRUCTED AND PRIOR TO THE INSTALLATION OF THE FILTER MEDIA,
- AFTER THE FILTER MEDIA HAS BEEN INSTALLED AND SEEDED. BIO-RETENTION CELLS MUST BE STABILIZED PER THE PROVIDED PLANTING SCHEME AND DENSITY FOR THE CANOPY COVERAGE OF 30% AND 50%,
- AFTER ONE YEAR TO INSPECT HEALTH OF THE VEGETATION AND MAKE CORRECTIONS,, AND
- ALL THE MATERIAL USED FOR THE CONSTRUCTION OF THE FILTER BASIN MUST BE CONFIRMED AS SUITABLE BY THE DESIGN ENGINEER. TESTING MUST BE DONE BY A CERTIFIED LABORATORY TO SHOW THAT THEY ARE PASSING DEP SPECIFICATIONS.

TESTING AND SUBMITTALS: THE CONTRACTOR SHALL IDENTIFY THE LOCATION OF THE SOURCE OF EACH COMPONENT OF THE FILTER MEDIA. ALL RESULTS OF THE FIELD AND LABORATORY TESTING SHALL BE SUBMITTED TO THE PROJECT ENGINEER FOR CONFIRMATION. THE CONTRACTOR SHALL:

- SELECT SAMPLES FOR SAMPLING OF EACH TYPE OF MATERIAL TO BE BLENDED FOR THE MIXED FILTER MEDIA AND SAMPLES OF THE UNDERDRAIN BEDDING MATERIAL. SAMPLES MUST BE A COMPOSITE OF THE THREE DIFFERENT LOCATIONS (GRABS) FROM THE STOCKPILE OR PIT FACE. SAMPLE SIZE REQUIRED WILL BE DETERMINED BY THE TESTING LABORATORY.
- PERFORM A SIEVE ANALYSIS CONFORMING TO THE STM C136 (STANDARD TESTING METHOD FOR SIEVE ANALYSIS OF FINE AND COURSE AGGREGATES 1996 A) ON EACH TYPE OF THE SAMPLE MATERIAL. THE BIO-RETENTION SOIL FILTER MEDIA MIXTURE MUST HAVE 8% TO 12% BY WEIGHT PASSING THE #200 SIEVE, A CLAY CONTENT OF LESS THAN 2% (DETERMINED HYDROMETER GRAIN SIZE ANALYSIS) AND HAVE 10% DRY WEIGHT OF ORGANIC MATTER.
- PERFORM A PERMEABILITY TEST ON THE SOIL FILTER MEDIA MIXTURE CONFORMING TO ASTM D2434 WITH THE MIXTURE COMPACTED TO 90%-92% OF MAXIMUM DRY DENSITY BASED ON ASTM D698.

UNDERDRAINED FILTER BASINS NOTES

PRIOR TO THE START OF CONSTRUCTION OF ANY UNDERDRAINED FILTER BASIN (I.E. A BIORETENTION CELL OR A GRASSED UNDERDRAINED SOIL FILTER) AT LEAST ONE TEST PIT SHALL BE EXCAVATED IN THE CENTER OF EACH BMP TO DETERMINE THE DEPTH TO GROUNDWATER OR LEDGE. EACH TEST PIT SHALL BE EXCAVATED TO A DEPTH OF AT LEAST 2' BELOW THE BOTTOM OF THE UNDERDRAIN BEDDING. IN THE EVENT THAT GROUNDWATER IS ENCOUNTERED WITHIN THE TEST PIT, AN IMPERMEABLE LINER SHALL BE INSTALLED. THIS LINER SHALL BE INSTALLED IN PLACE OF THE NON-WOVEN GEOTEXTILE FABRIC ON THE SIDES AND BOTTOM OF THE BASIN. IN THE EVENT THAT LEDGE IS ENCOUNTERED IN THE TEST PIT, THE LEDGE SHALL BE REMOVED TO A DEPTH OF AT LEAST THE BOTTOM OF THE UNDERDRAIN BEDDING AND AN IMPERMEABLE LINER SHALL BE INSTALLED. WHERE REQUIRED, A WATERPROOF LINER WITH SEALED JOINTS, SUCH AS 30 MIL PVC OR HDPE, OR APPROVED EQUAL, SHALL BE INSTALLED. ALL CROSSINGS FOR THE LINER FOR PIPES AND OTHER STRUCTURES SHALL BE SEALED.

ROOF DRIP EDGE FILTERS

INSPECTIONS BY A PROFESSIONAL ENGINEER SHALL CONSIST OF WEEKLY VISITS TO THE SITE TO INSPECT OF THE ROOF DRIP EDGE FILTERS UNDERDRAIN CONSTRUCTION, FILTER MATERIAL PLACEMENT FROM INITIAL GROUND DISTURBANCE TO FINAL STABILIZATION OF THE FILTER.

DEWATERING


A DEWATERING PLAN IS REQUIRED TO ADDRESS EXCAVATION DEWATERING FOLLOWING HEAVY RAINFALL EVENTS OR WHERE THE EXCAVATION MAY INTERCEPT THE GROUNDWATER TABLE DURING CONSTRUCTION. THE COLLECTED WATER NEEDS TREATMENT AND A DISCHARGE POINT THAT WILL NOT CAUSE DOWNGRADIENT EROSION AND OFFSITE SEDIMENTATION WITHIN A RESOURCE.

BASIC STANDARDS - EROSION CONTROL MEASURES

EROSION CONTROL MEASURES SHALL BE IMPLEMENTED AS DESCRIBED IN THE PLAN SET AND IN THE SEPARATE EROSION AND SEDIMENT CONTROL PLAN NARRATIVE AND INSPECTION AND MAINTENANCE PLAN FOR THIS PROJECT. THE CONTRACTOR (AND APPLICANT) SHALL BE RESPONSIBLE TO MAINTAIN ALL COMPONENTS OF THE EROSION CONTROL PLAN UNTIL THE SITE IS FULLY STABILIZED. HOWEVER, BASED ON SITE AND WEATHER CONDITIONS DURING CONSTRUCTION, ADDITIONAL EROSION CONTROL MEASURES MAY NEED TO BE IMPLEMENTED. ALL AREAS OF INSTABILITY AND EROSION MUST BE REPAIRED IMMEDIATELY DURING CONSTRUCTION AND NEED TO BE MAINTAINED UNTIL THE SITE IS FULLY STABILIZED OR VEGETATION IS ESTABLISHED. A CONSTRUCTION LOG MUST BE MAINTAINED FOR THE EROSION AND SEDIMENTATION CONTROL INSPECTIONS AND MAINTENANCE.

BIO-RETENTION CELL OVERSIGHT NOTES

NOT TO SCALE



BIO-RETENTION CELL BMP DETAIL

NOT TO SCALE

STATE OF MAINE — NANCY J. ST. CLAIR No. 6877 — REGISTERED PROFESSIONAL ENGINEER
12/30/2024

REV:	BY:	DATE:	STATUS:
4	DCS	05-03-2024	ASI-000
F	DCS	11-29-2023	ADD DETAIL
E	DCS	10-20-2023	FOR TOWN REVIEW
D	DCS	02-03-2022	CONDITIONS OF APPROVAL
C	DCS	12-29-2021	REV. PER CCSWCD, FOR TOWN REVIEW
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland, ME 04021
Tel (207) 829-5558


PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST


DETAIL SHEET
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	NTS

SHEET C-702


21012S TAB 21012D-1






NOTES:
1) USE MOLD 1 FOR AREAS WHERE SIDEWALK SHALL DIRECTLY ABUTS CURB. SEE PLAN FOR LOCATIONS.


CONCRETE SLIPFORM CURB DETAIL
NOT TO SCALE




TYPICAL PAVED ENTRANCE/PARKING DETAIL
NOT TO SCALE



TYPICAL PAVEMENT JOINT
NOT TO SCALE




TYPICAL PAVED TRAIL DETAIL
NOT TO SCALE




NOTES:
1) INSTALLATION SHOULD NOT ALLOW THE INTER-TWINING OF CABLES.
2) BEDDING AND BACKFILL SHALL BE FREE OF ROOTS, STUMPS AND OTHER DEBRIS.
3) COMMUNICATION CABLE AND POWER CABLE SHALL HAVE NO LESS THAN 12-INCHES OF RADIAL SEPARATION.
4) ELECTRICAL CONDUIT SHALL BE SCHEDULE 40 PVC OR AS DIRECTED BY CMP CO. DESIGN ENGINEERS.
5) REFER TO THE CMP CO. HANDBOOK OF REQUIREMENTS FOR ELECTRIC SERVICE AND INSTALLATIONS, LATEST EDITION FOR ADDITIONAL INFORMATION.


TYPICAL UNDERGROUND CABLE INSTALLATION
NOT TO SCALE




ACCESSIBLE PARKING SIGN & PAVEMENT PAINT
N.T.S.



FIRE HYDRANT
NOT TO SCALE



SEWER CLEANOUT
NOT TO SCALE




SCHEDULE OF TRENCH BACKFILL		
TYPE OF PIPE	EMBEDMENT MATERIAL	SELECT BACKFILL
CMP DUCTILE IRON RCP	MDOT 703.22 TYPE B UD BACKFILL	MDOT 703.22 TYPE B UD BACKFILL
PVC-SDR 35 HDPE	MDOT 703.22 TYPE C ¾" CRUSHED STONE	MDOT 703.22 TYPE B UD BACKFILL
PERFORATED PVC-SDR35 HDPE	MDOT 703.22 TYPE C ¾" CRUSHED STONE	MDOT 703.22 TYPE C ¾" CRUSHED STONE

NOTES:


BRACING AND SHEETING OR OTHER TRENCH PROTECTION TO BE PROVIDED TO MEET APPLICABLE STATE AND O.S.H.A. SAFETY STANDARDS. ALL SUCH TRENCH PROTECTION TO BE THE RESPONSIBILITY OF THE CONTRACTOR.


INSTALL WARNING TAPE DIRECTLY ABOVE UTILITIES, 12" BELOW FINISH GRADE.

PIPE TRENCH
NOT TO SCALE




GATE VALVE
NOT TO SCALE






NOTES:
1. INSTALL 3 FOOT LONG IMPERVIOUS DAMS IN BEDDING/INITIAL BACKFILL MATERIAL EVERY 100 FEET TO PREVENT TRENCH GROUNDWATER FROM BEING CHANNELED ALONG BEDDING/INITIAL BACKFILL.
2. REFER TO LATEST MDOT SPECIFICATIONS FOR BEDDING AND BACKFILL REQUIREMENTS.
3. INITIAL BACKFILL TO BE 12 INCHES OVER TOP OF PVC PIPE ONLY.

TYP. SEWER TRENCH
NOT TO SCALE




NOTES: MINIMUM DEPTH OF COVER IS 5'-0"

TRENCH DETAIL
NOT TO SCALE



NOTE: TRACER WIRE MUST BE PROVIDED FOR 2" PECTS

SERVICE TAP
NOT TO SCALE



TYPICAL DUMPSTER ENCLOSURE
NOT TO SCALE

REV:	BY:	DATE:	STATUS:
D	DCS	12-30-2024	FOR TOWN REVIEW
5	DCS	09-12-2024	CONTRACTOR RFI
4	DCS	05-03-2024	ASI-001
C	DCS	02-03-2022	CONDITIONS OF APPROVAL
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN, SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

STATE OF MAINE — NANCY J. ST. CLAIR No. 6877 — REGISTERED PROFESSIONAL ENGINEER — 12/30/2024

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland Center, ME 04021
Tel (207) 829-5558


PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012		ELECT.	DCS	DCS	NST

DETAIL SHEET
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	NTS

SHEET C-703

21012S TAB 21012D-4



WATERSHED AREA

SUBCATCHMENT:	COVER TYPE:	AREA:
1	IMPERVIOUS	3,541 S.F.
	MEADOW	8,582 S.F.
	WOODS	57,132 S.F.
2	WOODS	51,322 S.F.
3	WOODS	4,297 S.F.
4	WOODS	3,340 S.F.
5	WOODS	1,763 S.F.
6	WOODS	678 S.F.
7	WOODS	22,005 S.F.
8	IMPERVIOUS	621 S.F.
	MEADOW	897 S.F.
	WOODS	5,149 S.F.

OVERALL WATERSHED AREA: 159,327 S.F.

LEGEND (WATERSHED MAP)

EXISTING	DESCRIPTION	PROPOSED
	TCPATH	
	WATERSHED	
	SUBCATCHMENT	
	STUDY POINT	
	POND	

SOILS LEGEND

1) SOILS TYPE

LABEL	SOIL NAME	SLOPE	HYDROLOGIC SOIL GROUP
Au	AU GRES LOAMY SAND	0% TO 3% SLOPES	HSG A
Wa	WALPOLE FINE SANDY LOAM	0% TO 3% SLOPES	HSG A

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	
	BUILDING	
	EDGE PAVEMENT	
	EDGE OF GRAVEL	
122 120	CONTOURS	
30.20	SPOT GRADE	+30.20
S	SEWER	S
S	SEWER MH	
	UNDERDRAIN	UD
	UNDERGROUND ELEC. & TEL.	UGT/E
	TREELINE	
	DECIDUOUS TREE	X
	CONIFEROUS TREE	X

GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

STATE OF MAINE
NANCY J. ST. CLAIR
No. 6877
REGISTERED PROFESSIONAL ENGINEER
12/30/2024

REV:	BY:	DATE:	STATUS:
D	DCS	12-30-2024	FOR TOWN REVIEW
4	DCS	05-03-2024	ASI-001
C	DCS	02-03-2022	CONDITIONS OF APPROVAL
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland, ME 04021
Tel (207) 829-5558

PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012		ELECT.	DCS	DCS	NST

PRE DEVELOPMENT WATERSHED MAP
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET C-800

21012'S TAB 21012PRE

WATERSHED AREA

SUBCATCHMENT:	COVER TYPE:	AREA:
1	IMPERVIOUS	8,444 S.F.
	GRASS, FAIR	4,984 S.F.
2	WOODS	24,304 S.F.
	MEADOW	12,855 S.F.
3	WOODS	4,184 S.F.
4	WOODS	3,340 S.F.
5	WOODS	1,721 S.F.
6	WOODS	623 S.F.
	MEADOW	51 S.F.
7	IMPERVIOUS	52 S.F.
	WOODS	1,936 S.F.
	MEADOW	14,981 S.F.
8	THOMAS PT. RD.	620 S.F.
	BRUSH	1,802 S.F.
9	IMPERVIOUS	9,218 S.F.
	GRASS, GOOD	5,008 S.F.
10	IMPERVIOUS	1,723 S.F.
	THOMAS PT. RD.	3,541 S.F.
	WOODS	18,630 S.F.
	MEADOW	17,086 S.F.
11	BUILDING	17,881 S.F.
	IMPERVIOUS	114 S.F.
	GRASS, FAIR	4,434 S.F.
12	BUILDING	1,440 S.F.
	GRASS	360 S.F.

OVERALL WATERSHED AREA: 159,332 S.F.

LEGEND (WATERSHED MAP)

EXISTING	DESCRIPTION	PROPOSED
→	TCPATH	→
⬡	SUBCATCHMENT	⬡
□	STUDY POINT	□
△	POND	△

SOILS LEGEND

1) SOILS TYPE

LABEL	SOIL NAME	SLOPE	HYDROLOGIC SOIL GROUP
Au	AU GRES LOAMY SAND	0% TO 3% SLOPES	HSG A
Wa	WALPOLE FINE SANDY LOAM	0% TO 3% SLOPES	HSG A

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	
	BUILDING	
	EDGE PAVEMENT	
	EDGE OF GRAVEL	
--122--	CONTOURS	--120--
30.20	SPOT GRADE	+30.20
S	SEWER	S
Ⓢ	SEWER MH	
	UNDERDRAIN	UD
	UNDERGROUND ELEC. & TEL.	UGT/E
	TREELINE	
	DECIDUOUS TREE	X
	CONIFEROUS TREE	X

GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

REV:	BY:	DATE:	STATUS:
E	DCS	12-30-2024	FOR TOWN REVIEW
4	DCS	05-02-2024	ASI-001
D	DCS	02-03-2022	CONDITIONS OF APPROVAL
C	DCS	12-29-2021	REVISED PER CCSWCD REVIEW COMMENTS
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

STATE OF MAINE — NANCY J. ST. CLAIR No. 6877 — REGISTERED LAND SURVEYOR — 12/30/2024

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland Foresides, ME 04021
Tel (207) 829-5558


PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST

POST DEVELOPMENT WATERSHED MAP
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET C-900

21012S TAB 21012POST



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	
	BUILDING	
	EDGE PAVEMENT	
	EDGE OF GRAVEL	
--122--	CONTOURS	--120--
30.20	SPOT GRADE	+30.20
S	SEWER	S
S	SEWER MH	
	UNDERDRAIN	UD
	UNDERGROUND ELEC. & TEL.	UGT/E
	TREELINE	
	DECIDUOUS TREE	X
	CONIFEROUS TREE	X

REV:	BY:	DATE:	STATUS:
B	DCS	12-30-2024	FOR TOWN REVIEW
4	DCS	05-03-2024	ASI-001
A	DCS	11-23-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland, ME 04021
Tel (207) 829-5558

PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST

VEHICLE SIMULATION - FIRE TRUCK
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET 1 .

21012S TAB 21012 FIRE TRUCK TURN

Town of Brunswick, Maine

DEPARTMENT OF PLANNING AND DEVELOPMENT

APPROVED FINDINGS OF FACT
FINAL PLAN MAJOR DEVELOPMENT REVIEW
PLANNING BOARD

REVIEW DATE: January 11, 2022
CASE NUMBER: 21-070
PROJECT NAME: Tedford Housing Homeless Shelter, Resource Center
ADDRESS/ TAX MAP: Map 42, Lots 8 and 11
ZONING DISTRICT: Growth Mixed-Use 4 (GM4) Zoning District
OVERLAY ZONING: Cook's Corner Master Plan and Design Standards
APPLICANT: Tedford Housing
P.O. Boc 958
Brunswick, ME 04011
REPRESENTATIVE: Nancy St. Clair
St. Clair Associates
34 Forest Lane
Cumberland, ME 04011

I. APPLICATION COMPLETENESS

Staff has reviewed the application and determined that it is complete.

Approved Motion:

The Planning Board concurs with staff's conclusion that the basic Final Plan Major Development Review application materials have been submitted and that the application is complete such that the Board may proceed with substantive review of the application and identification of any further information required from the applicant.

First: Art Pierce Second: Rob Burgess Vote: 7-0-0

II. PROJECT SUMMARY

The approved Findings of Fact are based on the Final Plan Major Development Review Application titled "Major Development Review Tedford Housing Building" and dated November 23, 2021 (Exhibit A). The Planning Board reviewed and approved a Sketch Plan Major Development Review Application on September 8, 2021 (Exhibit B). The Staff Review Committee (SRC) reviewed the Final Plan Major Development Review application on December 8, 2021. The SRC meeting notes are included under separate cover.

The proposed *homeless shelter, resource center* is intended to provide temporary emergency housing and on-site resources for individuals and households that are clients of Tedford Housing. The proposed shelter is approximately 17,568 square feet and it will include ten (10) household apartment-style units, each with a bedroom with four (4) beds and living and dining space in each unit. The proposed shelter will also accommodate twenty-four (24) individual clients in a dormitory-style space. Therefore, the total number of beds proposed is sixty-four (64). The applicant has indicated that the facility will not be a "drop-in" facility available to any member of the public. Occupants of the shelter must be enrolled in Tedford Housing's programs to help seek

new housing options.

The project site will be served by a twenty-six (26) space parking lot, two (2) of which will be compliant with Americans with Disabilities Act (ADA) standards. Additional site improvements include interior walkways with benches, play area, connection to the retail center to the northeast of the site, small storage building, and a dumpster enclosure.

The applicant has included a Purchase and Sale Agreement with the property to demonstrate right, title, and interest.

III. REVIEW STANDARDS

3.4.1.X Homeless Shelter Supplementary Use Standards

Subsection (1) provides the formulas necessary to calculate maximum density allowed for a *homeless shelter, resource center.* Based on the underlying GM4 Zoning District, the maximum number of dwelling units permitted for the subject property is forty-six (46) dwelling units. The proposed project includes ten (10) apartment-style household units and twenty-four (24) dormitory-style beds for individuals. Using the formula, the twenty-four (24) individual beds equate to six (6) residential dwelling units. Therefore, the total number of dwelling units is calculated as sixteen (16), well below the maximum number of units allowed.

Subsection (2) provides the formulas necessary to calculate the demand for parking spaces for a *homeless shelter, resource center*. Using these formulas, the included traffic study by Maine Licensed Traffic Engineers John Adams and Bill Bray of Barton and Loguidice / Traffic Solution calculates the minimum parking demand as twenty-six (26) parking spaces. The proposed project provides the minimum twenty-six (26) parking spaces, including two (2) spaces compliant with the Americans with Disabilities Act (ADA).

Subsection (3) requires the applicant to provide interior floor plans dimensioned with spaces labeled with the proposed use. The applicant has provided floor plans prepared by Ryan Senatore Architecture in their application.

Subsection (4) requires non-apartment-style homeless shelter space to be dedicated for use by unaccompanied minors under eighteen (18) years of age or adults, but not both. The applicant has indicated that the dormitory-style section of the building is intended only for individual adults.

Subsection (5) requires a minimum 1,000-foot separation between any new homeless shelter and any existing homeless shelter. The nearest homeless shelter, which is operated by Tedford Housing, is approximately 2.6 miles from the subject property.

The Planning Board finds that the provisions of Section 3.4.1.X are satisfied.

4.1. Applicability of Property Development Standards

As the proposed project is for a commercial use, all regulations established in *Chapter 4 – Property Development Standards* of the Zoning Ordinance apply. The Town Codes Enforcement Officer and other members of the SRC have reviewed the application

and found that it complies with all applicable Zoning Ordinance standards associated with the GM4 Zoning District.
The Planning Board finds that the provisions of Section 4.1 are satisfied.

4.2. Dimensional and Density Standards

As referenced in Item 4.1 above, the proposed project has been found to comply with all applicable property developments standards. This includes the standards established in *Table 4.2.3. Growth Area Dimensional and Density Standards* of the Zoning Ordinance.

The Planning Board finds that the provisions of Section 4.2 are satisfied.

4.3. Natural and Historic Areas

4.3.1 Mapping of Natural and Historic Areas Requirements

As there were no natural or historic areas identified via the wetland delineation study performed by Mark Hampton Association, the Maine Natural Areas Program (MNAP), or the Town's GIS system.

The Planning Board finds that the provisions of Section 4.3.1 are not applicable.

4.3.2 Pollution

The subject property is not located within any floodplain or other special flood hazard area. No on-site wastewater is proposed as the applicant is proposing to connect to the Brunswick Sewer District system. Stormwater will be managed via Maine Department of Environmental Protection's Best Management Practices to treat stormwater runoff prior to discharge.

The Planning Board finds that the provisions of Section 4.3.2 are satisfied.

4.3.3 Protection of Natural Vegetation

As indicated in Item 4.3.1 above, no natural areas were identified on the subject property.

The subject property is not located in any designated scenic area.

The applicant has indicated that the site plan was developed with an attempt to protect existing wooded area to the greatest extent possible.

As indicated on the landscape plan, the subject property will be improved with new plantings and fencing.

The Planning Board finds that the provisions of Section 4.3.3 are satisfied.

4.3.4 Protection of Significant Plant and Animal Habitat

As stated in Items 4.3.1, the proposed project is not located within the Town's

Wildlife Protection Overlay (WPO) District and no other mapped significant plant and animal habitats were identified during the review process. Therefore, the proposed project will not have an undue adverse effect on important plant and animal habitats identified by the Maine Department of Inland Fisheries and Wildlife, or on rare and irreplaceable natural areas as identified by the Maine Natural Areas Program.

The Planning Board finds that the provisions of Section 4.3.4 are not applicable.

4.3.5 Steep Slopes

The subject property on which the proposed project is to be constructed does not have any 5,000 square foot or more of contiguous slopes exceeding twenty-five percent (25%).

The Planning Board finds that the provisions of Section 4.3.5 are not applicable.

4.3.6 Erosion and Sedimentation

The applicant has provided an Erosion and Sediment Control Plan and Narrative demonstrating that the plans have been developed according to the DEP's Best Management Practices Handbook. The plan also provided post-construction requirements. Furthermore, an Inspection and Maintenance Plan and Log have been provided.

The Planning Board finds that the provisions of Section 4.3.6 are satisfied.

4.3.7 Groundwater

The subject property is not located with any of the Town's Aquifer Protection Overlay (APO) Districts. Sewage will be conveyed by a connection to the Brunswick Sewer District. The applicant has indicated that they will construct an extension from Brunswick and Topsham Water District's water main along Thomas Point Road. The above referenced Best Management Practices for stormwater runoff and erosion and sedimentation control will treat stormwater prior to discharge.

The Planning Board finds that the provisions of Section 4.3.7 are satisfied.

4.3.8 Surface Waters, Wetlands, and Marine Resources

The wetland delineation study found no surface waters or wetlands on the subject property.

The Planning Board finds that the provisions of Section 4.3.8 are not applicable.

4.3.9 Historic and Archaeological Resources

No historic or archaeological resources were identified within the subject property.

The Planning Board finds that the provisions of Section 4.3.9 are not applicable.

4.4. Flood Hazard Areas

The subject property is not located within the Flood Protection Overlay (FPO) District or mapped Flood Hazard Area.

The Planning Board finds that the provisions of Section 4.4. are not applicable.

4.5. Basic and Municipal Services

4.5.1 Sewage Disposal

The proposed project will connect to the Brunswick Sewer District System.

The Planning Board finds that the provisions of Section 4.5.1 are satisfied.

4.5.2 Water Supply and Quality

The applicant has indicated that they will construct an eight-inch (8") diameter extension approximately 702 feet from the nearest connection to the Brunswick and Topsham Water District.

The Planning Board finds that the provisions of Section 4.5.2 are satisfied

4.5.3 Solid Waste Disposal

The site plan includes a dumpster enclosure for solid waste disposal. The applicant has indicated that they will contract with a local commercial waste hauler.

The Planning Board finds that the provisions of Section 4.5.3 are satisfied.

4.5.4 Stormwater Management

The proposed project requires only a DEP Stormwater Permit by Rule. The applicant has included an approved permit as an addendum to this application.

The Planning Board finds that the provisions of Section 4.5.1 are satisfied.

4.6. Landscaping Requirements

The proposed landscape plan has been reviewed by the Town Codes Enforcement Officer and Town Arborist and found to be consistent with all applicable Zoning Ordinance landscape standards. The applicant has also provided amenities such as an internal green space, benches, bicycle racks, and an outdoor play area.

The Planning Board finds that the provisions of Section 4.6 are satisfied.

4.7. Residential Recreation Requirements

As there are no permanent residential dwelling units proposed, the residential recreation impact fees are not applicable to the proposed project.

The Planning Board finds that the provisions of Section 4.7 are not applicable.

4.8. Circulation and Access

4.8.1 Street Standards

No new streets are proposed as part of the project. The applicant provided a traffic study with an estimated sixteen (16) peak hour trips. This number falls below the one-hundred (100) trips that would trigger the need for a traffic movement permit from Maine DOT. Furthermore, the traffic associated with the proposed project is not anticipated to impact the existing level of service.

The Planning Board finds that the provisions of Section 4.8.1 are satisfied.

4.8.2 Circulation and Access

There is one (1) access point proposed. The Town Engineer did not state any concerns with the location and dimensions of the access point. However, an entrance permit from the Town Engineer will be required.

The Planning Board finds that the provisions of Section 4.8.2 are sastisfied.

4.8.3 Pedestrian and Bicycle Access

A network of internal paths and walkways, including a connection to the Wal-Mart shopping center, are proposed. Bicycle racks are provided on-site. Furthermore, the applicant has indicated their willingness to contribute to a sidewalk fund that will be used for the future Thomas Point Road improvements.

The Planning Board finds that the provisions of Section 4.8.3 are satisfied.

4.8.4 Access for Persons with Disabilities

The site plan has been developed in accordance with Americans with Disability Act (ADA) design standard. This includes access from two (2) ADA-compliant parking spaces with accessible routes to the building entrance. ADA-compliant ramps are provided where necessary.

The Planning Board finds that the provisions of Section 4.8.4 are satisfied.

4.9. Parking and Loading

The twenty-six (26) parking spaces (include two (2) ADA-compliant spaces) provided meet the minimum parking demand standards for homeless shelters established in Section 4.3.1.X of the Zoning Ordinance.

A bicycle rack for six (6) bicycles meets the minimum standard.

All parking spaces meet the minimum dimensional standards.

The Planning Board finds that the provisions of Section 4.9 are satisfied.

4.10. Lighting

The applicant has included spec sheets for full cut-off lighting fixtures to be used on the subject property. The included photometric plan indicates that there will be no light trespass onto surrounding properties. The applicant did not indicate the proposed color temperature for the outdoor lighting but is strongly encouraged not to exceed 3,000 Kelvin.

The Planning Board finds that the provisions of Section 4.10 are satisfied.

4.11. Architectural Compatibility

The applicant has included a memorandum from Ryan Senatore Architecture outlining the architectural treatments used to be consistent with the Cook's Corner Design Standards. Such traditional New England architectural features include its main gable roof with smaller gable dormers perpendicular to the main roof and gabled projecting bays.

Consistent with traditional New England architecture, the proposed windows are double-hung with mullions dividing the individual panes.

Proposed exterior material include fiber cement siding with battens and architectural asphalt shingles, both of which are used throughout the surrounding area.

The Planning Board finds that the provisions of Section 4.11 are satisfied.

4.12. Neighborhood Protection Standards

As the proposed project is surrounded by the GM4 Zoning District neighborhood protection standards do not apply.

The Planning Board finds that the provisions of Section 4.12 are not applicable.

4.13. Signs

The proposed project includes a monument and building mounted sign. The Town Codes Enforcement Officer reviewed the proposed signage and found it consistent with Section 4.13

The Planning Board finds that the provisions of Section 4.13 are satisfied.

4.14. Performance Standards

The applicant has indicated their ability to comply with all of the performance standards pertaining to noise, smoke and particulate matter, dust and fumes, odors,

vibrations, unlicensed motor vehicles, or lighting and glare. If approved, construction of the facility will occur between the permitted hours of 7:00 AM – 7:00 PM

The Planning Board finds that the provisions of Section 4.14 are satisfied.

4.15. Site Maintenance

The applicant has indicated that the proposed project will be maintained consistent with their standard in place at their existing locations. The stormwater management plan accounts for the necessary maintenance of BMPs. A Inspection and Maintenance Plan and Log is included with the application.

This finding serves to advise the applicant that site features constructed or installed as required by this development review must be maintained in good repair, and replaced if damaged or destroyed, or in the case of living materials, if they die or are effectively destroyed after installation.

The Planning Board finds that the provisions of Section 4.15 are satisfied.

4.16. Financial and Technical Capacity

The application includes a Purchase and Sale Agreement with the owner of the subject properties. Copies of the subject properties' deeds are also included. An updated letter, dated November 22, 2021, from Bath Savings Institute is included and indicates the applicant's financial capacity to completed the proposed project.

A performance guarantee is required prior to the construction of the infrastructure intended to be dedicated to the Brunswick and Topsham Water District. According to the applicant, the BTWD has indicated the potential that they will cover the cost difference between installing a twelve-inch (12") diameter water main rather than the proposed eight-inch (8") diameter water main.

The introduction letter includes all members of the project's design team and their associated qualifications.

The Planning Board finds that the provisions of Section 4.16 are satisfied, provided the applicant provide a performance guarantee to the Brunswick and Topsham Water District.

4.17. Administrative Adjustments / Alternative Equivalent Compliance

No administrative adjustments or alternative equivalent compliance plans are requested.

The Planning Board finds that the provisions of Section 4.17 are not applicable.

IV. EXHIBITS

A. Final Plan Major Development Review Application, dated November 23, 2021
B. Sketch Plan Major Development Review Documentation, dated September 8, 2021

APPROVED MOTION
CASE NO. 21-070
REVIEW DATE: JANUARY 11, 2022

APPROVED MOTION: That the Final Plan Major Development Review for the properties located at Map 42, Lots 8 and 11is approved with the following conditions:

1. That the Planning Board's review and approval does hereby refer to these findings of fact, the plans and materials submitted by the applicant and the written and oral comments of the applicant, his representatives, reviewing officials, and members of the public as reflected in the public record. Any changes to the approved plan not called for in these conditions of approval or otherwise approved by the Director of Planning and Development as a minor modification shall require a review and approval in accordance with the Brunswick Zoning Ordinance.

2. Prior to the issuance of a building permit, the applicant shall submit to the Department of Planning and Development a copy of a performance guarantee approved by the Brunswick and Topsham Water District.

3. Prior to the issuance of a building permit, the applicant shall submit to the Director of Planning and Development documentation depicting Lots 8 and 11 as consolidated.

4. Prior to the issuance of a building permit, the applicant shall submit to the Department of Planning and Development a copy of a letter from the Brunswick Sewer indicating their ability to serve the project.

5. Prior to the issuance of a Certificate of Occupancy, the applicant shall submit to the Department of Planning and Develop an as-built construction plan per the request of the Cumberland County Soil and Water Conservation District.

6. Should within the next five (5) years the Town of Brunswick fund improvements to Thomas Point Road, as proposed in the existing Capital Improvement Plan, the applicant, prior to the start of said improvements, shall contribute funds for materials, mutually agreed upon in cost, for a sidewalk along the subject properties' Thomas Point Road frontage, not to exceed 387 feet in length. Should the Town not commence construction of the sidewalk within five (5) years of the date of approval this condition shall become null and void.

First: Kelly Matzen Second: Jane Arbuckle Vote: 7-0-0

Tedford Housing

Officers

Toni Kemmerle
President

Andrew Lardie
Vice President

John Gallagher
Treasurer

Jamie Pacheco
Secretary

Kevin Bunker
At Large

Patti Lawton
Past President

Directors

Donna Chale
Anna Cockrell
Cynthia Dechenes, MD
Carolyn Eklund
Robert Elder
Mark Publicker
Ann Rush
Nonny Soifer
Robert Stuart
Scott Upham

November 22, 2021

Matt Panfil, Director
Jared Woolston, Planner
Town of Brunswick Planning and Development
85 Union Street
Brunswick, ME 04011

Re: Tedford Housing financial capacity

Dear Matt:

Regarding Tedford's ability to meet the Specific Standards for financial capacity I offer the following:

Specific Standard (1): Right, title, and interest are provided in this application under separate cover.

Specific Standard (2)(a): A professional cost estimate has been performed and has informed the sources and uses table below.

Specific Standard (2)(b): We estimate a 12-month construction period for this project, beginning in the Fall of 2022.

Specific Standard (2)(c)(iv)(B): The following sources and uses table illustrates the financing plan for the project.

Tedford Resource Center Sources & Uses

Uses	Permanent	Construction Period
Acquisition	465,000	465,000
Hard Costs	7,129,016	7,129,016
Soft Costs	521,390	521,390
Financing Costs	84,500	84,500
Total	8,199,906	8,199,906

Sources		
Lead Grant	3,000,000	3,000,000
Supplemental Grants	400,000	400,000
Philanthropic Commitments	799,906	799,906
Construction Bridge Loan		4,000,000
Capital Campaign	4,000,000	
Total	8,199,906	8,199,906

Projections for and status of any fundraising is as follows:

1. For the lead grant, we expect notification in the Winter of 2021.
2. For the supplemental grants (governmental organizations) and Philanthropic commitments (private foundations), sources have been identified and we expect applications and notification in Spring of 2022.

United Way

United Way of Mid Coast Maine

United Way of Androscoggin County

EQUAL HOUSING OPPORTUNITY

P.O. Box 958, Brunswick, Maine 04011-0958 ▪ Office 207-729-1161 ▪ Fax 207-725-7626
info@tedfordhousing.org ▪ www.tedfordhousing.org ▪ facebook.com/tedfordhousing

Tedford Housing

Officers

Toni Kemmerle
President

Andrew Lardie
Vice President

John Gallagher
Treasurer

Jamie Pacheco
Secretary

Kevin Bunker
At Large

Patti Lawton
Past President

Directors

Donna Chale
Anna Cockrell
Cynthia Dechenes, MD
Carolyn Eklund
Robert Elder
Mark Publicker
Ann Rush
Nonny Soifer
Robert Stuart
Scott Upham

3. The capital campaign work is ongoing. We have retained a capital campaign consultant, have been holding regular meetings, and have a capital campaign strategy plan with major and supplemental donors identified. We anticipate the fundraising to be complete by Summer 2022.
4. The Construction Bridge Loan will be contingent upon reaching other successful fundraising projections/targets and will close just prior to construction start, in Fall 2022.

Specific Standard (2)(d): Not applicable.

Specific Standard (2)(e): Evidence of existence and good standing provided elsewhere in this application.

Finally, in additional support of our financial capacity, I enclose an updated letter from Bath Savings Institution.

Sincerely,

Rota L. Knott
Executive Director

United Way

United Way of Mid Coast Maine

United Way of Androscoggin County

EQUAL HOUSING OPPORTUNITY

P.O. Box 958, Brunswick, Maine 04011-0958 ▪ Office 207-729-1161 ▪ Fax 207-725-7626
info@tedfordhousing.org ▪ www.tedfordhousing.org ▪ facebook.com/tedfordhousing



Benj. F. Packard

Bath Savings Institution

Since 1852

November 22, 2021

Re: Tedford Housing
Cook's Corner Tedford Housing Building
$8.2 Million project

To Whom It May Concern:

Tedford Housing has been a Bath Savings Customer since 2015. They have always handled their deposit and loan accounts as agreed and are in good standing.

Bath Savings Institution ("Bank") has reviewed preliminary information for the proposed Project. Based on the Bank's experience with Tedford Housing, our knowledge of its Board of Directors and the information reviewed, the Bank believes they will have the ability and financial capacity to complete this project on time and on budget. While this letter is not a commitment to lend, Bath Savings Institution looks forward to a detailed review of the project and a potential commitment to support this need in our community, subject to our standard underwriting guidelines.

This letter is only a confirmation of Tedford Housings' relationship and capacity, and shall in no way obligate the Bank, or our customer, beyond the scope and intent of this letter.

Please feel free to contact me with questions.

Sincerely,

Julie Wagoner
SVP – Community Development and Commercial Lending

105 Front Street, PO Box 548, Bath, Maine 04530
Tel. 207-442-7711 Fax 207-442-9137
1-800-447-4559
Member FDIC

State of Maine

Department of the Secretary of State

I, the Secretary of State of Maine, certify *that according to the provisions of the Constitution and Laws of the State of Maine, the Department of the Secretary of State is the legal custodian of the Great Seal of the State of Maine which is hereunto affixed and of the reports of organization, amendment and dissolution of corporations and annual reports filed by the same.*

I further certify *that TEDFORD HOUSING, formerly TEDFORD SHELTER, formerly TEDFORD-OASIS PROGRAMS, INC., formerly BRUNSWICK AREA CHURCH COUNCIL SHELTER, INC. is a duly organized nonprofit corporation without capital stock under the laws of the State of Maine and that the date of incorporation is December 17, 1986.*

I further certify *that said nonprofit corporation has filed annual reports due to this Department, and that no action is now pending by or on behalf of the State of Maine to forfeit the charter and that according to the records in the Department of the Secretary of State, said nonprofit corporation is a legally existing nonprofit corporation in good standing under the laws of the State of Maine at the present time.*

In testimony whereof, I have caused the Great Seal of the State of Maine to be hereunto affixed. Given under my hand at Augusta, Maine, this twenty-third day of November 2021.

Shenna Bellows

Shenna Bellows

Secretary of State

Town of Brunswick, Maine

PLANNING BOARD

85 UNION STREET, BRUNSWICK, ME 04011

NOTICE TO ABUTTERS

A project has been submitted to the Brunswick Planning and Development Office:

Case No. 24-076 – Extension Request for Tedford Housing Site Plan Major Development Review Approval: The Planning Board will review and act on a **Site Plan Major Development Review Approval Extension Request** of the approved Case No. 21-70, Tedford Housing Homeless Shelter, Resource Center, submitted by the property owner, Tedford Housing. The subject property is located at 65 Thomas Point Road (Map 42, Lot 8) and within the **Growth Mixed-Use 4 (GM4) Zoning District**.

The Town property records indicate that you own property within **300 feet** of the parcel where this is proposed.

The application is available for review at the Planning and Development Department. To receive an electronic copy, please email Julie Erdman (jerdman@brunswickme.gov). If you would like further notice on the application or scheduled meeting dates, please visit the Town website at www.brunswickme.gov and click on the 'Notify Me' box on the home page. Under 'Agenda Center', select Staff Review Committee and Planning Board to be notified of development review meeting agendas as they are posted.

You may submit written comment to the Planning and Development Office or by email to the Director of Planning and Development, Julie Erdman (jerdman@brunswickme.org) by no later than noon on the meeting date.

This notice is in accordance with Section 5.2.K.3 of the Brunswick Zoning Ordinance which requires abutter notice for applications including consideration of a conditional or special use permit.

BECKFORD, ROHAN L
RE: Parcel 42-6
149B OLD BATH RD ,
BRUNSWICK , ME 04011
.

BRIGGS, TIFFANY A
RE: Parcel 42-5A
51 THOMAS PT RD ,
BRUNSWICK , ME 04011
.

BRUNSWICK MZL LLC
RE: Parcel CC1-15
535 5TH AVE 12TH FLOOR ,
NEW YORK , NY 10017
.

FAIR WINDS INC
RE: Parcel 42-10
68 THOMAS PT RD ,
BRUNSWICK , ME 04011
.

GREATER BRUNSWICK HOUSING CORP
RE: Parcel CC1-37
PO BOX A ,
BRUNSWICK , ME 04011
.

GREATER BRUNSWICK HOUSING CORP
RE: Parcel 42-12
PO BOX A ,
BRUNSWICK , ME 04011
.


KELLEY, PAUL TRUSTEE OF REVOCABLE TRUST
RE: Parcel 42-2
PO BOX 189 ,
BRUNSWICK , ME 04011
.

MAINE BLUE SHELLFISH INC
RE: Parcel 42-7
C/O CAPE COD SHELLFISH & SEAFOOD CO INC , 8 SEAFOOD WAY UNITS 2-3
BOSTON , MA 02210
.

TEDFORD HOUSING
RE: Parcel 42-8
PO BOX 958 ,
BRUNSWICK , ME 04011
.

TROMBLEY, RAYMOND H
RE: Parcel 42-16A
93 THOMAS POINT RD ,
BRUNSWICK , ME 04011
.

WAL-MART REAL ESTATE BUSINESS TRUST
RE: Parcel CC2-20
PROPERTY TAX DEPT-STORE #1939 , PO BOX 8050 MS 0555
BENTONVILLE , AR 72716-0555
.


Farley Rd
Farley Rd
Bath Rd
Tibbetts D
(pvt)
Thomas Point Rd
Gurnet Rd
Stephen Dr (pvt)
Thomas Point Rd
Landing Dr
Forrestal Dr (pvt)
Beacon Drive (pvt)

Town of Brunswick, Maine

DEPARTMENT OF PLANNING & DEVELOPMENT

MEMORANDUM

TO: Planning Board

FROM: Julie Erdman, Director of Planning and Development

DATE: January 28, 2025

SUBJECT: Tedford Site Plan Extension

A Site Plan Approval Extension has been requested by St. Clair Associates on behalf of Tedford Housing, for Case# 21-070 Tedford Housing Homeless Shelter, Resource Center which was approved by the Planning on Board on January 11, 2022. Pursuant to 5.2.9.Q. of the Brunswick Zoning Ordinance, a letter requesting the extension was received by the Planning Department on December 30, 2024; prior to site plan's date of expiration (January 11, 2025). As required, the letter details the reason for the request with the applicant citing fundraising to support the project as the major cause for delay.

The applicant intends to make minor changes to the approved plan which are stipulated in the attached letter. These revisions have been reviewed by staff and qualify as minor modifications. The applicant has been advised that the Planning Department may proceed with review of the minor modification application if the site plan extension is granted by the Planning Board.

The Brunswick Zoning Ordinance states the review authority may extend approval of a site plan but is not specific on the time constraints, consequently I advise the Planning Board to place an expiration on the extension should it choose to approve the request. The applicant states their intention to have the project completed later this calendar year, therefore an extension of one year should be adequate to complete substantial improvements as specified in Subsection 5.2.9.Q. The site plan and final findings of fact are attached for your reference.

DRAFT MOTION
TEDFORD HOUSING HOMELESS SHELTER, RESOURCE CENTER APPROVAL EXTENSION REQUEST
CASE NUMBER: 24-076

Motion 1: That the Tedford Housing Homeless Shelter, Resource Center (Case# 21-070) Approval is extended until January 11, 2026 with the following conditions:

1. All agreed upon conditions of the initial January 11, 2022 approval remain in effect.

St.Clair Associates
Land Surveying and Civil Engineering
34 Forest Lane
Cumberland, Maine 04021

21012 December 30, 2024

Julie Erdman, Director of Planning Development
Town of Brunswick Planning and Development
85 Union Street
Brunswick, ME 04011

Request for Site Plan Approval Extension and
Request for Minor Modification
Major Development Plan & Conditional Use
Tedford Housing Building (Case # 24-020)
65 Thomas Point Road
Assessor's Map 42, Lots 8 and 11
Brunswick, ME

Dear Ms. Erdman,

On behalf of Tedford Housing, we have prepared this two-part application to seek an extension of Site Plan Approval and Minor Site Revisions to address further detailing associated with site construction. We offer the following for your review:

Request for Site Plan Approval Extension

As you know, on May 14, 2024 the Brunswick Planning Board issued a re-approval of the Conditional Use Permit for Tedford Housing's new facility on Thomas Point Road. Previously, on January 11, 2022 the Brunswick Planning Board granted unanimous approvals of a Conditional Use Permit and the Final Major Development Review for Tedford Housing on Thomas Point Road. At the time of re-approval of the Conditional Use Permit, the Site Plan Approval had not lapsed (and will not lapse until January 11, 2025) and did not require re-approval.

We are respectfully requesting that the staff and Planning Board consider this request for extension of the Applicant's Site Plan Approval (Final Major Development Review), given the fact that the building is currently under construction but will not be ready for

occupancy by the date associated with the original Site Plan Approval (January 11, 2025).

As you may be aware, subsequent to the original Approvals in 2022, the Applicant continued its Capital Campaign to raise funds to support the construction of this new facility, including pursuit of Federal funding support. The fundraising process has been lengthy but finally reached the point to allow construction to proceed this fall. However, given the timing of this process, including the time necessary to complete the Federal level reviews, the construction will not be sufficiently complete to allow building occupancy by January 11, 2025. It is anticipated that the building will be completed for occupancy in late 2025. Given this timing, we are respectfully requesting an extension of the Applicant's Site Plan Approval (Final Major Development Review).

Request for Minor Modification

In addition, we have prepared the enclosed materials in support of a proposed Minor Modification to the Tedford Housing Site Plan. We have prepared the enclosed Minor Modification Application to accompany the revised plans associated with this site.

It is our understanding that as part of this process, you will and other staff members will evaluate the materials to determine whether the proposed changes qualify for a staff-level review process, or whether the proposed changes warrant a return to the Planning Board.

It is important to note that the building's size and location on the lot have not changed, the amount of parking spaces have not changed and the driveway location has not moved. The following section describes the proposed minor modifications in further detail.

Proposed Minor Changes

- Sheet naming and numbering revisions on the Site Plan drawings:

  To support the bidding and construction process these minor revisions were made. Since the Site Plan drawings are now included in a larger construction set which includes all the drawings associated with the architectural, structural, mechanical, electrical, and plumbing drawings these naming and numbering changes were made. Additional details and clarifications have also been added to address contractor questions during

the bidding process. These changes were made to clarify and further detail the design of the site elements with no changes to the overall design intent.

- Addition of walkway to mechanical room:

  As part of the conditional use review and reapproval of the project, in May of this year, the Fire Department requested that a paved walkway be added from Thomas Point Road to the mechanical room located along the front of the building. This short, paved walkway has been added, as requested.

- Paving of walkway through rear of site:

  As you know the original Site Plan included a walkway through the rear of the site to provide pedestrian access to the abutting Walmart property. The surface of this walkway had been proposed as mulch on the previously approved plan. The Applicants have proposed that the surface of this walkway be a material that can be maintained year-round. Accordingly, the Applicants are proposing that this walkway be paved. There are no proposed changes to the route of the walkway.

- Pedestrian Scale Walkway Lighting:

  In order to facilitate safe pedestrian use of the walkway, pedestrian scale lighting has been added along the walkway through the rear of the site. An updated lighting and photometrics plan has been prepared to demonstrate compliance with the local lighting criteria. A copy of this updated lighting plan is enclosed.

- Sewer Service Revisions:

  The building's proposed sewer service has been modified to address the connection to the discharge point for the internal plumbing. In addition, when the contractor excavated the existing manhole in Thomas Point Road, it was discovered that the existing manhole structure would not allow connection at the original design invert. The invert was modified and the service slope was adjusted to accommodate this existing condition. The proposed sewer service modifications were reviewed with the Brunswick Sewer Department and found to be acceptable.

- Addition of Door at Easterly Wall:

  As part of the further detailing of the interior floor plans for the building, an egress door and threshold were added along the easterly wall. This door is located at the end of a hall in the office area and will allow an additional exit from the office area, if needed. This door is not a public access and is not available for the residents' use.

- Mechanical Unit Locations:

  As part of the detailed mechanical systems design for the building there are a series of small exterior pad mounted mechanical units that are placed along the outer edges of the building. These unit locations have been added to the plan.

- Proposed future generator pad:

  As part of the original design there was a rectangular paved area off the northeasterly edge of the parking lot. This rectangular area was intended to provide access to the previously proposed gravel wetlands in the area for maintenance. With the prior elimination of this BMP (as approved in the prior modifications in late 2023) this pad area was not being used. This paved pad has been converted to a proposed concrete pad to allow for future placement of a backup generator.

Review Criteria for Minor Changes

It is our understanding that a minor modification is allowed under certain conditions which are established in the Brunswick Zoning Ordinance in Chapter 5.2.10.B. We have addressed each of the 6 bulleted items contained in the Ordinance below. For ease of review, the criteria are shown in *italics*, along with our response, as follows:

- *Does not materially alter the layout or scale of the development or its impact on its surroundings;*

As noted above, the overall site layout and scale are not materially altered by these proposed minor changes. The building location, orientation, size and overall program elements remain as previously approved. No changes are proposed to the site entrance, parking layout and number of parking spaces.

- *Does not increase the number of lots or dwelling units;*

There are no proposed changes with regard to lots or dwelling units.

- *Does not violate provisions of any Town Ordinance;*

The proposed changes have been designed in accordance with the applicable Ordinance standards.

- *Does not reduce the effectiveness of the approved landscaping, screening, or buffering of the site;*

The proposed minor changes do not modify the provisions of landscaping, screening or buffering of the site included in the prior approved plans.

- *Does not significantly alter on-site vehicular circulation; and*

No changes are proposed to the vehicular circulation patterns on the site. The previously approved parking layout remains unchanged, no changes are proposed with regard to the driveway location or width or number of parking spaces on the site.

- *Does not significantly alter drainage patterns.*

As noted above, the proposed site changes include modifications to the walkway surface material through the rear of the site. No grading changes were made as part of this modification. As such, no changes to the overall site drainage patterns occurred. Our office also evaluated the change in impervious cover associated with the conversion of the walkway surface to pavement. This increase in impervious cover did not alter the overall curve number (CN) of the subcatchment that includes the walkway. As such, there are no anticipated increases in peak discharge for this subcatchment.

Application Materials

We have included five copies of the following materials in support of the applicant's request for an extension of the project's Site Plan Approval and Minor Modification to the previously approved Final Major Development/Conditional Use for Tedford Housing:

- Cover Letter/Project Description
- Minor Modification Application Form
- Revised Site Plan Set (including a revised Photometric Plan)

Please note that in addition to the plan information cited above, a check for the Minor Modification Application fee, in the amount of $250.00, is being delivered directly by the Applicant, under separate cover, to be included as part of this submittal package.

Closure

With the submittal of the materials listed above, we are respectfully requesting staff consideration of this request for an extension of the project's Final Major Development Review approval and approval of these proposed Minor Site Plan changes under the Brunswick Ordinance provisions for a Minor Modification to the Planning Board's prior approval for Final Major Development/Conditional Use review for this project, as described above.

As the enclosed Plans, and this letter demonstrate, the Applicant is proposing minor modifications to the site that are intended to allow the project to be constructed while still maintaining the integrity of the previously approved plans.

We are confident that you and other staff members will concur with our assessment that the enclosed Plan revisions are within the criteria for review as a Minor Modification.

We are available to meet with you if you have any additional questions as you review the enclosed materials. We look forward to hearing from you after you have had a chance to further review these requests.

We look forward to hearing from you.


Sincerely,

ST.CLAIR ASSOCIATES

Nancy J. St.Clair, P.E.
Vice President
NJS:njs

Andrew Lardie, Executive Director Tedford Housing
Danielle Triffitt, Director of Administration, Tedford Housing
Tim Schneider, Sage Stone Consulting


SITE PLAN
TEDFORD HOUSING



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.



LOCATION MAP N.T.S.

APPLICANT:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

CIVIL ENGINEER:
ST.CLAIR ASSOCIATES
34 FOREST LANE
CUMBERLAND, ME 04021

LANDSCAPE ARCHITECT:
ACETO LANDSCAPE
ARCHITECTS
LANDSCAPE
ARCHITECTURE
PORTLAND, ME

SHEET INDEX:


SHEET	DESCRIPTION
C-100	COVER SHEET
C-200	EXISTING CONDITIONS PLAN
C-300	SITE PLAN
C-400	GRADING PLAN
L1-00	LANDSCAPE PLAN
L2-00	LANDSCAPE DETAILS
L2-01	LANDSCAPE DETAILS
L3-00	PHOTOMETRICS PLAN
C-700	DETAILS
C-701	DETAILS
C-702	DETAILS
C-703	DETAILS
C-800	PRE DEVELOPMENT WATERSHED MAP
C-900	POST DEVELOPMENT WATERSHED MAP



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.



LOCATION MAP N.T.S.

GENERAL NOTES

1) THE RECORD OWNER OF THE PROPERTY IS TEDFORD HOUSING AS DESCRIBED IN A DEED RECORDED AT THE CUMBERLAND COUNTY REGISTRY OF DEEDS IN BOOK 39438 PAGE 307.

2) THE PROPERTY IS SHOWN ON THE TOWN OF BRUNSWICK TAX MAP 42 BEING SHOWN AS LOT 8.

3) THE BEARINGS AND NORTH ORIENTATION IS BASED UPON GRID NORTH, NORTH AMERICAN DATUM OF 1983 MAINE WEST ZONE. THE CONTOURS AND ELEVATIONS SHOWN HEREON ARE REFERENCED TO NORTH AMERICAN VERTICAL DATUM OF 1988.

4) PLAN REFERENCES:

A) PLAN OF STANDARD BOUNDARY SURVEY FOR C C LAND DEVELOPERS, ETAL DATED MAY 20, 1993 BY PAUL H. RUOPP JR., PLS AND RECORDED IN PLAN BOOK 194 PAGE 62.

5) THE PROPERTY SHOWN HEREON IS SUBJECT TO AND BENEFITED ALL MATTERS OF RECORD ON FILE AT THE CUMBERLAND COUNTY REGISTRY OF DEEDS.

6) ALL GRADING AND UTILITIES SHOWN HEREON ARE SCHEMATIC ONLY AND ALL PROPOSED INVERTS AND SPOT ELEVATIONS ARE SUBJECT TO CHANGE UPON FURTHER DETAILED SITE DESIGN.

7) A WETLAND DELINEATION WAS COMPLETED BY MARK HAMPTON ASSOCIATES, INC. AS STATED IN A LETTER DATED AUGUST 3, 2021. THE LETTER STATES NO WETLANDS WERE FOUND ON THE PROPERTY.

8) THE LOCATION OF EXISTING TREES 10" IN DIAMETER OR GREATER HAVE BEEN DEPICTED ON THIS SURVEY PLAN.

9) DURING THE FIELD SURVEY, DEBRIS AND TRASH WAS OBSERVED ON THE PROPERTY INCLUDING CHUNKS OF CONCRETE.

10) THIS PLAN IS BASED UPON A BOUNDARY SURVEY PERFORMED IN ACCORDANCE WITH THE STATE OF MAINE BOARD OF LICENSURE FOR PROFESSIONAL LAND SURVEYORS STANDARDS OF PRACTICE WITH THE EXCEPTION THAT NO REPORT OF SURVEY HAS BEEN PREPARED, NO NEW LEGAL DESCRIPTION HAS BEEN PREPARED AND THAT THE PROPOSED MONUMENTATION SHOWN HEREON HAS NOT BEEN SET AT THE ISSUANCE OF THIS PLAN.

SPACE & BULK REQUIREMENTS

THE PROPERTY IS LOCATED IN THE TOWN OF BRUNSWICK GROWTH MIXED-USE 4 (GM4). THE SPACE AND BULK REQUIREMENTS FOR THE GM4 ZONING DISTRICT ARE AS FOLLOWS:

	REQUIRED
MINIMUM LOT SIZE:	7,000 S.F.
MINIMUM FRONT YARD SETBACK:	0 FEET
MINIMUM SIDE YARD SETBACK:	0 FEET
MINIMUM REAR YARD SETBACK:	15 FEET
MAXIMUM BUILDING HEIGHT:	60 FEET
MAXIMUM IMPERVIOUS COVER:	80%

SOILS LEGEND

1) SOILS TYPE

LABEL	SOIL NAME	SLOPE	HYDROLOGIC SOIL GROUP
Au	AU GRES LOAMY SAND	0% TO 3% SLOPES	HSG A
Wa	WALPOLE FINE SANDY LOAM	0% TO 3% SLOPES	HSG A

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	●
	BUILDING	
	EDGE PAVEMENT	
	TRAIL	
--122--	CONTOURS	--120--
30.20	SPOT GRADE	
S	SEWER	
Ⓢ	SEWER MH	
	TREELINE	
	CULVERT	
	SOILS BOUNDARY	
OHE	OVERHEAD ELEC. & TEL.	
	UTILITY POLE	
	DECIDUOUS TREE	
	CONIFEROUS TREE	

DAVID C. ST. CLAIR, JR. 2317 PROFESSIONAL LAND SURVEYOR STATE OF MAINE

REV:	BY:	DATE:	STATUS:
E	DCS	12-30-2024	FOR TOWN REVIEW
4	DCS	05-03-2024	ASI-001
D	DCS	10-20-2023	REVISED PLAN FOR TOWN REVIEW
C	DCS	02-03-2022	CONDITIONS OF APPROVAL
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland Foreside, ME 04021
Tel (207) 829-5558


PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST

EXISTING CONDITIONS PLAN
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET C-200

21012S TAB 21012EC




GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)

1 inch = 30 ft.



LOCATION MAP N.T.S.

GENERAL NOTES

1) THE RECORD OWNER OF THE PROPERTY IS TEDFORD HOUSING AS DESCRIBED IN A DEED RECORDED AT THE CUMBERLAND COUNTY REGISTRY OF DEEDS IN BOOK 39438 PAGE 307.

2) THE PROPERTY IS SHOWN ON THE TOWN OF BRUNSWICK TAX MAP 42 BEING SHOWN AS LOT 8.

3) THE BEARINGS AND NORTH ORIENTATION IS BASED UPON GRID NORTH, NORTH AMERICAN DATUM OF 1983 MAINE WEST ZONE. THE CONTOURS AND ELEVATIONS SHOWN HEREON ARE REFERENCED TO NORTH AMERICAN VERTICAL DATUM OF 1988.

4) PLAN REFERENCES:

A) PLAN OF STANDARD BOUNDARY SURVEY FOR C C LAND DEVELOPERS, ETAL DATED MAY 20, 1993 BY PAUL H. RUOPP JR., PLS AND RECORDED IN PLAN BOOK 194 PAGE 62.

5) THE PROPERTY SHOWN HEREON IS SUBJECT TO AND BENEFITED ALL MATTERS OF RECORD ON FILE AT THE CUMBERLAND COUNTY REGISTRY OF DEEDS.

6) A WETLAND DELINEATION WAS COMPLETED BY MARK HAMPTON ASSOCIATES, INC. AS STATED IN A LETTER DATED AUGUST 3, 2021. THE LETTER STATES NO WETLANDS WERE FOUND ON THE PROPERTY.

7) THE LOCATION OF EXISTING TREES 10" IN DIAMETER OR GREATER HAVE BEEN DEPICTED ON THIS SITE PLAN.

8) THE PROPOSED DEVELOPMENT SHALL BE SERVICED BY PUBLIC WATER AND PUBLIC SEWER, AND UNDERGROUND ELECTRIC, TELEPHONE AND CABLE TV SERVICES.

9) THE TOWN OF BRUNSWICK ENGINEERING DEPARTMENT RESERVES THE RIGHT TO REQUEST ADDITIONAL WORK BEYOND WHAT IS SHOWN ON THE PLAN DUE TO UNKNOWN SITE CONDITIONS. ANY CHANGES MADE DURING CONSTRUCTION SHALL BY COORDINATED WITH THE TOWN OF BRUNSWICK ENGINEERING DEPARTMENT.

10) A PRECONSTRUCTION MEETING IS REQUIRED BEFORE START OF CONSTRUCTION. THE MEETING SHALL INCLUDE APPROPRIATE TOWN STAFF, THE DEVELOPER AND HIS CONTRACTOR, AND UTILITY COMPANY REPRESENTATIVES. ANY PLAN REVISIONS REQUIRED AS A RESULT OF THE MEETING SHALL BE PROVIDED TO ALL PARTIES ASSOCIATED WITH THE PROJECT.

11) THE PROPERTY SHOWN ON THE APPROVED SITE PLAN MAY BE DEVELOPED AND USED ONLY AS SHOWN ON THE PLAN. ALL ELEMENTS AND FEATURES OF THE PLAN AND ALL REPRESENTATIONS MADE BY THE APPLICANT WHICH APPEAR IN THE RECORD OF THE PLANNING BOARD PROCEEDINGS ARE CONDITIONS OF APPROVAL. NO CHANGE FROM THE CONDITIONS OF APPROVAL IS PERMITTED UNLESS AN AMENDED SITE PLAN IS APPROVED BY THE PLANNING BOARD.

12) ALL POLE MOUNTED AND BUILDING MOUNTED LIGHT FIXTURES SHALL BE EQUIPPED WITH PHOTOCELLS THAT CONTROL THE SITE LIGHTING TO TURN ON AT DUSK AND WILL DIM AT 7 PM. ONLY SECURITY LIGHTING WILL REMAIN ON OVERNIGHT. ALL LIGHTING WILL TURN OFF AT DAWN.

13) SNOW STORAGE IS ONLY ALLOWED IN THE DESIGNATED AREAS SHOWN HEREON. SNOW STORAGE MAY NEED TO BE REMOVED FROM THE SITE AS NECESSARY. NO SNOW STORAGE IS ALLOWED IN STORMWATER MANAGEMENT STRUCTURES.

14) SEE LANDSCAPE ARCHITECT PLANS, RE: L100 FOR ANY PLANTING/ SEEDING AREA, INCLUDING GRAVEL WETLAND BASIN.

SPACE & BULK REQUIREMENTS

THE PROPERTY IS LOCATED IN THE TOWN OF BRUNSWICK GROWTH MIXED-USE 4 (GM4). THE SPACE AND BULK REQUIREMENTS FOR THE GM4 ZONING DISTRICT ARE AS FOLLOWS:

	REQUIRED	PROPOSED
MINIMUM LOT SIZE:	7,000 S.F.	133,075 S.F.
MINIMUM FRONT YARD SETBACK:	0 FEET	25 FEET
MINIMUM SIDE YARD SETBACK:	0 FEET	26.7 FEET
MINIMUM REAR YARD SETBACK:	15 FEET	106.16 FEET
MAXIMUM BUILDING HEIGHT:	60 FEET	1 STORY
MAXIMUM IMPERVIOUS COVER:	80%	28.34%
PROPOSED IMPERVIOUS SURFACE: (ONSITE BUILDING & PAVEMENT)		37,724 S.F.
PROPOSED IMPERVIOUS SURFACE: (OFFSITE BETWEEN ROW & THOMAS POINT RD)		837 S.F
TOTAL PROPOSED IMPERVIOUS SURFACE:		39,951 S.F.
TOTAL LANDSCAPE AREA:		52,608 S.F.
PROPOSED DEVELOPED AREA:		91,294 S.F.

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	
	BUILDING	
	EDGE PAVEMENT	
	EDGE OF GRAVEL	
	RAMP	R
--122-- --120--	CONTOURS	
30.20	SPOT GRADE	+30.20
-S-	SEWER	-S-
	SEWER MH	
	UNDERDRAIN	UD
	CATCH BASIN	
	UNDERGROUND ELEC. & TEL.	UGT/E
OHE	OVERHEAD ELEC. & TEL.	
	UTILITY POLE	
	GATE VALVE	
	HYDRANT	
	TREELINE	
	DECIDUOUS TREE	X
	CONIFEROUS TREE	X

REV:	BY:	DATE:
E	DCS	05-03-2024
4	DCS	03-26-2024
3	DCS	10-20-2023
D	DCS	05-05-2022
2	DCS	05-05-2022
1	DCS	02-03-2022
C	DCS	11-23-2021
B	DCS	10-05-2021
A	DCS	12-30-2024

STATUS: FOR TOWN REVIEW

ASI 001 CHANGE TRAIL MATERIAL TO PAVEMENT
ADD DOOR, ADJUST HVAC UNIT & SIDEWALK MATERIAL
REVISED PLAN FOR TOWN REVIEW
UPDATE GRADING
MOVE TRANSFORMER PAD, ADD HVAC PADS
CONDITIONS OF APPROVAL
FOR TOWN REVIEW
FOR TOWN REVIEW

THIS PLAN, SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

STATE OF MAINE — NANCY J. ST. CLAIR No. 6877 — REGISTERED LAND SURVEYOR — 12/30/2024

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland Foreside, ME 04021
Tel (207) 829-5558


PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST

SITE PLAN
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET C-300

21012S TAB 21012S



GENERAL NOTES

1) THE CONTRACTOR SHALL REVIEW AND FAMILIARIZE THEMSELVES WITH ALL THE GENERAL NOTES AND CONSTRUCTION NOTES WITHIN THE DESIGN PLAN SHEETS AND DETAILS SHEET OF THIS DESIGN PLAN SET.
2) THE PROPOSED STORMDRAIN PIPES SHALL BE HDPE SMOOTHBORE OR APPROVED EQUAL.
3) PROVIDE 2" RIGID STYROFOAM INSULATION IN ALL AREAS WHERE DEPTH OF COVER IS LESS THAN 4'.
4) UNLESS OTHERWISE NOTED, THE LIGHT POLES SHALL BE NO HIGHER THAN 12-FEET TO 16-FEET HIGH.
5) INSTALL INLET PROTECTION IN ALL CATCH BASIN AND STORM DRAIN INLETS.
6) PER ADA REQUIREMENTS, ALL BARRIER FREE PARKING SPACES AND ACCESS AISLES SHALL BE CONSTRUCTED WITH NO MORE THAN 2% SLOPES IN ANY DIRECTION. ANY CONFLICTS TO THIS REQUIREMENT AS A RESULT OF FIELD CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN ENGINEER FOR REVIEW AND FURTHER EVALUATION.
7) PER ADA REQUIREMENTS, ALL SIDEWALKS SHALL HAVE A MAXIMUM RUNNING SLOPE OF 5% WITH A MAXIMUM OF A 2% CROSS SLOPE. HANDICAP RAMPS SHALL NOT EXCEED A 1 IN 12 SLOPE (8.33%), WITH A 5 FOOT LONG LANDING AT EACH END. LANDING SLOPE SHALL NOT EXCEED 2%.
8) CONTRACTOR SHALL REFER TO THE LATEST APPLICABLE VERSION OF THE ADA REQUIREMENTS FOR ADDITIONAL INFORMATION.
9) WATER MAINS 4-INCH OR GREATER IN DIAMETER SHALL BE DUCTILE IRON, CLASS 52.
10) MINIMUM DEPTH OF COVER OVER WATER MAIN SHALL BE 5'-0"
11) MAINTAIN 10-FEET HORIZONTAL SEPARATION FROM SEWER AND GAS PIPELINES.
12) INSULATE WATER MAIN PIPE TRENCH WHERE MAIN CROSSES OR IS LOCATED WITHIN 5 FEET OF CULVERTS AND DRAINS.
13) WATER MAINS HAVING HYDRANT BRANCHES SHALL BE 8-INCH MINIMUM DIAMETER.
14) BLOWOFF SIZE SHALL BE 2-INCH FOR MAINS 4-INCHES OR LARGER IN DIAMETER.
15) DOMESTIC WATER SERVICE SHALL MEET THE BRUNSWICK & TOPSHAM WATER DISTRICT STANDARDS.
16) WATER MAIN MATERIALS SHOULD BE PURCHASED FROM THE BRUNSWICK & TOPSHAM WATER DISTRICT TO ENSURE MATERIALS MEET SPEC.
17) ALL FITTINGS, VALVES, BLOW OFFS AND HYDRANTS SHALL BE RESTRAINED.
18) SEE LANDSCAPE ARCHITECT PLANS, RE: L100 FOR ANY PLANTING/ SEEDING AREA, INCLUDING GRAVEL WETLAND BASIN.

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	
	BUILDING	
	EDGE PAVEMENT	
	EDGE OF GRAVEL	
--122--	CONTOURS	124
30.20	SPOT GRADE	+30.20
S	SEWER	S
Ⓢ	SEWER MH	Ⓢ
	UNDERDRAIN	UD
	UNDERGROUND ELEC. & TEL.	UGT/E
SD	STORM DRAIN	SD
	CATCH BASIN	
	GATE VALVE	
	HYDRANT	
	TREELINE	
	DECIDUOUS TREE	X
	CONIFEROUS TREE	X
	EC. BLANKET	
	FILTER BARRIER	FB
	RIPRAP	

GRAPHIC SCALE
30 0 15 30 60 120
(IN FEET)
1 inch = 30 ft.

REV:	BY:	STATUS:
G	DCS	12-30-2024 FOR TOWN REVIEW
4	DCS	05-03-2024 ASI-001 ADD TRASHTRACKS (2) OUTLETS, CHANGE TRAIL SURFACE TO PAVEMENT, ADD WALK TO SPRINKLER ROOM
3	DCS	03-26-2024 ADD DOOR, ADJUST HVAC UNIT & SIDEWALK ENTRANCE LOCATION
F	DCS	11-28-2023 REVISE GRADING AT DUMPSTER
E	DCS	10-20-2023 REVISED PLAN FOR TOWN REVIEW
2	DCS	06-29-2023 UPDATED SITE GRADING
1	DCS	05-05-2022 MOVE TRANSFORMER PAD, ADD HVAC PADS
D	DCS	02-03-2022 CONDITIONS OF APPROVAL
C	DCS	12-29-2021 REVISED PER CCSWCD COMMENTS
B	DCS	11-23-2021 FOR TOWN REVIEW
A	DCS	10-05-2021 FOR TOWN REVIEW

STATE OF MAINE
NANCY J. ST. CLAIR
No. 6877
REGISTERED PROFESSIONAL ENGINEER
12/30/2024

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland Foreside, ME 04021
Tel (207) 829-5558

PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012		DCS	DCS	NST
	ELECT.			


THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

GRADING & UTILITY PLAN
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET C-400

21012S TAB 21012G



NOTES:

1. BUFFERING ALONG WESTERLY PROPERTY LINE SHALL INCLUDE 5' TALL GREEN GIANT ARBORVITAE OR EQUIVALENT. ARBORVITAE SHALL BE MIXED WITH MINIMUM OF 2 ADDITIONAL COMPATIBLE PLANT SPECIES TO ADD DIVERSITY IN FORM AND/OR COLOR. ALL PLANTINGS SHALL BE DEER-RESISTANT. TYPICAL PLANT/GROUPING SPACING SHALL BE PER PLAN.
2. ALL PLANTING AND SEEDING SHOULD RECEIVE REGULAR WATERING FOR ESTABLISHMENT; ONE YEAR (FOR SEEDING) TWO YEARS MIN. (FOR SHRUBS AND TREES).

SITE FURNISHINGS SCHEDULE

QTY.	DESCRIPTION	VENDOR*
8	BENCH	SEE SHT. L2-00
4	BICYCLE RACK	SEE SHT. L2-00

*OR APPROVED EQUAL

PLANT SCHEDULE

SYMBOL	ABBR.	BOTANICAL NAME	COMMON NAME	QTY	SIZE	SPACING
TREES						
	AR	ACER RUBRUM 'KARPICK'	RED MAPLE	04	3" CAL	PER PLAN
	QR	QUERCUS RUBRA	NORTHERN RED OAK	19	3" CAL	PER PLAN
	BPW	BETULA POPULIFOLIA 'WHITESPIRE'	GRAY BIRCH (MULTI STEM)	17	10-12' B&B	PER PLAN
	AB	ABIES BALSAMEA	BALSAM FIR	06	8'-10' HEIGHT	PER PLAN
	TP	THUJA PLICATA 'GREEN GIANT'	GREEN GIANT ARBORVITAE	25	5' MIN. HT.	PER PLAN
	PM	PINUS MUGO	MUGO PINE	20	5' MIN. HT.	PER PLAN
	PS	PINUS STROBUS	EASTERN WHITE PINE	11	6-7' MIN.	PER PLAN
SHRUBS						
	AM	ARONIA MELANOCARPA 'LOW SCAPE MOUND'	LOW BLACK CHOKEBERRY	185	#3	PER PLAN
	CS	CORUS SERICEA	RED TWIG DOGWOOD	94	#5	PER PLAN
	DKO	DIERVILLA 'KODIAK ORANGE'	BUSH HONEYSUCKLE	59	#5	PER PLAN
	RA	RHUS AROMATICA	GRO LOW SUMAC	60	#2	PER PLAN
ORNAMENTAL GRASSES & PERENNIALS						
	CA	CALAMAGROSTIS X ACUTIFLORA 'KARL FOERSTER'	FEATHER REED GRASS	125	#1	30" O.C.
	PV	PANICUM VIRGATUM 'SHENANDOAH'	SWITCH GRASS	470	#1	30" O.C.
	SS	SCHIZACHYRIUM SCOPARIUM 'PRAIRIE BLUES'	LITTLE BLUESTEM	65	#1	24" O.C.

SEED MIXES

LAWN (SEED MIX) (WILDFLOWER FARM'S ECO-LAWN GRASS SEED)
TOTAL AREA : +/- 4,700 SQ FT
ECO-LAWN IS A DROUGHT-RESISTANT GRASS THAT REQUIRES MOWING ONLY ONCE PER MONTH. EACH 5 POUND BAG OF SEED COVERS 1,000 SQUARE FEET. A THICK HEALTHY LAWN IS THE BEST DEFENCE AGAINST WEEDS, DISEASE, DROUGHT AND INSECT DAMAGE.

GROUP 'A' (SUBMERGENT ZONE)
NEW ENGLAND WETMIX (WETLAND SEED MIX)
SUPPLIER: NEW ENGLAND WETLAND PLANT, INC.
TOTAL AREA : +/- 3,300 SQ FT
APPLICATION RATE 18 LBS/ACRE | 2500 SQ FT/LB
SPECIES: FOX SEDGE (CAREX VULPINOIDEA), LURID SEDGE (CAREX LURIDA), BLUNT BROOM SEDGE (CAREX SCOPARIA), BLUE VERVAIN (VERBENA HASTATA), FOWL BLUEGRASS (POA PALUSTRIS), HOP SEDGE (CAREX LUPULINA), GREEN BULRUSH (SCIRPUS ATROVIRENS), CREEPING SPIKE RUSH (ELEOCHARIS PALUSTRIS), FRINGED SEDGE (CAREX CRINITA), SOFT RUSH (JUNCUS EFFUSUS), SPOTTED JOE PYE WEED (EUPATORIUM MACULATUM), RATTLESNAKE GRASS (GLYCERIA CANADENSIS), SWAMP ASTER (ASTER PUNICEUS), BLUEFLAG (IRIS VERSICOLOR), SWAMP MILKWEED (ASCLEPIAS INCARNATA), SQUARE STEMMED MONKEY FLOWER (MIMULUS RINGENS).

GROUP 'B' (RESTORATION ZONE)
NEW ENGLAND CONSERVATION/WILDLIFE MIX
SUPPLIER: NEW ENGLAND WETLAND PLANT, INC.
TOTAL AREA : +/- 20,000 SQ FT
APPLICATION RATE : 25LBS/ACRE | 1750 SQ FT/LB
SPECIES: SPECIES: VIRGINIA WILD RYE (ELYMUS VIRGINICUS), LITTLE BLUESTEM (SCHIZACHYRIUM SCOPARIUM), BIG BLUESTEM (ANDROPOGON GERARDII), RED FESCUE (FESTUCA RUBRA), SWITCH GRASS (PANICUM VIRGATUM), PARTRIDGE PEA (CHAMAECRISTA FASCICULATA), PANICLEDLEAF TICK TREFOIL (DESMODIUM PANICULATUM), INDIAN GRASS (SORGHASTRUM NUTANS), BLUE VERVAIN (VERBENA HASTATA), BUTTERFLY MILKWEED (ASCLEPIAS TUBEROSA), BLACK EYED SUSAN (RUDBECKIA HIRTA), COMMON SNEEZEWEED (HELENIUM AUTUNALE), HEATH ASTER (ASTERPILOSUS/SYMPHYOTRICHUM PILOSUM), EARLY GOLDENROD (SOLIDAGO JUNCEA), UPLAND BENTGRASS (AGROSTIS PERENNANS).

ACETO LANDSCAPE ARCHITECTS
207 221 3390 | ACETOLA.COM

SEAL

PROJECT TITLE

TEDFORD HOUSING
THOMAS POINT ROAD
BRUNSWICK, ME

PREPARED FOR

OWNER:

TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

REVISIONS | DATE

ISSUE DATE


CONSTRUCTION SET
MAY03, 2024

SHEET TITLE


LANDSCAPE PLAN

SHEET INFORMATION

L 1-00



2 BICYCLE RACK X.X
NTS





5 PRIVACY FENCE 6.2
NTS

627 Amersale Drive
Naperville, IL 60563
Phone: (800) 323-5664
sales@belson.com

Model # PBSC-6-W **Dimension Sheet**

PALISADE WOOD BENCH





www.belson.com

2 BENCH X.X
NTS

ACETO LANDSCAPE ARCHITECTS
207 221 3390 | ACETOLA.COM

SEAL

PROJECT TITLE

TEDFORD HOUSING
THOMAS POINT ROAD
BRUNSWICK, ME

PREPARED FOR

OWNER:

TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

REVISIONS DATE

ISSUE DATE


MAY 03, 2024

SHEET TITLE

LANDSCAPE
DETAILS

SHEET INFORMATION


L 2-00



1 DECIDUOUS TREE PLANTING

1":1'-0"

9.1




NOTES:
EVERGREEN PLANT MATERIAL SHOULD BE TREATED WITH "AGRI-GEL" (OR EQUIVALENT APPROVED BY LANDSCAPE ARCHITECT). DIP TREE ROOTS BEFORE PLANTING.

2 EVERGREEN TREE PLANTING

1":1'-0"


9.2



4 PERENNIAL & GRASS PLANTING

1":1'-0"

9.4



3 SHRUB PLANTING

1":1'-0"

9.3

NOTES:
1. ALL PLANTING AND SEEDING SHOULD RECEIVE REGULAR WATERING FOR ESTABLISHMENT; ONE YEAR (FOR SEEDING) TWO YEARS MIN. (FOR TREES).
2. TREES OUTSIDE OF IRRIGATION ZONES TO BE INSTALLED WITH DRIP IRRIGATION BAGS (BY GEWITT, TREEGATOR, OR APPROVED EQUAL) PER MANUFACTURER'S INSTRUCTIONS. CONTRACTOR AND/OR MAINTENANCE SHALL FILL BAGS AS OFTEN AS NECESSARY TO PREVENT FROM BEING EMPTIED.

ACETO LANDSCAPE ARCHITECTS
207 221 3390 | ACETOLA.COM

SEAL

PROJECT TITLE

TEDFORD HOUSING
THOMAS POINT ROAD
BRUNSWICK, ME

PREPARED FOR

OWNER:

TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

REVISIONS DATE

ISSUE DATE


CONSTRUCTION SET
MAY 03, 2024

SHEET TITLE

LANDSCAPE DETAILS


SHEET INFORMATION

L 2-01



Luminaire Schedule							
Symbol	Qty	Label	Mounting Height	LLF	Lum. Lumens	Lum. Watts	Description
	3	A4	25' - 0" ADF	0.900	21357	150	VP-2-320L-145-3K7-4W
	15	BO	3' - 6" AFG	0.900	1468	45	FN1-24LU-3K-DB
	2	DL	8' - 0" AFG	0.900	1030	12	LTR-4RD-H-SL10L-DM1_LTR-4RD-T-SL35K8XWS

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
Overall Area	Illuminance	Fc	0.35	13.7	0.0	N.A.	N.A.
Parking Lot	Illuminance	Fc	2.12	4.0	0.3	7.07	13.33



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)

1 inch = 30 - FT.

1. THIS LIGHTING DESIGN IS BASED ON LIMITED INFORMATION SUPPLIED BY OTHERS TO CURRENT LIGHTING. SITE DETAILS PROVIDED HEREON ARE REPRODUCED ONLY AS A VISUALIZATION AID. FIELD DEVIATIONS MAY SIGNIFICANTLY AFFECT PREDICTED PERFORMANCE. PRIOR TO INSTALLATION, CRITICAL SITE INFORMATION (POLE LOCATIONS, ORIENTATION, MOUNTING HEIGHT, ETC.) SHOULD BE COORDINATED WITH THE CONTRACTOR AND/OR SPECIFIER RESPONSIBLE FOR THE PROJECT.
2. LUMINAIRE DATA IS TESTED TO INDUSTRY STANDARDS UNDER LABORATORY CONDITIONS. OPERATING VOLTAGE AND NORMAL MANUFACTURING TOLERANCES OF LAMP, BALLAST, AND LUMINAIRE MAY AFFECT FIELD RESULTS.
3. CONFORMANCE TO FACILITY CODE AND OTHER LOCAL REQUIREMENTS IS THE RESPONSIBILITY OF THE OWNER AND/OR THE OWNER'S REPRESENTATIVE.

TITLE:

TEDFORD

BRUNSWICK, ME

SITE PHOTOMETRIC PLAN

REVISED FROM DRAWING NUMBER(S):	

DN BY: DHK	DATE: 11/24/21	CHK BY: N/A
REV. BY:	DATE:	SCALE: AS NOTED
QUOTE: N/A	DRAWING / DESIGN NO.: A240941	

EROSION & SEDIMENTATION CONTROL

BASIC STANDARDS - EROSION CONTROL MEASURES

THIS PLAN IDENTIFIES THE MINIMUM EROSION CONTROL MEASURES THAT SHALL BE IMPLEMENTED ON THIS SITE. THE CONTRACTOR WILL BE RESPONSIBLE TO MAINTAIN ALL COMPONENTS OF THE EROSION CONTROL PLAN UNTIL THE SITE IS FULLY STABILIZED. HOWEVER, BASED ON SITE AND WEATHER CONDITIONS DURING CONSTRUCTION, ADDITIONAL EROSION CONTROL MEASURES MAY NEED TO BE IMPLEMENTED. ALL AREAS OF INSTABILITY AND EROSION SHALL BE REPAIRED IMMEDIATELY DURING CONSTRUCTION AND SHALL BE MAINTAINED UNTIL THE SITE IS FULLY STABILIZED OR VEGETATION IS ESTABLISHED. THE CONTRACTOR SHALL MAINTAIN A CONSTRUCTION LOG TO DOCUMENT ALL EROSION AND SEDIMENTATION CONTROL INSPECTIONS AND MAINTENANCE AND REPAIRS.

A. POLLUTION PREVENTION AND GENERAL HOUSEKEEPING

1. MINIMIZATION OF EXPOSED SOIL AREAS: IN ORDER TO PROTECT DOWNGRADIENT AREAS AND BUFFERS, AND TO AVOID POTENTIAL EROSION OF ANY OPEN DRAINAGE CHANNELS, SWALES, OR OTHER NATURAL RESOURCES, THE CONTRACTOR SHALL SEQUENCE AND PHASE EARTHWORKS OPERATIONS TO LIMIT THE AMOUNT OF SITE DISTURBANCE AND/OR EXPOSED SOIL TO ONLY THOSE AREAS NECESSARY TO EFFECTIVELY CONSTRUCT THE PROPOSED IMPROVEMENTS. TO THE EXTENT PRACTICABLE, THE CONTRACTOR SHALL RETAIN NATURAL COVER, AND PERMANENTLY STABILIZE AREAS AS SOON AS EARTHWORKS ARE COMPLETED. LESS EXPOSED SOIL RESULTS IN FEWER EROSION CONTROLS TO INSTALL AND MAINTAIN. IF WORK WITHIN AN AREA IS NOT ANTICIPATED TO BEGIN WITHIN TWO WEEKS TIME, THE CONTRACTOR SHALL CONSIDER LEAVING THE AREA IN ITS NATURALLY EXISTING COVER.
2. SPILL PREVENTION: CONTROLS MUST BE USED TO PREVENT POLLUTANTS FROM BEING DISCHARGED FROM MATERIALS ON SITE, INCLUDING STORAGE PRACTICES TO MINIMIZE EXPOSURE OF THE MATERIALS TO STORMWATER, AND APPROPRIATE SPILL PREVENTION, CONTAINMENT, AND RESPONSE PLANNING AND IMPLEMENTATION.
3. GROUNDWATER PROTECTION: DURING CONSTRUCTION, LIQUID PETROLEUM PRODUCTS AND OTHER HAZARDOUS MATERIALS WITH THE POTENTIAL TO CONTAMINATE GROUNDWATER MAY NOT BE STORED OR HANDLED IN AREAS OF THE SITE DRAINING TO AN INFILTRATION AREA. AN "INFILTRATION AREA" IS ANY AREA OF THE SITE THAT BY DESIGN OR AS A RESULT OF SOILS, TOPOGRAPHY AND OTHER RELEVANT FACTORS ACCUMULATES RUNOFF THAT INFILTRATES INTO THE SOIL. DIKES, BERMS, SUMPS, AND OTHER FORMS OF SECONDARY CONTAINMENT THAT PREVENT DISCHARGE TO GROUNDWATER MAY BE USED TO ISOLATE PORTIONS OF THE SITE FOR THE PURPOSES OF STORAGE AND HANDLING OF THESE MATERIALS.
4. FUGITIVE SEDIMENT AND DUST: ACTIONS MUST BE TAKEN TO ENSURE THAT ACTIVITIES DO NOT RESULT IN NOTICEABLE EROSION OF SOILS OR FUGITIVE DUST EMISSIONS DURING OR AFTER CONSTRUCTION. OIL MAY NOT BE USED FOR DUST CONTROL. FOR OPERATIONS DURING WET MONTHS, THE CONTRACTOR SHALL SWEEP ROADWAYS OR PAVED AREAS AT LEAST ONCE A WEEK AND PRIOR TO SIGNIFICANT STORM EVENTS TO AVOID TRACKING OF MUD OFF THE SITE. WHERE CHRONIC MUD TRACKING OCCURS, A STABILIZED CONSTRUCTION ENTRANCE SHALL BE PROVIDED. FOR OPERATIONS DURING DRY MONTHS, THAT EXPERIENCE FUGITIVE DUST PROBLEMS, THE CONTRACTOR SHALL WET DOWN THE ACCESS ROADS WITH WATER ONCE A WEEK OR MORE FREQUENTLY, AS NEEDED.
5. DEBRIS AND OTHER MATERIALS: LITTER, CONSTRUCTION DEBRIS, AND CHEMICALS EXPOSED TO STORMWATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE.
6. NON-STORMWATER DISCHARGES: IDENTIFY AND PREVENT CONTAMINATION BY NON-STORMWATER DISCHARGES.

B. STRUCTURAL AND NON-STRUCTURAL MEASURES

1. SEDIMENT BARRIERS: PRIOR TO SOIL DISTURBANCE, THE CONTRACTOR SHALL PROPERLY INSTALL SEDIMENT BARRIERS ACROSS OR AT THE TOE OF A SLOPE AND AT THE DOWNGRADIENT EDGE OF ANY DISTURBED AREA. SEDIMENT BARRIERS SHALL BE INSTALLED IN LOCATIONS WHERE SEDIMENTATION MAY REDUCE THE CAPACITY OF STORMDRAIN SYSTEMS, UPSTREAM OF ADJACENT WETLANDS AND WATERCOURSES, AND OTHER AREAS THAT MAY BE AFFECTED BY SEDIMENT. SEDIMENT BARRIERS SHALL NOT BE USED IN AREAS OF CONCENTRATED FLOWS. SEDIMENT BARRIERS MAY BE SILT FENCE, OR A BERM OF EROSION CONTROL MIX, OR OTHER APPROVED FILTER MATERIALS.
   a. SILT FENCE: SILT FENCE IS GENERALLY A BETTER FILTER THAN HAY BALE BARRIERS. SILT FENCES CAN BE USED FOR 60 DAYS OR LONGER DEPENDING ON MANUFACTURER'S RECOMMENDATIONS. PROPER INSTALLATION OF SILT FENCE IS CRITICAL TO ITS FUNCTION (SEE DETAIL).
   b. EROSION CONTROL MIX BERMS: EROSION CONTROL MIX CAN BE MANUFACTURED ON OR OFF THE PROJECT SITE. EROSION CONTROL MIX SHALL CONTAIN A WELL-GRADED MIXTURE OF PARTICLE SIZES AND MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER. THE MIX COMPOSITION SHALL MEET THE MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION STANDARDS FOR ORGANIC MATTER AND PARTICLE SIZE BY WEIGHT, SOLUBLE SALTS AND pH LEVELS. EROSION CONTROL MIX MUST BE FREE OF REFUSE, CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH. THE EROSION CONTROL MIX BERM MUST BE PLACED ALONG A RELATIVELY LEVEL CONTOUR. CUT TALL GRASSES OR WOODY VEGETATION TO AVOID CREATING VOIDS AND BRIDGES THAT WOULD ENABLE FINES TO WASH UNDER THE BARRIER.
   c. CONTINUOUS CONTAINED BERMS (FILTER SOCK): A FILTER SOCK CAN BE INSTALLED. IN AREAS WHERE TRENCHING IS NOT FEASIBLE SUCH AS OVER FROZEN GROUND OR OVER PAVEMENT. A VEHICLE CAN EVEN PASS OVER IT.
   d. INSPECTION AND MAINTENANCE OF SEDIMENT BARRIERS: SEDIMENT BARRIERS ARE EFFECTIVE ONLY IF INSTALLED AND MAINTAINED PROPERLY. IF THERE IS EVIDENCE OF END FLOW ON PROPERLY INSTALLED BARRIERS, THE CONTRACTOR SHALL EXTEND BARRIERS UPHILL OR REPLACE THEM WITH TEMPORARY CHECK DAMS. THE CONTRACTOR SHALL INSPECT SEDIMENT BARRIERS IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. THEY SHALL BE REPAIRED BY THE CONTRACTOR IMMEDIATELY IF THERE ARE ANY SIGNS OF EROSION OR SEDIMENTATION BELOW THEM. IF THERE ARE SIGNS OF UNDERCUTTING AT THE CENTER OR THE EDGES OF THE BARRIER, OR IMPOUNDING OF LARGE VOLUMES OF WATER BEHIND THEM, SEDIMENT BARRIERS SHALL BE REPLACED WITH A TEMPORARY CHECK DAM. SHOULD THE FABRIC ON A SILT FENCE OR FILTER BARRIER DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL IS NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY. SEDIMENT BARRIERS SHALL BE REMOVED AFTER EACH STORM EVENT. SEDIMENT DEPOSITS SHALL BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER. FILTER BERMS SHOULD BE RESHAPED AS NEEDED. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED. THE CONTRACTOR SHALL MAINTAIN THE SEDIMENT BARRIERS UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED. SEDIMENT BARRIERS SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREAS HAVE BEEN PERMANENTLY STABILIZED.

2. TEMPORARY CHECK DAMS: MAY BE CONSTRUCTED OF EITHER STONE OR CONTAINED BERMS OF EROSION CONTROL MIX. TEMPORARY CHECK DAMS ALSO MAY TRAP SMALL AMOUNTS OF SEDIMENT BUT SHALL NOT BE USED IN PLACE OF SEDIMENT BARRIERS. THE DAM SHALL BE LEFT IN PLACE PERMANENTLY TO AVOID UNNECESSARY DISTURBANCE OF THE SOIL DURING REMOVAL. IF IT IS NECESSARY TO REMOVE A STONE CHECK DAM FROM A GRASS-LINED CHANNEL, WHICH WILL BE MOWED, THE CONTRACTOR SHALL ENSURE THAT ALL STONES ARE REMOVED, INCLUDING ANY STONES WASHED DOWNSTREAM.
   a. SIZING AND PLACEMENT: THE MAXIMUM HEIGHT OF THE CHECK DAM SHALL BE 2 FEET. THE CENTER OF THE CHECK DAM MUST BE AT LEAST 6 INCHES LOWER THAN THE OUTER EDGES. THE MAXIMUM SPACING BETWEEN THE DAMS SHALL BE SUCH THAT THE TOE OF THE UPSTREAM DAM IS AT THE SAME ELEVATION AS THE TOP OF THE DOWNSTREAM DAM. CHECK DAMS SHALL BE INSTALLED BEFORE RUNOFF IS DIRECTED TO THE SWALE OR DRAINAGE DITCH. STONE SHALL BE INSTALLED OF 2 TO 3 INCH STONE. HAND OR MECHANICAL PLACEMENT IS NECESSARY TO PROPERLY INSTALL (SEE DETAIL). THE CONTRACTOR SHALL PROPERLY INSTALL CHECK DAMS TO AVOID UNDERCUTTING AND BYPASS OF THE FLOW AROUND THE ENDS OF THE CHECK DAMS.
   b. INSPECTIONS AND MAINTENANCE: THE CONTRACTOR SHALL MAKE REGULAR INSPECTIONS TO ENSURE THAT THE CENTER OF THE DAM IS LOWER THAN THE EDGES. EROSION CAUSED BY HIGH FLOWS AROUND THE EDGES OF THE DAM SHALL BE CORRECTED IMMEDIATELY. IF EVIDENCE OF SILTATION IN THE WATER IS APPARENT DOWNSTREAM FROM THE CHECK DAM, THE CHECK DAM SHALL BE INSPECTED AND ADJUSTED IMMEDIATELY. CHECK DAMS SHALL BE CHECKED FOR SEDIMENT ACCUMULATION AFTER EACH SIGNIFICANT RAINFALL. SEDIMENT MUST BE REMOVED WHEN IT REACHES ONE HALF OF THE ORIGINAL HEIGHT OR BEFORE. IF IT IS POSSIBLE, LEAVE THE DAM IN PLACE PERMANENTLY. THE STONE MAY BE SPREAD ALONG THE DITCH INVERT TO PROVIDE ADDITIONAL PROTECTION.

3. STABILIZED CONSTRUCTION ENTRANCE/EXIT: PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL INSTALL A STABILIZED CONSTRUCTION ENTRANCE/EXIT AT ALL POINTS OF ACCESS TO THE EXISTING ROAD. THIS AREA SHALL CONSIST OF A STABILIZED PAD OF AGGREGATE UNDERLAIN WITH FILTER FABRIC. THE CONTRACTOR SHALL MONITOR PAVEMENT EDGES TO FOR CRACKING OR RAVELING OF THE EXISTING PAVEMENT EDGE IN THE AREA OF ANY UNPROTECTED ENTRANCE. IF THE EXISTING PAVEMENT EDGE SHOWS SIGNS OF IMPACT, THEN THE STABILIZED CONSTRUCTION EXIT SHALL BE USED FOR ALL ENTERING AND EXITING CONSTRUCTION VEHICLES. WOVEN OR NONWOVEN GEOTEXTILE FABRIC SHALL BE PLACED OVER THE ENTIRE AREA TO BE COVERED WITH AGGREGATE. THE STABILIZED CONSTRUCTION ENTRANCE/EXIT SHALL CONSIST OF A 10' WIDE (MINIMUM) BY 50' LONG (MINIMUM) 6" THICK PAD OF 2"-3" STONE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT. THE PAD SHALL EXTEND THE FULL WIDTH OF POINTS WHERE INGRESS OR EGRESS OCCURS. THE EXIT SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. WHEN THE STABILIZED PAD BECOMES INEFFECTIVE, THE STONE SHALL BE REMOVED ALONG WITH THE COLLECTED SOIL MATERIAL AND REDISTRIBUTED ON SITE IN A STABLE MANNER. A NEW ENTRANCE SHALL BE RECONSTRUCTED. THE CONTRACTOR SHALL SWEEP OR WASH PAVEMENT AT EXITS, WHICH HAVE EXPERIENCED MUD-TRACKING ON TO THE PAVEMENT OR TRAVELED WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH AGGREGATE, WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING STORM DRAINS, DITCHES, OR WATERWAYS.

4. SOIL STOCKPILES:

STOCKPILES OF SOIL OR SUBSOIL SHALL BE MULCHED WITH HAY OR STRAW AT A RATE OF 75 LBS/1,000 S.F. (1.5 TONS PER ACRE) OR WITH A FOUR-INCH LAYER OF EROSION CONTROL MIX. THIS SHALL BE DONE WITHIN 24 HOURS OF STOCKING AND RE-ESTABLISHED PRIOR TO ANY RAINFALL. PLACEMENT OF ANY SOIL STOCKPILES WITHIN 100 FEET FROM ANY NATURAL RESOURCES TO BE PRESERVED SHALL BE AVOIDED.

5. NATURAL RESOURCES PROTECTION:

ANY AREAS WITHIN 100 FEET FROM ANY NATURAL RESOURCES, IF NOT STABILIZED WITH A MINIMUM OF 75% MATURE VEGETATION CATCH, SHALL BE MULCHED USING TEMPORARY MULCHING WITHIN 7 DAYS OF EXPOSURE OR PRIOR TO ANY STORM EVENT. SEDIMENT BARRIERS SHALL BE PLACED BETWEEN ANY NATURAL RESOURCE AND THE DISTURBED AREA.

6. STORMDRAIN INLET PROTECTION: A SEDIMENT FILTER INSTALLED AROUND A STORM DRAIN DROP INLET OR CURB INLET TO PREVENT SEDIMENT FROM ENTERING A STORM DRAINAGE SYSTEM PRIOR TO PERMANENT STABILIZATION OF THE DISTURBED AREA. THE INLET PROTECTION DEVICE SHALL BE CONSTRUCTED IN A MANNER THAT WILL FACILITATE CLEAN-OUT AND DISPOSAL OF TRAPPED SEDIMENTS AND MINIMIZE INTERFERENCE WITH CONSTRUCTION ACTIVITIES. ANY RESULTANT PONDING OF STORMWATER MUST NOT CAUSE EXCESSIVE INCONVENIENCE OR DAMAGE TO ADJACENT AREAS OR STRUCTURES.
   a. MANUFACTURED SEDIMENT BARRIERS AND FILTERS: INCLUDE VARIOUS TYPES OF SYSTEMS SUCH AS THE "SILT SACK" OR OTHER MANUFACTURED MATERIALS. THESE MEASURES ARE ACCEPTABLE AS LONG AS THEY ARE INSTALLED, USED AND MAINTAINED AS SPECIFIED BY THE VENDOR OR MANUFACTURER.
   b. INSPECTION AND MAINTENANCE OF STORMDRAIN INLET PROTECTION: THE CONTRACTOR SHALL INSPECT STRUCTURES BEFORE AND AFTER EACH RAIN EVENT AND SHALL REPAIR AS NEEDED. IF THE FILTER BECOMES CLOGGED WITH SEDIMENT SO THAT IT NO LONGER ADEQUATELY PERFORMS ITS FUNCTION, THE THE CONTRACTOR SHALL CLEAN AND REPLACE THE FILTER. SEDIMENT SHALL BE REMOVED AND THE STORMDRAIN SEDIMENT FILTER RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE. SEDIMENT FILTERS SHALL BE REMOVED AND THE AREA STABILIZED AFTER THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED. THE CONTRACTOR SHALL CLEAN ALL CATCHBASINS AND STORMDRAIN INLETS AT THE END OF CONSTRUCTION AND AFTER THE SITE HAS BEEN FULLY STABILIZED.

7. STORMWATER CHANNELS: DITCHES, SWALES, AND OTHER OPEN STORMWATER CHANNELS SHALL BE CONSTRUCTED AND STABILIZED USING MEASURES THAT ACHIEVE LONG-TERM EROSION CONTROL. DITCHES, SWALES, AND OTHER OPEN STORMWATER CHANNELS SHALL BE CONSTRUCTED IN SECTIONS SO THAT THE GRADING, SHAPING, AND INSTALLATION OF THE PERMANENT LINING ON EACH SECTION CAN BE COMPLETED THE SAME DAY. IF A CHANNEL'S FINAL GRADING OR LINING INSTALLATION MUST BE DELAYED, THEN EITHER DIVERSION BERMS MUST BE USED TO DIVERT STORMWATER AWAY FROM THE CHANNEL, PROPERLY-SPACED CHECK DAMS MUST BE INSTALLED IN THE CHANNEL TO SLOW THE WATER VELOCITY, OR A TEMPORARY LINING SHALL BE INSTALLED ALONG THE CHANNEL TO PREVENT SCOURING.

8. TRENCH OR FOUNDATION DE-WATERING: ACCUMULATED WATER IN TRENCHES, FOUNDATIONS, PONDS, AND OTHER AREAS THAT RETAIN WATER AFTER EXCAVATION SHALL BE CAREFULLY REMOVED BY THE CONTRACTOR TO AVOID DOWNSTREAM IMPACTS DUE TO THE HEAVILY SILTED WATER. THE COLLECTED WATER SHALL BE REMOVED FROM THE PONDED AREA, EITHER THROUGH GRAVITY OR PUMPING, AND SHALL BE REMOVED TO AREAS THAT ARE SPECIFICALLY DESIGNED TO COLLECT THE MAXIMUM AMOUNT OF SEDIMENT POSSIBLE, LIKE A SEDIMENTATION BASIN OR DEVICE SUCH AS A "DIRT BAG" FILTER OR EQUAL. AVOID ALLOWING THE WATER TO FLOW OVER DISTURBED AREAS OF THE SITE. THE CONTRACTOR SHALL USE A NON-WOVEN GEOTEXTILE SEDIMENT CONTROL BAG SUCH AS A "DIRT BAG" OR EQUIVALENT AS A PREFERRED OPTION.

C. STABILIZATON MEASURES

1. TEMPORARY STABILIZATION: THE CONTRACTOR SHALL STABILIZE ANY EXPOSED SOILS THAT WILL NOT BE WORKED FOR MORE THAN 7 DAYS WITH MULCH OR OTHER NON-ERODABLE COVER. STABILIZE AREAS WITHIN 75 FEET OF A WETLAND OR WATERBODY WITHIN 48 HOURS OF THE INITIAL DISTURBANCE OF THE SOIL OR PRIOR TO ANY STORM EVENT, WHICHEVER COMES FIRST.

2. PERMANENT STABILIZATION: IF THE AREA HAS BEEN BROUGHT TO FINAL GRADE OR WILL NOT BE WORKED FOR MORE THAN ONE YEAR, THE CONTRACTOR SHALL PERMANENTLY STABILIZE THE AREA WITHIN 7 DAYS BY PLANTING VEGETATION, SEEDING, SOD, OR THROUGH THE USE OF PERMANENT MULCH, OR RIPRAP, OR PAVER SUBBASE. IF USING VEGETATION FOR STABILIZATION, AMEND AREAS OF DISTURBED SUBSOILS WITH TOPSOIL, COMPOST, OR FERTILIZERS; PROTECT SEEDED AREAS WITH MULCH OR, IF NECESSARY, EROSION CONTROL BLANKETS; AND SCHEDULE SODDING, PLANTING, AND SEEDING TO AVOID DIE-OFF FROM SUMMER DROUGHT AND FALL FROSTS. NEWLY SEEDED OR SODDED AREAS MUST BE PROTECTED FROM VEHICLE TRAFFIC, EXCESSIVE PEDESTRIAN TRAFFIC, AND CONCENTRATED RUNOFF UNTIL THE VEGETATION IS WELL-ESTABLISHED. IF GERMINATION IS SPARSE, PLANT COVERAGE IS SPOTTY, OR TOPSOIL EROSION IS EVIDENT THE CONTRACTOR SHALL RESEED AND MULCH THE AREAS. ONE OR MORE OF THE FOLLOWING SHALL APPLY TO A PARTICULAR SITE.
   a. SEEDED AREAS: FOR SEEDED AREAS, PERMANENT STABILIZATION MEANS A 90% COVER OF HEALTHY PLANTS WITH NO EVIDENCE OF WASHING OR RILLING OF THE TOPSOIL.
   b. SODDED AREAS: FOR SODDED AREAS, PERMANENT STABILIZATION MEANS THE COMPLETE BINDING OF THE SOD ROOTS INTO THE UNDERLYING SOIL WITH NO SLUMPING OF THE SOD OR DIE-OFF.
   c. PERMANENT MULCH: FOR MULCHED AREAS, PERMANENT MULCHING MEANS TOTAL COVERAGE OF THE EXPOSED AREA WITH AN APPROVED MULCH MATERIAL. EROSION CONTROL MIX MAY BE USED AS MULCH FOR PERMANENT STABILIZATION ACCORDING TO THE MDEP APPROVED APPLICATION RATES AND LIMITATIONS.
   d. RIPRAP: FOR AREAS STABILIZED WITH RIPRAP, PERMANENT STABILIZATION MEANS THAT SLOPES STABILIZED WITH RIPRAP HAVE AN APPROPRIATE BACKING OF A WELL-GRADED GRAVEL OR APPROVED GEOTEXTILE TO PREVENT SOIL MOVEMENT FROM BEHIND THE RIPRAP.
   e. PAVER AREAS: FOR PAVER AREAS, PERMANENT STABILIZATION MEANS THE PLACEMENT OF THE COMPACTED SUBBASE IS COMPLETED.
   f. DITCHES, CHANNELS, AND SWALES: FOR OPEN CHANNELS, PERMANENT STABILIZATION MEANS THE CHANNEL IS STABILIZED WITH A 90% COVER OF HEALTHY VEGETATION, WITH A WELL-GRADED RIPRAP LINING, OR WITH ANOTHER NON-EROSIVE LINING SUCH AS CONCRETE OR PAVEMENT. THERE MUST BE NO EVIDENCE OF SLUMPING OF THE CHANNEL LINING, UNDERCUTTING OF THE CHANNEL BANKS, OR DOWN-CUTTING OF THE CHANNEL.

3. REMOVAL OF STABILIZATION MEASURES: WITHIN 30 DAYS AFTER PERMANENT STABILIZATION IS ATTAINED THE CONTRACTOR SHALL REMOVE ANY TEMPORARY SEDIMENT CONTROL MEASURES (SUCH AS SILT FENCE, ETC.), REMOVE ANY ACCUMULATED SEDIMENTS AND STABILIZE THE AREA. SILT FENCE SHALL BE REMOVED BY CUTTING THE FENCE MATERIALS AT GROUND LEVEL TO AVOID ADDITIONAL SOIL DISTURBANCE.

A. TEMPORARY VEGETATION

THE FOLLOWING SHALL APPLY IN AREAS TO RECEIVE TEMPORARY SEEDING:
1. GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AND MULCH ANCHORING. INSTALL EROSION CONTROL MEASURES SUCH AS DIVERSIONS, GRADE STABILIZATION STRUCTURES, SEDIMENT BASINS AND GRASSED WATERWAYS TO PROTECT NEWLY SEEDED AREAS.

2. APPLY LIMESTONE AND FERTILIZER AT THE RATE OF 600 POUNDS PER ACRE OR 13.8 POUNDS PER 1,000 SQUARE FEET OF 10-10-10 (N-P2O5-K2O) OR EQUIVALENT. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE (138 LB. PER 1,000 SQUARE FEET). WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED.

3. SEEDING RATES AND DEPTHS SHALL BE AS SPECIFIED ON THE PLAN SET, OR AS IDENTIFIED IN THE TABLE BELOW. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED 10 % WHEN HYDROSEEDING.

4. APPLY MULCH OVER SEEDED AREA.

5. TEMPORARY SEEDING SHALL BE PERIODICALLY INSPECTED. AT A MINIMUM, 95% OF THE SOIL SURFACE SHOULD BE COVERED BY VEGETATION. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHALL BE MADE AND OTHER TEMPORARY MEASURES USED IN THE INTERIM (MULCH, FILTER BARRIERS, CHECK DAMS, ETC.).


TEMPORARY SEEDING TABLE

SEED	Lb./Ac.	SEEDING	DEPTHSEEDING	DATES	NOTES
WINTER RYE	112	(2 Bu)	1-1.5 IN	8/15-10/1	GOOD FOR FALL SEEDING, SELECT HARDY SPECIES SUCH AS AROOSTOOK RYE.
OATS	80	(2.5 Bu)	1-1.5 IN	4/1-7/1 (SPRING)	8/15-9/15 (FALL) BEST FOR SPRING SEEDING. FALL SEEDING REQUIRES MULCH
ANNUAL RYEGRASS	400		.25 IN	4/1-7/1	GROWS QUICKLY BUT IS OF SHORT DURATION, USE WHERE APPEARANCE IS IMPORTANT. CAN BE USED THROUGHOUT GROWING SEASON. IF MULCHED.
SUDANGRASS	40	(1.0 Bu)	0.5-1.0 IN	5/15-8/15	GOOD GROWTH DURING HOT SUMMER
PERENNIAL RYEGRASS	40	(2.0 Bu)	0.25 IN	8/15-9/15	GOOD COVER, LONGER LASTING THAN ANNUAL RYEGRASS. CAN BE USED THROUGHOUT GROWING SEASON, IF MULCHED.
TEMPORARY MULCH				10/1-4/1	REFER TO TEMPORARY MULCHING OR PERMANENT VEGETATION

E. TEMPORARY MULCHING

APPLY TEMPORARY MULCHING TO PROTECT THE EXPOSED SOIL SURFACE AND AID IN THE GROWTH OF VEGETATION.
1. IN SENSITIVE AREAS (WITHIN 100 FT OF STREAMS, WETLANDS AND IN LAKE WATERSHEDS) TEMPORARY MULCH MUST BE APPLIED WITHIN 7 DAYS OF EXPOSING SOIL OR PRIOR TO ANY STORM EVENT.
2. IN OTHER AREAS, THE TIME PERIOD CAN RANGE FROM 14 TO 30 DAYS, DEPENDING ON SITE CONDITIONS (SOIL ERODIBILITY, SEASON OF YEAR, EXTENT OF DISTURBANCE, PROXIMITY TO SENSITIVE RESOURCES, ETC.) AND THE POTENTIAL IMPACT OF EROSION ON ADJACENT AREAS.
3. AREAS WHICH HAVE BEEN TEMPORARILY OR PERMANENTLY SEEDED, SHALL BE MULCHED IMMEDIATELY FOLLOWING SEEDING.
4. AREAS WHICH CANNOT BE SEEDED WITHIN THE GROWING SEASON SHALL BE MULCHED FOR OVER-WINTER PROTECTION AND THE AREA SHALL BE SEEDED AT THE BEGINNING OF THE GROWING SEASON.
5. MULCH CAN BE USED IN CONJUNCTION WITH TREE, SHRUB, VINE, AND GROUND COVER PLANTINGS.
6. MULCH ANCHORING SHALL BE USED ON SLOPES GREATER THAN 5% IN LATE FALL (PAST SEPTEMBER 15), AND OVER-WINTER (SEPTEMBER 15 - APRIL 15).
7. WHEN MULCH IS APPLIED TO PROVIDE PROTECTION OVER WINTER (PAST THE GROWING SEASON), IT SHALL BE APPLIED TO A DEPTH OF FOUR INCHES (150-200 LBS. OF HAY PER 1000 SQ. FT OR DOUBLE STANDARD APPLICATION RATE). SEEDING CANNOT GENERALLY BE EXPECTED TO GROW UP THROUGH THIS DEPTH OF MULCH AND WILL BE SMOTHERED. IF VEGETATION IS DESIRED, THE MULCH WILL NEED TO BE REMOVED IN THE SPRINGTIME AND THE AREA RESEEDED AND MULCHED.
8. ALL MULCHES MUST BE INSPECTED PERIODICALLY BY THE CONTRACTOR, IN PARTICULAR AFTER RAINSTORMS, TO CHECK FOR RILL EROSION. IF LESS THAN 90% OF THE SOIL SURFACE IS COVERED BY MULCH, ADDITIONAL MULCH SHALL BE IMMEDIATELY APPLIED. NETS MUST BE INSPECTED AFTER RAIN EVENTS FOR DISLOCATION OR FAILURE. IF WASHOUT OR BREAKAGE OCCUR, RE-INSTALL THE NETS AS NECESSARY AFTER REPAIRING DAMAGE TO THE SLOPE. INSPECTIONS SHALL TAKE PLACE UNTIL GRASSES ARE FIRMLY ESTABLISHED (95% SOIL SURFACE COVERED WITH GRASS).
9. WHERE MULCH IS USED IN CONJUNCTION WITH ORNAMENTAL PLANTINGS, THE CONTRACTOR SHALL INSPECT PERIODICALLY THROUGHOUT THE YEAR TO DETERMINE IF MULCH IS MAINTAINED COVERAGE OF THE SOIL SURFACE. REPAIR AS NEEDED.
10. THE CHOICE OF MATERIALS FOR MULCHING SHALL BE BASED ON SOIL, SITE CONDITIONS AND SEASONS. RECOMMENDED MULCHES INCLUDE HAY AND STRAW OR EROSION CONTROL MIX.
11. HAY AND STRAW:
   a. ORGANIC MULCHES INCLUDING HAY AND STRAW MUST BE AIR-DRIED, FREE OF UNDESIRABLE SEEDS AND COARSE MATERIALS.
   b. APPLICATION RATE SHALL BE 2 BALES (70-90 POUNDS) PER 1000 SQ FT OR 1.5 TO 2 TONS (90-100 BALES) PER ACRE TO COVER 75 TO 90 % OF THE GROUND SURFACE. HAY MULCH IS SUBJECT TO WIND BLOWING UNLESS KEPT MOIST OR ANCHORED.
   c. ANCHORING METHODS INCLUDE NETTING OVER HAY WITH JUTE, WOOD FIBER OR PLASTIC NETTING ANCHORED TO THE SOIL SURFACE. STAPLE MATS ACCORDING TO MANUFACTURER'S RECOMMENDATION.
12. EROSION CONTROL MIX:
   a. EROSION CONTROL MIX CAN BE MANUFACTURED ON OR OFF THE PROJECT SITE. IT MUST CONSIST PRIMARILY OF ORGANIC MATERIAL AND WILL INCLUDE ANY OF THE FOLLOWING: SHREDDED BARK, STUMP GRINDINGS, COMPOSTED BARK OR OTHER ACCEPTABLE PRODUCTS BASED ON A SIMILAR RAW SOURCE. WOOD OR BARK CHIPS, GROUND CONSTRUCTION DEBRIS OR REPROCESSED WOOD PRODUCTS WILL NOT BE ACCEPTABLE AS THE ORGANIC COMPONENTS.
   b. EROSION CONTROL MIX SHALL CONTAIN A WELL-GRADED MIXTURE OF PARTICLE SIZES AND MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER.
   c. EROSION CONTROL MIX SHALL BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH. THE MIX COMPOSITION SHALL MEET THE MAINE DEP STANDARDS:
   d. WHEN USED AS MULCH, A MINIMUM 4" THICK LAYER OF EROSION CONTROL MIX SHALL BE USED AS A STAND-ALONE REINFORCEMENT:
      1. ON SLOPES 2 HORIZONTAL TO 1 VERTICAL OR LESS.
      2. ON FROZEN GROUND AND DORMANT SEEDED AREAS.
      3. AT THE EDGE OF GRAVEL PARKING AREAS AND AREAS UNDER CONSTRUCTION.
      4. OTHER REINFORCEMENT BMPS (I.E. RIPRAP) SHALL BE USED:
      a. ON STEEPER SLOPES GREATER THAN 2:1 AND
      b. SLOPES WITH EXPOSURE TO WIND.
      c. AT LOW POINTS WITH CONCENTRATED FLOWS AND
      d. IN GULLIES

5. THE MULCH MAY BE PLACED WITH A HYDRAULIC BUCKET, WITH A PNEUMATIC BLOWER OR BY HAND. IT SHALL BE PLACED EVENLY AND MUST PROVIDE 100 % SOIL COVERAGE, WITH THE SOIL TOTALLY INVISIBLE.
6. ANY REQUIRED REPAIRS SHALL BE MADE BY THE CONTRACTOR IMMEDIATELY, WITH ADDITIONAL EROSION CONTROL MIX PLACED ON TOP OF THE MULCH TO REACH THE RECOMMENDED THICKNESS. WHEN THE MIX IS DECOMPOSED, CLOGGED WITH SEDIMENT, ERODED OR INEFFECTIVE, IT SHALL BE REPLACED OR REPAIRED. EROSION CONTROL MIX MULCH SHOULD BE LEFT IN PLACE. VEGETATION ADDS STABILITY AND SHOULD BE PROMOTED. IF THE MULCH NEEDS TO BE REMOVED SPREAD IT OUT INTO THE LANDSCAPE.
13. SPRAY ON MULCHES:
   a. IF USING SYNTHETIC, SPRAY-ON EMULSIONS THAT ARE MIXED WITH WATER T



WITH TRENCHING WITHOUT TRENCHING

NOTES:

SILT FENCE AND FILTER BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.

SHOULD THE FABRIC ON A SILT FENCE OF FILTER BARRIER DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL IS NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.


SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.

ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, PREPARED AND SEEDED. THE TRENCH SHALL BE BACKFILLED AND THE SOIL COMPACTED OVER THE FILTER FABRIC.

SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY STABILIZED.

SILT-FENCE DETAIL

NOT TO SCALE



SECTION VIEW

NOTES:
1) THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT OF WAY. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES TO TRAP SEDIMENT


2) WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT OF WAY OR EXISTING PAVED AREAS.

3) WHEN WASHING IS REQUIRED, IT SHALL BE COMPLETED ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.

4) ADDITIONAL SWEEPING MAY ALSO BE REQUIRED.

CONSTRUCTION ENTRANCE DETAIL

NOT TO SCALE




NOTE:


NEENAH FOUNDRY #R-4353 OR APPROVED EQUAL

BEEHIVE GRATE

NOT TO SCALE




SILTSACK ®



PIPE INLET/OUTLET GRATE

NOT TO SCALE



WOOD WASTE COMPOST/BARK FILTER BERMS

A) EROSION CONTROL MIX MUST CONSIST PRIMARILY OF ORGANIC MATERIALS, SEPARATED AT THE POINT OF GENERATION, AND MAY INCLUDE: SHREDDED BARK, STUMP GRINDINGS, COMPOSTED BARK, OR ACCEPTABLE MANUFACTURED PRODUCTS. WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS OR REPROCESSED WOOD PRODUCTS ARE NOT ACCEPTABLE AT THE ORGANIC COMPONENT OF THE MIX. THE MIX SHALL CONFORM TO THE FOLLOWING STANDARDS:

B) EROSION CONTROL MIX SHALL CONTAIN A WELL -GRADED MIXTURE OF PARTICLE SIZES AND MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER. EROSION CONTROL MIX MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH. THE MIX COMPOSITION SHALL MEET THE FOLLOWING STANDARDS:

1) THE ORGANIC MATTER CONTENT SHALL BE BETWEEN 80% AND 100%, DRY WEIGHT BASIS.

2) PARTICLE SIZE BY WEIGHT SHALL BE 100% PASSING A 6" SCREEN AND A MINIMUM OF 70% MAXIMUM OF 85%, PASSING A 0.75" SCREEN

3) THE ORGANICS PORTION NEEDS TO BE FIBROUS AND ELONGATED.

4) LARGE PORTIONS OF SILTS, CLAYS OR FINE SANDS ARE NOT ACCEPTABLE IN THE MIX.

5) SOLUBLE SALTS CONTENT SHALL BE LESS THAN 4.0 MMHOS/CM.


6) THE pH SHOULD FALL BETWEEN 5.0 AND 8.0 THE COMPOSTED BERM SHALL BE PLACED, UNCOMPACTED, ALONG A RELATIVELY LEVEL CONTOUR.

NOTE: EROSION CONTROL MIX FILTER BERMS MAY BE USED IN COMBINATION WITH SILT FENCE TO IMPROVE SEDIMENT REMOVAL AND PREVENT CLOGGING OF THE EROSION CONTROL MIX BERM BY LARGER SEDIMENT PARTICLES. (SILT FENCE PLACED TO FILTER RUNOFF BEFORE BERM)

NOTE: EROSION CONTROL MIX FILTER BERM CAN BE USED IN LIEU OF SILT FENCE, CONTRACTOR'S CHOICE.

WOOD WASTE COMPOST/BARK FILTER BERM

NOT TO SCALE



1. SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICK AND GRASS, MATS/BLANKETS SHALL HAVE GOOD SOIL CONTACT.

2. APPLY PERMANENT SEEDING BEFORE PLACING BLANKETS.

3. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH.

4. CHOOSE MATERIAL BASED ON SLOPE, SOILS AND APPLICATION.

5. FOLLOW MANUFACTURER SPECIFICATIONS FOR STAPLE PLACEMENT


6. BLANKETS/MATS SHOULD BE INSTALLED VERTICALLY DOWNSLOPE

7. TURF REINFORCED MATS SHALL BE KEYED IN AT THE TOP AND DOWNGRADIENT ENDS AND SHALL BE INSTALLED PER MANUFACTURER RECOMMENDATIONS.

8. THE EROSION CONTROL MAT SHALL BE ADS GEOSYNTHETIC PPS-10 TURF REINFORCEMENT MAT OR APPROVED EQUAL

EROSION CONTROL MAT

NOT TO SCALE



TYPICAL DRAIN MANOLE DETAIL

NOT TO SCALE

STATE OF MAINE
NANCY J. ST. CLAIR
No. 6877
REGISTERED PROFESSIONAL ENGINEER
12/30/2024

REV:	BY:	DATE:	STATUS:
F	DCS	12-30-2024	FOR TOWN REVIEW
4	DCS	05-03-2024	ASI-001
E	DCS	10-20-2023	FOR TOWN REVIEW
D	DCS	02-03-2022	CONDITIONS OF APPROVAL
C	DCS	12-29-2021	REV. PER CCSWCD, FOR TOWN REVIEW
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland, ME 04021
Tel (207) 829-5558

PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST

DETAIL SHEET
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	NTS

SHEET C-701

21012S TAB 21012D-2

GRASSED UNDERDRAINED SOIL FILTER NOTES

GRASSED UNDERDRAINED SOIL FILTER CONSTRUCTION NOTES

GENERAL:

EROSION AND SEDIMENTATION FROM UNSTABLE CONSTRUCTION AREAS IS THE MOST COMMON REASON FOR FILTER FAILURE. THE SOIL FILTER MEDIA SHALL NOT BE INSTALLED UNTIL THE AREA THAT DRAINS TO IT HAS BEEN PERMANENTLY STABILIZED OR UNLESS THE RUNOFF IS DIVERTED AROUND THE FILTER. PERMANENT STABILIZATION SHALL MEAN THAT TRIBUTARY AREAS ARE EITHER STABILIZED WITH BASE PAVEMENT, 90% VEGETATION OR OTHER PERMANENT STABILIZATION MEASURES.

CONSTRUCTION COMPONENTS: UNDERDRAINED FILTERS CONSIST OF (FROM BOTTOM UP):

- A GEOTEXTILE FABRIC TO SEPARATE THE FILTER BASIN FROM THE NATURAL SOILS. AN IMPERMEABLE MEMBRANE MAY BE REQUIRED IN PLACE OF THE GEOTEXTILE FABRIC IF GROUNDWATER IMPACT OR CONTAMINATION IS A CONCERN, OR IF IT MAY INFLUENCE THE EFFECTIVENESS OF THE BASIN.
- A 12 TO 14-INCH BASE OF COARSE CLEAN STONE OR COARSE GRAVEL IN WHICH A 4-INCH TO 6-INCH PERFORATED UNDERDRAIN PIPE SYSTEM IS BEDDED.
- AN 18-INCH LAYER OF UNCOMPACTED SOIL FILTER MEDIA.
- A SURFACE COVER OF GRASS AND MULCH.

BASIN EXCAVATION: THE BASIN AREA MAY BE EXCAVATED FOR UNDERDRAIN INSTALLATION AND CAN BE USED AS A SEDIMENT TRAP DURING CONSTRUCTION. AFTER EXCAVATION OF THE BASIN, THE OUTLET STRUCTURE AND PIPING SYSTEM MAY BE INSTALLED IF PROTECTED WITH A SEDIMENT BARRIER.

SACRIFICIAL MULCH COVER: IF THE BASIN WILL BE USED AS A SEDIMENT TRAP, THE SIDES OF THE EMBANKMENTS MUST BE STABILIZED AND MAINTAINED TO PREVENT EROSION. THE BASIN WILL NEED TO BE RESTORED FOR ITS PLANNED PURPOSE AFTER CONSTRUCTION. BEFORE FINAL STABILIZATION OF THE DRAINAGE AREA TO THE BASIN, A 2-INCH TO 3-INCH LAYER OF SANDY LOAM (WITH LESS THAN 2% CLAY CONTENT) MAY BE SPREAD ON THE SURFACE OF THE SOIL FILTER MEDIA AS A SACRIFICIAL PROTECTION LAYER. THE SACRIFICIAL LAYER WILL NEED TO BE REMOVED AT THE END OF CONSTRUCTION, AND THE SOIL FILTER MEDIA WILL NEED TO BE SEEDED AND MULCHED.

COMPACTION OF SOIL FILTER: SOIL FILTER MEDIA AND UNDERDRAIN BEDDING MATERIAL SHALL BE APPLIED TO REACH A BULK DENSITY OF BETWEEN 90% AND 92% STANDARD PROCTOR. THE SOIL FILTER MEDIA SHOULD BE INSTALLED IN AT LEAST TWO LIFTS OF 9 INCHES TO PREVENT POCKETS OF LOOSE MEDIA. THE CONTRACTOR SHALL USE CAUTION TO AVOID OVER COMPACTION OF THE FILTER MEDIA.

REMEDIAL LOAM COVER: IF VEGETATION IS NOT ESTABLISHED WITHIN THE FIRST YEAR, THE BASIN MAY BE ROTOTILLED, RESEEDED AND PROTECTED WITH A WELL-ANCHORED EROSION CONTROL BLANKET. OR, A 2-INCH TO 3-INCH LAYER OF FINE SANDY LOAM MAY BE APPLIED BEFORE SEEDING AND MULCHING.

CONSTRUCTION OVERSIGHT: INSPECTION OF THE FILTER BASIN MUST BE PROVIDED FOR EACH PHASE OF CONSTRUCTION BY THE DESIGN ENGINEER, OR QUALIFIED INSPECTING ENGINEER, WITH REQUIRED REPORTING TO THE DEP. ALL MATERIAL INTENDED FOR THE FILTER BASIN MUST BE APPROVED BY THE INSPECTING ENGINEER AFTER TESTS BY A CERTIFIED LABORATORY SHOW THAT THE MATERIAL CONFORMS TO ALL DEP SPECIFICATIONS. THE CONTRACTOR SHALL PROVIDE THE OWNER AND INSPECTING ENGINEER WITH AN UP-TO-DATE CONSTRUCTION SCHEDULE TO ALLOW TIMELY INSPECTIONS DURING THE VARIOUS STAGES OF CONSTRUCTION. AT A MINIMUM, INSPECTIONS SHALL OCCUR:

- AFTER THE PRELIMINARY CONSTRUCTION OF THE FILTER GRADES AND ONCE THE UNDERDRAIN PIPES ARE INSTALLED (NOT BACKFILLED),
- AFTER THE DRAINAGE LAYER IS CONSTRUCTED AND PRIOR TO THE INSTALLATION OF THE SOIL FILTER MEDIA,
- AFTER THE SOIL FILTER MEDIA HAS BEEN INSTALLED, SEEDED AND MULCHED, AND
- AFTER ONE YEAR, TO INSPECT VEGETATION AND MAKE CORRECTIONS.

TESTING AND SUBMITTALS: THE SOURCE OF EACH COMPONENT OF THE SOIL FILTER MEDIA SHALL BE IDENTIFIED PRIOR TO CONSTRUCTION. SAMPLES OF EACH TYPE OF MATERIAL SHOULD BE BLENDED FOR THE FILTER MEDIA AND THE UNDERDRAIN BEDDING MATERIAL. SAMPLES MUST BE A COMPOSITE OF THREE DIFFERENT LOCATIONS (GRABS) FROM THE STOCKPILE OR PIT FACE. SAMPLE SIZE REQUIREMENTS WILL BE DETERMINED BY THE TESTING LABORATORY. A SIEVE ANALYSIS CONFORMING TO ASTM C136 SHALL BE PERFORMED ON EACH TYPE OF THE SAMPLE MATERIAL. TESTING THE PERMEABILITY OF THE SOIL FILTER MEDIA MIXTURE IS REQUIRED FOR THE MIXTURE AT A MEASURED BULK DRY DENSITY OF 90-92% BASED ON ASTM D698.

ALL GRADATION TESTS, INCLUDING HYDROMETER TESTING FOR CLAY CONTENT, AND PERMEABILITY TESTING OF THE SOIL FILTER MATERIAL, SHALL BE PERFORMED BY A QUALIFIED SOIL TESTING LABORATORY. THE CONTRACTOR SHALL SUBMIT FIELD AND LABORATORY RESULTS AND VERIFICATION OF SOIL TESTING COMPLIANCE TO THE OWNER AND THE INSPECTING ENGINEER FOR REVIEW AND APPROVAL BEFORE PLACEMENT. TESTING RESULTS SHALL BE INCLUDED AS PART OF THE INSPECTING ENGINEER'S REPORTING TO THE MDEP.

CONSTRUCTION OF GRASSED UNDERDRAINED SOIL FILTER:

GEOTEXTILE FABRIC: A GEOTEXTILE FABRIC SHALL BE PLACED BETWEEN THE SIDES OF THE FILTER LAYER AND ADJACENT SOIL TO PREVENT THE SURROUNDING SOIL FROM MIGRATING INTO AND CLOGGING THE FILTER OR CLOGGING THE OUTLET. SEAMS SHOULD BE OVERLAPPED A MINIMUM OF 12 INCHES. DO NOT WRAP FABRIC OVER THE PIPE BEDDING AS IT MAY CLOG AND PREVENT FLOWS OUT OF THE FILTER. THE GEOTEXTILE FABRIC SHALL BE MIRAFI 170N OR APPROVED EQUAL.

IMPERMEABLE LINER: AN IMPERMEABLE LINER MAY BE REQUIRED ON CERTAIN SITES, IF NOTED IN THE MDEP PERMIT, OR ON THE PLANS OR DETAILS. IF REQUIRED, THE IMPERMEABLE LINER SHALL BE INSTALLED IN LIEU OF THE GEOTEXTILE FABRIC NOTED ABOVE. THE LINER MUST SEAMLESSLY EXTEND UP THE SIDES OF THE BASIN AND BE ANCHORED INTO THE SUBGRADE. THE IMPERMEABLE LINER MATERIAL SHALL BE WATERPROOF WITH SEALED JOINTS SUCH AS 30MIL PVC OR HDPE, OR APPROVED EQUAL. ALL CROSSINGS OF THE LINER FOR PIPES OR OTHER STRUCTURES SHALL BE SEALED. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL CONFIRM WITH THE OWNER AND ENGINEER WHETHER AN IMPERMEABLE LINER IS REQUIRED FOR EACH BMP.

UNDERDRAIN LAYER: THE PERFORATED PIPING IN THE UNDERDRAIN LAYER SHALL BE BEDDED IN A MINIMUM OF 12 TO 14 INCHES OF UNDERDRAIN BACKFILL MATERIAL, WITH AT LEAST 4 INCHES OF MATERIAL BENEATH THE PIPE AND 4 INCHES ABOVE THE UNDERDRAIN PIPING. THE UNDERDRAIN MATERIAL SHALL CONSIST OF WELL-GRADED, CLEAN, COARSE GRAVEL MEETING THE MAINE DOT SPECIFICATION 703.22 UNDERDRAIN BACKFILL FOR TYPE B UNDERDRAIN.

PERFORATED UNDERDRAIN PIPING: THE PERFORATED UNDERDRAIN PIPING SHALL BE EITHER A 4" DIAMETER OR 6" DIAMETER (AS SPECIFIED ON THE PLANS) RIGID SCHEDULE 40 PVC OR SDR35 PIPE. THE UNDERDRAIN PIPING WITHIN THE FILTER BED SHALL BE SPACED NO FURTHER THAN 15' APART AND SHOULD HAVE A POSITIVE SLOPE TO THE OUTLET INVERT SHOWN ON THE PLANS. STRUCTURE JOINTS SHOULD BE SEALED AND WATER TIGHT. CLEAN OUTS SHALL BE INSTALLED AT THE UPSTREAM ENDS OF THE UNDERDRAIN PIPING. CLEAN OUTS SHALL INCLUDE SCREW CAPS SET NO MORE THAN 2" ABOVE GRADE.

SOIL FILTER BED: THE SOIL FILTER OVER THE GRAVEL UNDERDRAIN PIPE BEDDING MUST BE AT LEAST 18 INCHES DEEP AND MUST EXTEND ACROSS THE ENTIRE FILTER AREA. THIS SOIL MIXTURE SHALL BE A UNIFORM MIX, FREE OF STONES, STUMPS, ROOTS, OR OTHER SIMILAR OBJECTS LARGER THAN TWO INCHES. NO MATERIALS OR SUBSTANCES THAT MAY BE HARMFUL TO PLANT GROWTH CAN BE MIXED WITHIN THE FILTER. EXCEPT FOR AGRICULTURAL SOURCES, MOST ORGANIC SOURCES MAY BE ACCEPTABLE FOR THE ORGANIC COMPONENT OF THE MEDIA. THE MEDIA MIXTURE SHALL HAVE VERY LITTLE OR NO CLAY CONTENT AS TESTED VIA HYDROMETER TEST. SOILS WITH MORE THAN 2% CLAY CONTENT COULD CAUSE FAILURE OF THE SYSTEM AND ARE NOT PERMITTED FOR USE. THE FILTER MUST BE PERMEABLE ENOUGH TO INSURE DRAINAGE WITHIN 24 TO 48 HOURS, YET HAVE SUFFICIENT FINES TO INSURE THE FILTRATION OF FINE PARTICLES AND THE REMOVAL OF DISSOLVED POLLUTANTS.

OPTIONAL HAY LAYER: A LAYER OF HAY CAN BE PLACED TO SEPARATE THE UNDERDRAIN LAYER FROM THE FILTER LAYER ABOVE TO PREVENT SUBSIDENCE OR PLUGGING OF THE UNDERDRAIN LAYER AND/OR PIPE.

SOIL FILTER MEDIA - LAYERED SYSTEM WITH TOPSOIL: THE MEDIA SHALL CONSIST OF A LAYERED SYSTEM THAT TAKES ADVANTAGE OF THE CHARACTERISTICS OF NATURAL SOILS. THE DIFFERENT LAYERS FROM THE BOTTOM UP SHALL BE:

- FILTER LAYER: A 12-INCH LAYER OF LOAMY COARSE SAND WHICH IS LOOSELY INSTALLED AND MEETS THE GRAIN SIZE SPECIFICATION SHOWN IN THE FOLLOWING TABLE.

  LOAMY COARSE SAND SPECIFICATIONS

SIEVE #	%PASSING BY WEIGHT
NO. 10	85-100
NO. 20	70-100
NO. 60	15-40
NO. 200	8-15
200 (CLAY SIZE)	LESS THAN 2.0

- TOPSOIL: THE SURFACE OF THE BASIN SHALL BE COVERED WITH 6 INCHES OF NON-CLAYEY, LOAMY TOPSOIL SUCH AS USDA LOAMY SAND TOPSOIL WITH 5 TO 8% HUMIFIED ORGANIC CONTENT. TOPSOIL FROM THE DEVELOPMENT SITE MAY BE APPROPRIATE BUT IT SHALL BE TESTED FOR ORGANIC CONTENT AND CLAY CONTENT (HYDROMETER TEST) BEFORE APPROVAL FOR INSTALLATION. THE SOIL MUST BE SCREENED, LOOSE, FRIABLE, AND SHALL BE FREE FROM ADMIXTURES OF SUBSOIL, REFUSE, STONES (GREATER THAN 2 INCHES IN DIAMETER), CLUMPS, ROOT AND OTHER UNDESIRABLE FOREIGN MATTER. THE TOPSOIL SHALL BE GENTLY MIXED WITHIN THE FILTER LAYER TO PROVIDE CONTINUITY FOR DEEP ROOT PENETRATION. THE TEETH OF A BACKHOE, A HAND RAKE, A SHOVEL OR ROTOTILLING 2-3 INCHES MAY BE USED TO CREATE A LOOSENED TRANSITION.

SEEDING AND MULCHING: THE FILTER BED SHALL BE SEEDED WITH A DROUGHT TOLERANT GRASS MIX AND MULCHED. WATERING IS RECOMMENDED TO ESTABLISH A HEALTHY VEGETATION BASE. THE FOLLOWING SEED MIX IS RECOMMENDED:


SEED MIX SHALL CONTAIN THE FOLLOWING:

CREEPING RED FESCUE	20 LBS/ACRE
TALL FESCUE	20 LBS/ACRE
BIRDSFOOT TREFOIL	8 LBS/ACRE
TOTAL	48 LBS/ACRE


UPON SEEDING, MULCH WITH HAY OR EROSION CONTROL BLANKET, DO NOT FERTILIZE.

ADDITIONAL INFORMATION:


ADDITIONAL DETAILED INFORMATION IS OUTLINED IN THE MAINE STORMWATER MANAGEMENT DESIGN MANUAL (BEST MANAGEMENT PRACTICES MANUAL VOLUME III DATED MARCH 2016 WITH SUBSEQUENT REVISIONS).



PLAN VIEW




CROSS SECTION



DETAIL


NOTE: SEE GRASSED UD SOIL FILTER NOTES FOR ADDITIONAL INFORMATION.

GRASSED UD SOIL FILTER BMP




ROOF DRIPLINE BMP SECTION

NOT TO SCALE




INFILTRATION TRENCH

NOT TO SCALE



SECTION VIEW



PLAN VIEW

STONE RESERVOIR BENEATH PARKING LOT

NOT TO SCALE

CONSTRUCTION OVERSIGHT

THE APPLICANT WILL RETAIN THE SERVICES OF A PROFESSIONAL ENGINEER TO INSPECT THE CONSTRUCTION AND STABILIZATION OF ALL STORMWATER MANAGEMENT STRUCTURES. IF NECESSARY, THE INSPECTING ENGINEER WILL INTERPRET THE BMP'S CONSTRUCTION PLAN FOR THE CONTRACTOR. ONCE ALL STORMWATER MANAGEMENT STRUCTURES ARE CONSTRUCTED AND STABILIZED, THE INSPECTING ENGINEER WILL NOTIFY THE DEPARTMENT IN WRITING WITHIN 30 DAYS TO STATE THAT THE SITEWORK HAS BEEN COMPLETED. ACCOMPANYING THE ENGINEER'S NOTIFICATION MUST BE A LOG OF THE ENGINEER'S INSPECTIONS GIVING THE DATE OF EACH INSPECTION THE TIME OF EACH INSPECTION AND THE ITEMS INSPECTED ON EACH VISIT, AND INCLUDE ANY TESTING DATA OR SIEVE ANALYSIS DATA OF EVERY MINERAL SOIL AND SOIL MEDIA SPECIFIED IN THE PLANS AND USED ON SITE.

CONSTRUCTION OVERSIGHT: INSPECTION BY A PROFESSIONAL ENGINEER WILL OCCUR AT A MINIMUM:

- AFTER THE PRELIMINARY CONSTRUCTION OF THE FILTER GRADES AND ONCE THE UNDERDRAIN PIPES ARE INSTALLED BUT NOT BACKFILLED,
- AFTER THE DRAINAGE LAYER IS CONSTRUCTED AND PRIOR TO THE INSTALLATION OF THE FILTER MEDIA,
- AFTER THE FILTER MEDIA HAS BEEN INSTALLED AND SEEDED. BIO-RETENTION CELLS MUST BE STABILIZED PER THE PROVIDED PLANTING SCHEME AND DENSITY FOR THE CANOPY COVERAGE OF 30% AND 50%,
- AFTER ONE YEAR TO INSPECT HEALTH OF THE VEGETATION AND MAKE CORRECTIONS,, AND
- ALL THE MATERIAL USED FOR THE CONSTRUCTION OF THE FILTER BASIN MUST BE CONFIRMED AS SUITABLE BY THE DESIGN ENGINEER. TESTING MUST BE DONE BY A CERTIFIED LABORATORY TO SHOW THAT THEY ARE PASSING DEP SPECIFICATIONS.

TESTING AND SUBMITTALS: THE CONTRACTOR SHALL IDENTIFY THE LOCATION OF THE SOURCE OF EACH COMPONENT OF THE FILTER MEDIA. ALL RESULTS OF THE FIELD AND LABORATORY TESTING SHALL BE SUBMITTED TO THE PROJECT ENGINEER FOR CONFIRMATION. THE CONTRACTOR SHALL:

- SELECT SAMPLES FOR SAMPLING OF EACH TYPE OF MATERIAL TO BE BLENDED FOR THE MIXED FILTER MEDIA AND SAMPLES OF THE UNDERDRAIN BEDDING MATERIAL. SAMPLES MUST BE A COMPOSITE OF THE THREE DIFFERENT LOCATIONS (GRABS) FROM THE STOCKPILE OR PIT FACE. SAMPLE SIZE REQUIRED WILL BE DETERMINED BY THE TESTING LABORATORY.
- PERFORM A SIEVE ANALYSIS CONFORMING TO THE STM C136 (STANDARD TESTING METHOD FOR SIEVE ANALYSIS OF FINE AND COURSE AGGREGATES 1996 A) ON EACH TYPE OF THE SAMPLE MATERIAL. THE BIO-RETENTION SOIL FILTER MEDIA MIXTURE MUST HAVE 8% TO 12% BY WEIGHT PASSING THE #200 SIEVE, A CLAY CONTENT OF LESS THAN 2% (DETERMINED HYDROMETER GRAIN SIZE ANALYSIS) AND HAVE 10% DRY WEIGHT OF ORGANIC MATTER.
- PERFORM A PERMEABILITY TEST ON THE SOIL FILTER MEDIA MIXTURE CONFORMING TO ASTM D2434 WITH THE MIXTURE COMPACTED TO 90%-92% OF MAXIMUM DRY DENSITY BASED ON ASTM D698.

UNDERDRAINED FILTER BASINS NOTES

PRIOR TO THE START OF CONSTRUCTION OF ANY UNDERDRAINED FILTER BASIN (I.E. A BIORETENTION CELL OR A GRASSED UNDERDRAINED SOIL FILTER) AT LEAST ONE TEST PIT SHALL BE EXCAVATED IN THE CENTER OF EACH BMP TO DETERMINE THE DEPTH TO GROUNDWATER OR LEDGE. EACH TEST PIT SHALL BE EXCAVATED TO A DEPTH OF AT LEAST 2' BELOW THE BOTTOM OF THE UNDERDRAIN BEDDING. IN THE EVENT THAT GROUNDWATER IS ENCOUNTERED WITHIN THE TEST PIT, AN IMPERMEABLE LINER SHALL BE INSTALLED. THIS LINER SHALL BE INSTALLED IN PLACE OF THE NON-WOVEN GEOTEXTILE FABRIC ON THE SIDES AND BOTTOM OF THE BASIN. IN THE EVENT THAT LEDGE IS ENCOUNTERED IN THE TEST PIT, THE LEDGE SHALL BE REMOVED TO A DEPTH OF AT LEAST THE BOTTOM OF THE UNDERDRAIN BEDDING AND AN IMPERMEABLE LINER SHALL BE INSTALLED. WHERE REQUIRED, A WATERPROOF LINER WITH SEALED JOINTS, SUCH AS 30 MIL PVC OR HDPE, OR APPROVED EQUAL, SHALL BE INSTALLED. ALL CROSSINGS FOR THE LINER FOR PIPES AND OTHER STRUCTURES SHALL BE SEALED.

ROOF DRIP EDGE FILTERS

INSPECTIONS BY A PROFESSIONAL ENGINEER SHALL CONSIST OF WEEKLY VISITS TO THE SITE TO INSPECT OF THE ROOF DRIP EDGE FILTERS UNDERDRAIN CONSTRUCTION, FILTER MATERIAL PLACEMENT FROM INITIAL GROUND DISTURBANCE TO FINAL STABILIZATION OF THE FILTER.

DEWATERING


A DEWATERING PLAN IS REQUIRED TO ADDRESS EXCAVATION DEWATERING FOLLOWING HEAVY RAINFALL EVENTS OR WHERE THE EXCAVATION MAY INTERCEPT THE GROUNDWATER TABLE DURING CONSTRUCTION. THE COLLECTED WATER NEEDS TREATMENT AND A DISCHARGE POINT THAT WILL NOT CAUSE DOWNGRADIENT EROSION AND OFFSITE SEDIMENTATION WITHIN A RESOURCE.

BASIC STANDARDS - EROSION CONTROL MEASURES

EROSION CONTROL MEASURES SHALL BE IMPLEMENTED AS DESCRIBED IN THE PLAN SET AND IN THE SEPARATE EROSION AND SEDIMENT CONTROL PLAN NARRATIVE AND INSPECTION AND MAINTENANCE PLAN FOR THIS PROJECT. THE CONTRACTOR (AND APPLICANT) SHALL BE RESPONSIBLE TO MAINTAIN ALL COMPONENTS OF THE EROSION CONTROL PLAN UNTIL THE SITE IS FULLY STABILIZED. HOWEVER, BASED ON SITE AND WEATHER CONDITIONS DURING CONSTRUCTION, ADDITIONAL EROSION CONTROL MEASURES MAY NEED TO BE IMPLEMENTED. ALL AREAS OF INSTABILITY AND EROSION MUST BE REPAIRED IMMEDIATELY DURING CONSTRUCTION AND NEED TO BE MAINTAINED UNTIL THE SITE IS FULLY STABILIZED OR VEGETATION IS ESTABLISHED. A CONSTRUCTION LOG MUST BE MAINTAINED FOR THE EROSION AND SEDIMENTATION CONTROL INSPECTIONS AND MAINTENANCE.

BIO-RETENTION CELL OVERSIGHT NOTES

NOT TO SCALE



BIO-RETENTION CELL BMP DETAIL

NOT TO SCALE

STATE OF MAINE — NANCY J. ST. CLAIR No. 6877 — REGISTERED PROFESSIONAL ENGINEER
12/30/2024

REV:	BY:	DATE:	STATUS:
4	DCS	05-03-2024	ASI-000
F	DCS	11-29-2023	ADD DETAIL
E	DCS	10-20-2023	FOR TOWN REVIEW
D	DCS	02-03-2022	CONDITIONS OF APPROVAL
C	DCS	12-29-2021	REV. PER CCSWCD, FOR TOWN REVIEW
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland, ME 04021
Tel (207) 829-5558


PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST


DETAIL SHEET
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	NTS

SHEET C-702


21012S TAB 21012D-1






NOTES:
1) USE MOLD 1 FOR AREAS WHERE SIDEWALK SHALL DIRECTLY ABUTS CURB. SEE PLAN FOR LOCATIONS.


CONCRETE SLIPFORM CURB DETAIL
NOT TO SCALE




TYPICAL PAVED ENTRANCE/PARKING DETAIL
NOT TO SCALE



TYPICAL PAVEMENT JOINT
NOT TO SCALE




TYPICAL PAVED TRAIL DETAIL
NOT TO SCALE




NOTES:
1) INSTALLATION SHOULD NOT ALLOW THE INTER-TWINING OF CABLES.
2) BEDDING AND BACKFILL SHALL BE FREE OF ROOTS, STUMPS AND OTHER DEBRIS.
3) COMMUNICATION CABLE AND POWER CABLE SHALL HAVE NO LESS THAN 12-INCHES OF RADIAL SEPARATION.
4) ELECTRICAL CONDUIT SHALL BE SCHEDULE 40 PVC OR AS DIRECTED BY CMP CO. DESIGN ENGINEERS.
5) REFER TO THE CMP CO. HANDBOOK OF REQUIREMENTS FOR ELECTRIC SERVICE AND INSTALLATIONS, LATEST EDITION FOR ADDITIONAL INFORMATION.


TYPICAL UNDERGROUND CABLE INSTALLATION
NOT TO SCALE




ACCESSIBLE PARKING SIGN & PAVEMENT PAINT
N.T.S.



FIRE HYDRANT
NOT TO SCALE



SEWER CLEANOUT
NOT TO SCALE




SCHEDULE OF TRENCH BACKFILL		
TYPE OF PIPE	EMBEDMENT MATERIAL	SELECT BACKFILL
CMP DUCTILE IRON RCP	MDOT 703.22 TYPE B UD BACKFILL	MDOT 703.22 TYPE B UD BACKFILL
PVC-SDR 35 HDPE	MDOT 703.22 TYPE C ¾" CRUSHED STONE	MDOT 703.22 TYPE B UD BACKFILL
PERFORATED PVC-SDR35 HDPE	MDOT 703.22 TYPE C ¾" CRUSHED STONE	MDOT 703.22 TYPE C ¾" CRUSHED STONE

NOTES:


BRACING AND SHEETING OR OTHER TRENCH PROTECTION TO BE PROVIDED TO MEET APPLICABLE STATE AND O.S.H.A. SAFETY STANDARDS. ALL SUCH TRENCH PROTECTION TO BE THE RESPONSIBILITY OF THE CONTRACTOR.


INSTALL WARNING TAPE DIRECTLY ABOVE UTILITIES, 12" BELOW FINISH GRADE.

PIPE TRENCH
NOT TO SCALE




GATE VALVE
NOT TO SCALE






NOTES:
1. INSTALL 3 FOOT LONG IMPERVIOUS DAMS IN BEDDING/INITIAL BACKFILL MATERIAL EVERY 100 FEET TO PREVENT TRENCH GROUNDWATER FROM BEING CHANNELED ALONG BEDDING/INITIAL BACKFILL.
2. REFER TO LATEST MDOT SPECIFICATIONS FOR BEDDING AND BACKFILL REQUIREMENTS.
3. INITIAL BACKFILL TO BE 12 INCHES OVER TOP OF PVC PIPE ONLY.

TYP. SEWER TRENCH
NOT TO SCALE




NOTES: MINIMUM DEPTH OF COVER IS 5'-0"

TRENCH DETAIL
NOT TO SCALE



NOTE: TRACER WIRE MUST BE PROVIDED FOR 2" PECTS

SERVICE TAP
NOT TO SCALE



TYPICAL DUMPSTER ENCLOSURE
NOT TO SCALE

REV:	BY:	DATE:	STATUS:
D	DCS	12-30-2024	FOR TOWN REVIEW
5	DCS	09-12-2024	CONTRACTOR RFI
4	DCS	05-03-2024	ASI-001
C	DCS	02-03-2022	CONDITIONS OF APPROVAL
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN, SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

STATE OF MAINE — NANCY J. ST. CLAIR No. 6877 — REGISTERED PROFESSIONAL ENGINEER — 12/30/2024

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland Center, ME 04021
Tel (207) 829-5558


PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012		ELECT.	DCS	DCS	NST

DETAIL SHEET
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	NTS

SHEET C-703

21012S TAB 21012D-4



WATERSHED AREA

SUBCATCHMENT:	COVER TYPE:	AREA:
1	IMPERVIOUS	3,541 S.F.
	MEADOW	8,582 S.F.
	WOODS	57,132 S.F.
2	WOODS	51,322 S.F.
3	WOODS	4,297 S.F.
4	WOODS	3,340 S.F.
5	WOODS	1,763 S.F.
6	WOODS	678 S.F.
7	WOODS	22,005 S.F.
8	IMPERVIOUS	621 S.F.
	MEADOW	897 S.F.
	WOODS	5,149 S.F.

OVERALL WATERSHED AREA: 159,327 S.F.

LEGEND (WATERSHED MAP)

EXISTING	DESCRIPTION	PROPOSED
	TCPATH	
	WATERSHED	
	SUBCATCHMENT	
	STUDY POINT	
	POND	

SOILS LEGEND

1) SOILS TYPE

LABEL	SOIL NAME	SLOPE	HYDROLOGIC SOIL GROUP
Au	AU GRES LOAMY SAND	0% TO 3% SLOPES	HSG A
Wa	WALPOLE FINE SANDY LOAM	0% TO 3% SLOPES	HSG A

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	
	BUILDING	
	EDGE PAVEMENT	
	EDGE OF GRAVEL	
122 120	CONTOURS	
30.20	SPOT GRADE	+30.20
S	SEWER	S
S	SEWER MH	
	UNDERDRAIN	UD
	UNDERGROUND ELEC. & TEL.	UGT/E
	TREELINE	
	DECIDUOUS TREE	X
	CONIFEROUS TREE	X

GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

STATE OF MAINE
NANCY J. ST. CLAIR
No. 6877
REGISTERED PROFESSIONAL ENGINEER
12/30/2024

REV:	BY:	DATE:	STATUS:
D	DCS	12-30-2024	FOR TOWN REVIEW
4	DCS	05-03-2024	ASI-001
C	DCS	02-03-2022	CONDITIONS OF APPROVAL
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland, ME 04021
Tel (207) 829-5558

PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012		ELECT.	DCS	DCS	NST

PRE DEVELOPMENT WATERSHED MAP
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET C-800

21012'S TAB 21012PRE

WATERSHED AREA

SUBCATCHMENT:	COVER TYPE:	AREA:
1	IMPERVIOUS	8,444 S.F.
	GRASS, FAIR	4,984 S.F.
2	WOODS	24,304 S.F.
	MEADOW	12,855 S.F.
3	WOODS	4,184 S.F.
4	WOODS	3,340 S.F.
5	WOODS	1,721 S.F.
6	WOODS	623 S.F.
	MEADOW	51 S.F.
7	IMPERVIOUS	52 S.F.
	WOODS	1,936 S.F.
	MEADOW	14,981 S.F.
8	THOMAS PT. RD.	620 S.F.
	BRUSH	1,802 S.F.
9	IMPERVIOUS	9,218 S.F.
	GRASS, GOOD	5,008 S.F.
10	IMPERVIOUS	1,723 S.F.
	THOMAS PT. RD.	3,541 S.F.
	WOODS	18,630 S.F.
	MEADOW	17,086 S.F.
11	BUILDING	17,881 S.F.
	IMPERVIOUS	114 S.F.
	GRASS, FAIR	4,434 S.F.
12	BUILDING	1,440 S.F.
	GRASS	360 S.F.

OVERALL WATERSHED AREA: 159,332 S.F.

LEGEND (WATERSHED MAP)

EXISTING	DESCRIPTION	PROPOSED
→	TCPATH	→
⬡	SUBCATCHMENT	⬡
□	STUDY POINT	□
△	POND	△

SOILS LEGEND

1) SOILS TYPE

LABEL	SOIL NAME	SLOPE	HYDROLOGIC SOIL GROUP
Au	AU GRES LOAMY SAND	0% TO 3% SLOPES	HSG A
Wa	WALPOLE FINE SANDY LOAM	0% TO 3% SLOPES	HSG A

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	
	BUILDING	
	EDGE PAVEMENT	
	EDGE OF GRAVEL	
--122--	CONTOURS	--120--
30.20	SPOT GRADE	+30.20
S	SEWER	S
Ⓢ	SEWER MH	
	UNDERDRAIN	UD
	UNDERGROUND ELEC. & TEL.	UGT/E
	TREELINE	
	DECIDUOUS TREE	X
	CONIFEROUS TREE	X

GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

REV:	BY:	DATE:	STATUS:
E	DCS	12-30-2024	FOR TOWN REVIEW
4	DCS	05-02-2024	ASI-001
D	DCS	02-03-2022	CONDITIONS OF APPROVAL
C	DCS	12-29-2021	REVISED PER CCSWCD REVIEW COMMENTS
B	DCS	11-23-2021	FOR TOWN REVIEW
A	DCS	10-05-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

STATE OF MAINE — NANCY J. ST. CLAIR No. 6877 — REGISTERED LAND SURVEYOR — 12/30/2024

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland Foresides, ME 04021
Tel (207) 829-5558


PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST

POST DEVELOPMENT WATERSHED MAP
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET C-900

21012S TAB 21012POST



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	BOUNDARY LINE/R.O.W.	
	ABUTTER LINE/R.O.W.	
	SETBACK	
	EASEMENT	
	MONUMENT	
	IRON PIPE/ROD	
	BUILDING	
	EDGE PAVEMENT	
	EDGE OF GRAVEL	
--122--	CONTOURS	--120--
30.20	SPOT GRADE	+30.20
S	SEWER	S
S	SEWER MH	
	UNDERDRAIN	UD
	UNDERGROUND ELEC. & TEL.	UGT/E
	TREELINE	
	DECIDUOUS TREE	X
	CONIFEROUS TREE	X

REV:	BY:	DATE:	STATUS:
B	DCS	12-30-2024	FOR TOWN REVIEW
4	DCS	05-03-2024	ASI-001
A	DCS	11-23-2021	FOR TOWN REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM ST.CLAIR ASSOCIATES ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO ST.CLAIR ASSOCIATES

ST.CLAIR ASSOCIATES
LAND SURVEYING AND CIVIL ENGINEERING
34 Forest Lane
Cumberland, ME 04021
Tel (207) 829-5558

PROJECT NO.	FIELD BOOK	DESIGN	CHKD	DRAWN
21012	ELECT.	DCS	DCS	NST

VEHICLE SIMULATION - FIRE TRUCK
OF:
THOMAS POINT ROAD PROPERTY
THOMAS POINT ROAD
BRUNSWICK, MAINE
FOR:
TEDFORD HOUSING
P.O. BOX 958
BRUNSWICK, ME 04011

DATE	SCALE
02-09-2021	1"=30'

SHEET 1 .

21012S TAB 21012 FIRE TRUCK TURN

Town of Brunswick, Maine

DEPARTMENT OF PLANNING AND DEVELOPMENT

APPROVED FINDINGS OF FACT
FINAL PLAN MAJOR DEVELOPMENT REVIEW
PLANNING BOARD

REVIEW DATE: January 11, 2022
CASE NUMBER: 21-070
PROJECT NAME: Tedford Housing Homeless Shelter, Resource Center
ADDRESS/ TAX MAP: Map 42, Lots 8 and 11
ZONING DISTRICT: Growth Mixed-Use 4 (GM4) Zoning District
OVERLAY ZONING: Cook's Corner Master Plan and Design Standards
APPLICANT: Tedford Housing
P.O. Boc 958
Brunswick, ME 04011
REPRESENTATIVE: Nancy St. Clair
St. Clair Associates
34 Forest Lane
Cumberland, ME 04011

I. APPLICATION COMPLETENESS

Staff has reviewed the application and determined that it is complete.

Approved Motion:

The Planning Board concurs with staff's conclusion that the basic Final Plan Major Development Review application materials have been submitted and that the application is complete such that the Board may proceed with substantive review of the application and identification of any further information required from the applicant.

First: Art Pierce Second: Rob Burgess Vote: 7-0-0

II. PROJECT SUMMARY

The approved Findings of Fact are based on the Final Plan Major Development Review Application titled "Major Development Review Tedford Housing Building" and dated November 23, 2021 (Exhibit A). The Planning Board reviewed and approved a Sketch Plan Major Development Review Application on September 8, 2021 (Exhibit B). The Staff Review Committee (SRC) reviewed the Final Plan Major Development Review application on December 8, 2021. The SRC meeting notes are included under separate cover.

The proposed *homeless shelter, resource center* is intended to provide temporary emergency housing and on-site resources for individuals and households that are clients of Tedford Housing. The proposed shelter is approximately 17,568 square feet and it will include ten (10) household apartment-style units, each with a bedroom with four (4) beds and living and dining space in each unit. The proposed shelter will also accommodate twenty-four (24) individual clients in a dormitory-style space. Therefore, the total number of beds proposed is sixty-four (64). The applicant has indicated that the facility will not be a "drop-in" facility available to any member of the public. Occupants of the shelter must be enrolled in Tedford Housing's programs to help seek

new housing options.

The project site will be served by a twenty-six (26) space parking lot, two (2) of which will be compliant with Americans with Disabilities Act (ADA) standards. Additional site improvements include interior walkways with benches, play area, connection to the retail center to the northeast of the site, small storage building, and a dumpster enclosure.

The applicant has included a Purchase and Sale Agreement with the property to demonstrate right, title, and interest.

III. REVIEW STANDARDS

3.4.1.X Homeless Shelter Supplementary Use Standards

Subsection (1) provides the formulas necessary to calculate maximum density allowed for a *homeless shelter, resource center.* Based on the underlying GM4 Zoning District, the maximum number of dwelling units permitted for the subject property is forty-six (46) dwelling units. The proposed project includes ten (10) apartment-style household units and twenty-four (24) dormitory-style beds for individuals. Using the formula, the twenty-four (24) individual beds equate to six (6) residential dwelling units. Therefore, the total number of dwelling units is calculated as sixteen (16), well below the maximum number of units allowed.

Subsection (2) provides the formulas necessary to calculate the demand for parking spaces for a *homeless shelter, resource center*. Using these formulas, the included traffic study by Maine Licensed Traffic Engineers John Adams and Bill Bray of Barton and Loguidice / Traffic Solution calculates the minimum parking demand as twenty-six (26) parking spaces. The proposed project provides the minimum twenty-six (26) parking spaces, including two (2) spaces compliant with the Americans with Disabilities Act (ADA).

Subsection (3) requires the applicant to provide interior floor plans dimensioned with spaces labeled with the proposed use. The applicant has provided floor plans prepared by Ryan Senatore Architecture in their application.

Subsection (4) requires non-apartment-style homeless shelter space to be dedicated for use by unaccompanied minors under eighteen (18) years of age or adults, but not both. The applicant has indicated that the dormitory-style section of the building is intended only for individual adults.

Subsection (5) requires a minimum 1,000-foot separation between any new homeless shelter and any existing homeless shelter. The nearest homeless shelter, which is operated by Tedford Housing, is approximately 2.6 miles from the subject property.

The Planning Board finds that the provisions of Section 3.4.1.X are satisfied.

4.1. Applicability of Property Development Standards

As the proposed project is for a commercial use, all regulations established in *Chapter 4 – Property Development Standards* of the Zoning Ordinance apply. The Town Codes Enforcement Officer and other members of the SRC have reviewed the application

and found that it complies with all applicable Zoning Ordinance standards associated with the GM4 Zoning District.
The Planning Board finds that the provisions of Section 4.1 are satisfied.

4.2. Dimensional and Density Standards

As referenced in Item 4.1 above, the proposed project has been found to comply with all applicable property developments standards. This includes the standards established in *Table 4.2.3. Growth Area Dimensional and Density Standards* of the Zoning Ordinance.

The Planning Board finds that the provisions of Section 4.2 are satisfied.

4.3. Natural and Historic Areas

4.3.1 Mapping of Natural and Historic Areas Requirements

As there were no natural or historic areas identified via the wetland delineation study performed by Mark Hampton Association, the Maine Natural Areas Program (MNAP), or the Town's GIS system.

The Planning Board finds that the provisions of Section 4.3.1 are not applicable.

4.3.2 Pollution

The subject property is not located within any floodplain or other special flood hazard area. No on-site wastewater is proposed as the applicant is proposing to connect to the Brunswick Sewer District system. Stormwater will be managed via Maine Department of Environmental Protection's Best Management Practices to treat stormwater runoff prior to discharge.

The Planning Board finds that the provisions of Section 4.3.2 are satisfied.

4.3.3 Protection of Natural Vegetation

As indicated in Item 4.3.1 above, no natural areas were identified on the subject property.

The subject property is not located in any designated scenic area.

The applicant has indicated that the site plan was developed with an attempt to protect existing wooded area to the greatest extent possible.

As indicated on the landscape plan, the subject property will be improved with new plantings and fencing.

The Planning Board finds that the provisions of Section 4.3.3 are satisfied.

4.3.4 Protection of Significant Plant and Animal Habitat

As stated in Items 4.3.1, the proposed project is not located within the Town's

Wildlife Protection Overlay (WPO) District and no other mapped significant plant and animal habitats were identified during the review process. Therefore, the proposed project will not have an undue adverse effect on important plant and animal habitats identified by the Maine Department of Inland Fisheries and Wildlife, or on rare and irreplaceable natural areas as identified by the Maine Natural Areas Program.

The Planning Board finds that the provisions of Section 4.3.4 are not applicable.

4.3.5 Steep Slopes

The subject property on which the proposed project is to be constructed does not have any 5,000 square foot or more of contiguous slopes exceeding twenty-five percent (25%).

The Planning Board finds that the provisions of Section 4.3.5 are not applicable.

4.3.6 Erosion and Sedimentation

The applicant has provided an Erosion and Sediment Control Plan and Narrative demonstrating that the plans have been developed according to the DEP's Best Management Practices Handbook. The plan also provided post-construction requirements. Furthermore, an Inspection and Maintenance Plan and Log have been provided.

The Planning Board finds that the provisions of Section 4.3.6 are satisfied.

4.3.7 Groundwater

The subject property is not located with any of the Town's Aquifer Protection Overlay (APO) Districts. Sewage will be conveyed by a connection to the Brunswick Sewer District. The applicant has indicated that they will construct an extension from Brunswick and Topsham Water District's water main along Thomas Point Road. The above referenced Best Management Practices for stormwater runoff and erosion and sedimentation control will treat stormwater prior to discharge.

The Planning Board finds that the provisions of Section 4.3.7 are satisfied.

4.3.8 Surface Waters, Wetlands, and Marine Resources

The wetland delineation study found no surface waters or wetlands on the subject property.

The Planning Board finds that the provisions of Section 4.3.8 are not applicable.

4.3.9 Historic and Archaeological Resources

No historic or archaeological resources were identified within the subject property.

The Planning Board finds that the provisions of Section 4.3.9 are not applicable.

4.4. Flood Hazard Areas

The subject property is not located within the Flood Protection Overlay (FPO) District or mapped Flood Hazard Area.

The Planning Board finds that the provisions of Section 4.4. are not applicable.

4.5. Basic and Municipal Services

4.5.1 Sewage Disposal

The proposed project will connect to the Brunswick Sewer District System.

The Planning Board finds that the provisions of Section 4.5.1 are satisfied.

4.5.2 Water Supply and Quality

The applicant has indicated that they will construct an eight-inch (8") diameter extension approximately 702 feet from the nearest connection to the Brunswick and Topsham Water District.

The Planning Board finds that the provisions of Section 4.5.2 are satisfied

4.5.3 Solid Waste Disposal

The site plan includes a dumpster enclosure for solid waste disposal. The applicant has indicated that they will contract with a local commercial waste hauler.

The Planning Board finds that the provisions of Section 4.5.3 are satisfied.

4.5.4 Stormwater Management

The proposed project requires only a DEP Stormwater Permit by Rule. The applicant has included an approved permit as an addendum to this application.

The Planning Board finds that the provisions of Section 4.5.1 are satisfied.

4.6. Landscaping Requirements

The proposed landscape plan has been reviewed by the Town Codes Enforcement Officer and Town Arborist and found to be consistent with all applicable Zoning Ordinance landscape standards. The applicant has also provided amenities such as an internal green space, benches, bicycle racks, and an outdoor play area.

The Planning Board finds that the provisions of Section 4.6 are satisfied.

4.7. Residential Recreation Requirements

As there are no permanent residential dwelling units proposed, the residential recreation impact fees are not applicable to the proposed project.

The Planning Board finds that the provisions of Section 4.7 are not applicable.

4.8. Circulation and Access

4.8.1 Street Standards

No new streets are proposed as part of the project. The applicant provided a traffic study with an estimated sixteen (16) peak hour trips. This number falls below the one-hundred (100) trips that would trigger the need for a traffic movement permit from Maine DOT. Furthermore, the traffic associated with the proposed project is not anticipated to impact the existing level of service.

The Planning Board finds that the provisions of Section 4.8.1 are satisfied.

4.8.2 Circulation and Access

There is one (1) access point proposed. The Town Engineer did not state any concerns with the location and dimensions of the access point. However, an entrance permit from the Town Engineer will be required.

The Planning Board finds that the provisions of Section 4.8.2 are sastisfied.

4.8.3 Pedestrian and Bicycle Access

A network of internal paths and walkways, including a connection to the Wal-Mart shopping center, are proposed. Bicycle racks are provided on-site. Furthermore, the applicant has indicated their willingness to contribute to a sidewalk fund that will be used for the future Thomas Point Road improvements.

The Planning Board finds that the provisions of Section 4.8.3 are satisfied.

4.8.4 Access for Persons with Disabilities

The site plan has been developed in accordance with Americans with Disability Act (ADA) design standard. This includes access from two (2) ADA-compliant parking spaces with accessible routes to the building entrance. ADA-compliant ramps are provided where necessary.

The Planning Board finds that the provisions of Section 4.8.4 are satisfied.

4.9. Parking and Loading

The twenty-six (26) parking spaces (include two (2) ADA-compliant spaces) provided meet the minimum parking demand standards for homeless shelters established in Section 4.3.1.X of the Zoning Ordinance.

A bicycle rack for six (6) bicycles meets the minimum standard.

All parking spaces meet the minimum dimensional standards.

The Planning Board finds that the provisions of Section 4.9 are satisfied.

4.10. Lighting

The applicant has included spec sheets for full cut-off lighting fixtures to be used on the subject property. The included photometric plan indicates that there will be no light trespass onto surrounding properties. The applicant did not indicate the proposed color temperature for the outdoor lighting but is strongly encouraged not to exceed 3,000 Kelvin.

The Planning Board finds that the provisions of Section 4.10 are satisfied.

4.11. Architectural Compatibility

The applicant has included a memorandum from Ryan Senatore Architecture outlining the architectural treatments used to be consistent with the Cook's Corner Design Standards. Such traditional New England architectural features include its main gable roof with smaller gable dormers perpendicular to the main roof and gabled projecting bays.

Consistent with traditional New England architecture, the proposed windows are double-hung with mullions dividing the individual panes.

Proposed exterior material include fiber cement siding with battens and architectural asphalt shingles, both of which are used throughout the surrounding area.

The Planning Board finds that the provisions of Section 4.11 are satisfied.

4.12. Neighborhood Protection Standards

As the proposed project is surrounded by the GM4 Zoning District neighborhood protection standards do not apply.

The Planning Board finds that the provisions of Section 4.12 are not applicable.

4.13. Signs

The proposed project includes a monument and building mounted sign. The Town Codes Enforcement Officer reviewed the proposed signage and found it consistent with Section 4.13

The Planning Board finds that the provisions of Section 4.13 are satisfied.

4.14. Performance Standards

The applicant has indicated their ability to comply with all of the performance standards pertaining to noise, smoke and particulate matter, dust and fumes, odors,

vibrations, unlicensed motor vehicles, or lighting and glare. If approved, construction of the facility will occur between the permitted hours of 7:00 AM – 7:00 PM

The Planning Board finds that the provisions of Section 4.14 are satisfied.

4.15. Site Maintenance

The applicant has indicated that the proposed project will be maintained consistent with their standard in place at their existing locations. The stormwater management plan accounts for the necessary maintenance of BMPs. A Inspection and Maintenance Plan and Log is included with the application.

This finding serves to advise the applicant that site features constructed or installed as required by this development review must be maintained in good repair, and replaced if damaged or destroyed, or in the case of living materials, if they die or are effectively destroyed after installation.

The Planning Board finds that the provisions of Section 4.15 are satisfied.

4.16. Financial and Technical Capacity

The application includes a Purchase and Sale Agreement with the owner of the subject properties. Copies of the subject properties' deeds are also included. An updated letter, dated November 22, 2021, from Bath Savings Institute is included and indicates the applicant's financial capacity to completed the proposed project.

A performance guarantee is required prior to the construction of the infrastructure intended to be dedicated to the Brunswick and Topsham Water District. According to the applicant, the BTWD has indicated the potential that they will cover the cost difference between installing a twelve-inch (12") diameter water main rather than the proposed eight-inch (8") diameter water main.

The introduction letter includes all members of the project's design team and their associated qualifications.

The Planning Board finds that the provisions of Section 4.16 are satisfied, provided the applicant provide a performance guarantee to the Brunswick and Topsham Water District.

4.17. Administrative Adjustments / Alternative Equivalent Compliance

No administrative adjustments or alternative equivalent compliance plans are requested.

The Planning Board finds that the provisions of Section 4.17 are not applicable.

IV. EXHIBITS

A. Final Plan Major Development Review Application, dated November 23, 2021
B. Sketch Plan Major Development Review Documentation, dated September 8, 2021

APPROVED MOTION
CASE NO. 21-070
REVIEW DATE: JANUARY 11, 2022

APPROVED MOTION: That the Final Plan Major Development Review for the properties located at Map 42, Lots 8 and 11is approved with the following conditions:

1. That the Planning Board's review and approval does hereby refer to these findings of fact, the plans and materials submitted by the applicant and the written and oral comments of the applicant, his representatives, reviewing officials, and members of the public as reflected in the public record. Any changes to the approved plan not called for in these conditions of approval or otherwise approved by the Director of Planning and Development as a minor modification shall require a review and approval in accordance with the Brunswick Zoning Ordinance.

2. Prior to the issuance of a building permit, the applicant shall submit to the Department of Planning and Development a copy of a performance guarantee approved by the Brunswick and Topsham Water District.

3. Prior to the issuance of a building permit, the applicant shall submit to the Director of Planning and Development documentation depicting Lots 8 and 11 as consolidated.

4. Prior to the issuance of a building permit, the applicant shall submit to the Department of Planning and Development a copy of a letter from the Brunswick Sewer indicating their ability to serve the project.

5. Prior to the issuance of a Certificate of Occupancy, the applicant shall submit to the Department of Planning and Develop an as-built construction plan per the request of the Cumberland County Soil and Water Conservation District.

6. Should within the next five (5) years the Town of Brunswick fund improvements to Thomas Point Road, as proposed in the existing Capital Improvement Plan, the applicant, prior to the start of said improvements, shall contribute funds for materials, mutually agreed upon in cost, for a sidewalk along the subject properties' Thomas Point Road frontage, not to exceed 387 feet in length. Should the Town not commence construction of the sidewalk within five (5) years of the date of approval this condition shall become null and void.

First: Kelly Matzen Second: Jane Arbuckle Vote: 7-0-0

Draft
Town of Brunswick
Minutes
Planning Board
Tuesday, January 28, 2025 @ 6:00 PM

Committee Members Present: Bill Dana, Kelly Matzen, Rob Burgess, Arthur Pierce, Alison Harris, Laura Hatmaker, Chris Baldwin (online)

Committee Members Absent:

Call to Order

Chair Dana called the meeting to order and acknowledged the meeting was properly noticed.

1. **Case No. 24-071 Northbridge Apartments -** The Planning Board will review and act upon a **Sketch Plan Major Development Review** application submitted by Atlantic Resource Consultants on behalf of Northbridge Brunswick Land, LLC for 4 multi-family buildings with 24 units each (96 units in total), associated parking and amenities. The subject property, 0 Admiral Fitch Avenue (Map 040 Lot 50), is located within the **Growth Mixed-Use 7 Zoning District (GM7)**. (This item began at 0:02:00).

   Member Pierce motioned that the Staff Review Committee concurs with staff's conclusion that the basic Sketch Plan Major Development Review application materials have been submitted and that the application is complete such that the Committee may proceed with substantive review of the application and identification of any further information required from the applicant. Member Hatmaker seconded. The motion carried with all in favor. None opposed.

   Wendy Nowokunski and Silas Canavan presented to the board.

   The board discussed.

   Member Harris motioned that the Sketch Plan Application is approved. Member Pierce seconded. The motion carried with all in favor. None opposed.

2. **Case No. 24-072 Pleasant Street Dental Conditional Use Permit –** The Planning Board will hold a **PUBLIC HEARING** and act upon a **Conditional Use Permit** application submitted by Dextrous Creative on behalf of James Moshier, DMD for expansion of the existing **Office** use. The project will expand the building footprint by 333 sq ft to add a wheelchair lift and stairs to the second floor which will be expanded by 946 sq ft. The subject property, 53 Pleasant Street (Map U16 Lot 51), is located within the **Growth Residential 6 Zoning District (GR6)** and the **Village Review Overlay District (VRO).**

3. **Case No. 24-073 Pleasant Street Dental Minor Review -** The Planning Board will review and act upon a **Minor Development Review** application submitted by Dextrous Creative on behalf of James Moshier, DMD for expansion of an existing dental office. The project will expand the building footprint by 333 sq ft to add a wheelchair lift and stairs to the second floor which will be enlarged by 946 sq ft. The subject property, 53 Pleasant Street (Map U16 Lot 51), is located within the **Growth Residential 6 Zoning District (GR6)** and the **Village Review Overlay District (VRO).**

   (These items were discussed together beginning at 0:52:30).

   Member Matzen recused himself.

Member Harris motioned that the Board concurs with planning staff's conclusion that the Conditional Use Permit application materials and the basic Minor Development Review application materials have been submitted and that the applications are complete such that the Board may proceed with substantive review of the application and identification of any further information required from the applicant. Member Hatmaker seconded. The motion carried with all in favor. None opposed.

The board discussed.

Member Burgess motioned that a Conditional Use Permit for an "Office" at the property located at 53 Pleasant Street (Map U16 Lot 51) is approved with the following conditions: 1) That the Board's review and approval does hereby refer to these findings of fact, the plans and materials submitted by the applicant and the written and oral comments of the applicant, their representatives, reviewing officials, and members of the public as reflected in the public record. Any changes to the approved plan not called for in these conditions of approval or otherwise approved by the Director of Planning and Development as a minor modification shall require a review and approval in accordance with the Brunswick Zoning Ordinance. Member Pierce seconded. The motion carried with all in favor.

Member Pierce motioned that the Planning Board approves the Minor Development Review application for the office addition on the property located at 53 Pleasant Street (Map U16 Lot 51), as outlined in the application, with the following conditions: 1) That the Board's review and approval does hereby refer to these findings of fact, the plans and materials submitted by the applicant and the written and oral comments of the applicant, their representatives, reviewing officials, and members of the public as reflected in the public record. Any changes to the approved plan not called for in these conditions of approval or otherwise approved by the Director of Planning and Development as a minor modification shall require a review and approval in accordance with the Brunswick Zoning Ordinance. 2) Prior to the issuance of a building permit, the applicant shall supply a commitment letter from a financial institution for the estimated project amount, to the satisfaction of the Director of Planning and Development. Member Harris seconded. The motion carried with all in favor.

4. **Case No. 24-076 Extension Request for Tedford Housing Site Plan Major Development Review Approval -** The Planning Board will review and act on a **Site Plan Major Development Review Approval Extension Request** of the approved Case No. 21-070, Tedford Housing Homeless Shelter, Resource Center, submitted by St. Clair Associates on behalf of the property owner, Tedford Housing. The subject property is located at 65 Thomas Point Road (Map 42, Lot 8) and within the **Growth Mixed-Use 4 (GM4) Zoning District**. (This item began at 1:08:30).

   Nancy St. Clair presented to the board. The board discussed.

   Member Pierce motioned that the Tedford Housing Homeless Shelter, Resource Center (Case# 21-070) Approval is extended until January 11, 2027 with the following condition: 1) All agreed upon conditions of the initial January 11, 2022 approval remain in effect. Member Hatmaker seconded. The motion carried with all in favor. None opposed.

5. **Other Business** (This item began at 1:17:10).

   The board discussed.

6. **Adjournment:**

   The meeting adjourned.

Julia Pols
Recording Secretary
2/26/25

PLEASE NOTE: THESE MINUTES ARE ACTION MINUTES. THE ENTIRE MEETING CAN BE VIEWED AT WWW.BRUNSWICKME.GOV

From: Julie Erdman
To: Jen Navarro
Cc: James Dealaman
Subject: RE: 211 ft away from Tedford
Date: Wednesday, February 26, 2025 11:47:58 AM
Attachments: image001.png
image002.png
image003.png
image004.png
image005.png
image006.png
image007.png

Hi Jennifer,

The ZBA will be the ones to decide whether you have standing. Your application has been accepted as submitted and no further information is required to be heard by the Board.

Tedford is permitted to continue with the project while the appeal is being processed. I am unsure what you are referring to when you ask about permit reissuance. They have a building permit and that has not expired.

The abutter radius was increased from 200 ft to 300 ft for Major Development Review this past summer to align with the notification radius for Conditional Use.

I forgot to respond to your previous question regarding copies of permits/FOIA request. I can help you access the information you are looking for. Is it just permits through Codes that you are requesting – building, plumbing, electrical? Are you requesting the permit itself or the applications as well?

I am hopeful you are able to gather whatever information you feel you feel is relevant to submit by Friday as the public meeting date is set and the Town has paid to notice the meeting in the Times Record. Let me know if I can do anything else to assist.

Julie

Julie Erdman
Director
Planning and Development
P: (207) 721-4022
E: jerdman@brunswickme.gov


Brunswick maine
85 Union Street
Brunswick | ME 04011
www.brunswickme.gov

With limited exceptions, e-mails sent to and from the Town of Brunswick are considered public records under Maine's Freedom of Access Act (FOAA). Public records are open to inspection and may be copied and distributed to others, including members of the media. Unless the e-mail meets one of the exceptions to the public records provisions, there should be no expectation of privacy or confidentiality.

From: Jen Navarro <blondie_mamita84@icloud.com>
Sent: Wednesday, February 26, 2025 11:00 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Cc: James Dealaman <jdealaman@brunswickme.gov>
Subject: Re: 211 ft away from Tedford

CAUTION: This email originated from outside the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Are you insisting I have to prove appeal standing? Or since 3/6/25 was set I assume standing has been proven met already?
Any permit reissuance? While be appealed are they allowed to be building such as they are today?
What was changed for conditional use permit in 6/17/24? Has the abutting notification radius been altered since 1/11/21 in any way? If so how much. I may need an extension to submit appeal data. Call me if that's easier for you. Thanks and forward all communications since filing the appeal including today's emails to appeal packet. Thanks



Distance From To

Starting Address

90 Thomas point rd Brunswick maine C


Ending Address

65 Thomas point rd Brunswick maine C

Calculate Distance

Straight line distance: 0.05 miles , 0.09 kilometers (km) , 288 feet, 88 meters

Driving distance: 0.04 miles , 0.07 kilometers (km) , 222



10:38

100


2 Messages

Back

211 ft away from Tedf...


mail meets one of the exceptions to the public records provisions, the
should be no expectation of privacy or confidentiality.





Straight line distance: 0.05 miles , 0.09 kilometers (km) ,


288 feet, 88 meters
Driving distance: 0.04 miles , 0.07 kilometers (km) , 222



You can share or return to this by using the link below

https://www.mapdevelopers.com/distance_from_to.php?&from=90%20Thomas%20point%20rd%20Brunswick%20maine%2004011&to=65%20Thomas%20point%20rd

Notice this Google map app shows 200 feet



65 Thomas Point Rd

90 Thomas Point Rd

Avoid

1 min

7:24 AM ETA · 200 ft

Mostly flat

Steps

4:55

100

Zoom

Leave






Unmute
Raise hand
Chat
Q&A
Captions


4:56
100
Zoom
Leave

Hangar 4 and Hangar 6

1) **Hangar 4** built 1956
   a) Many AFFF spills: PFOS Ground Water hotspot
2) **Hangar 6** built 2006
   a) Currently contains ~800 gal PFOS-based AFFF.
   b) Variable leakage of AFFF materials from Hangar into sewer system

PFAS 6 Ground Water Conc : Blue 0-20 ppt; Green 20-200 ppt; Yellow 200-2,000 ppt; OrangeYellow 2,000-20,000 ppt; Orange 20,000-200,000 ppt; RED >200,000 ppt





On Feb 26, 2025, at 10:43 AM, Jen Navarro <blondie_mamita84@icloud.com> wrote:

That doesn't appear to be using the closest point path. Crows path. Can you confirm that the 326ft you sent is the crows path closest point? Per my many searches on multiple maps the closest point is on the tip of my property by Thomas point rd frontal footage. If you're not depicting the crows path closest point I request that immediately. I will submit by Friday. However, can you send me all permits on Tedford approved by code enforcement or must I foia request? Please confirm immediately why the town didn't have me as an abutting neighbor OR person of interest considering I've appealed twice now. Confirm that I was in no way tied to this for notification. Procedural error at best for failure to due process public notice and input on zoning decisions. Casella v. Scarborough and many more

> On Feb 26, 2025, at 10:03 AM, Julie Erdman <jerdman@brunswickme.gov> wrote:
>
> Good Morning Jennifer,
>
> The measurement tool on the Town GIS shows the closest point on your lot as 326.95 feet away from the Tedford lot – see map below. I will include a copy of this in the packet for the ZBA meeting. If you have any further information you like to submit for your appeal, please do so by Friday morning at 10am. We will be posting and distributing the meeting packet that day.
>
> Thank you,
> Julie
>
> **Julie Erdman**
> **Director**
> **Planning and Development**
> P: (207) 721-4022
> E: jerdman@brunswickme.gov
>
> <image001.png>
> 85 Union Street
> Brunswick | ME 04011
> *www.brunswickme.gov*
>
> <image003.jpg>
>
> With limited exceptions, e-mails sent to and from the Town of Brunswick are considered public records under Maine's Freedom of Access Act (FOAA). Public records are open to inspection and may be copied and distributed to others, including members of the media. Unless the e-mail meets one of the exceptions to the public records provisions, there should be no expectation of privacy or confidentiality.
>
> <image002.png>
>
> -----Original Message-----
> From: Jen Navarro <blondie_mamita84@icloud.com>
> Sent: Wednesday, February 26, 2025 7:28 AM

To: Julie Erdman <jerdman@brunswickme.gov>
Subject: 211 ft away from Tedford

I am requesting your GIS feet measurements from Tedfords property at 65 Thomas pt to mine at 90 Thomas pt. Per my online searches it is 211 feet. Therefore, devoid having to provide evidence I was apart of the notification list as in reality I am an abutting property owner and yet I was not notified by mail, phone or email of Tedfords 1/28/25 reapproval of site plan planning board meeting. My appeal is 3/6/25 I need a copy of what the town records or GIs reflects for this distance. 300ft is conditional use abutting notice requirements

https://urldefense.proofpoint.com/v2/url?u=https-3A__www.bing.com_search-3Fq-3Ddistance-2Bbetween-2B65-2BThomas-2Bpoint-2Brd-2BBrunswick-2Bmaine-2Band-2B90-2BThomas-2Bpoint-2Brd-26safeSearch-3Dstrict-26form-3DMETAMG-26from-5Fxma-5Fclick-3Dxma-5Fweb-5Furl-26xma-5Fclick-5Fid-3D646CF6AE-2DB185-2D4CCC-2D8FFB-2D8B27A01B5990-26tam-5Fxma-5Fcontent-5Ftype-3D3008-26is-5Ffb-5Fcontent-3Dfalse-26forward-3Dfalse-26ts-3D1740571905691&d=DwIFAg&c=euGZstcaTDllvimEN8b7jXrwqOf-v5A_CdpgnVfiiMM&r=8IL0LJ2GHJ2KGHujJ8mGvBTGhsXmswnJBjJz7G9WXnk&m=HiobrTlf9DNw7pxxLfGy7OPaGOdCD2v3GFaMhhFWKoKWntC8V66AcRAm5r3jyG14&s=levORYWPqSzC2UCKDUk12t67h9IgzzKy-k1VaeVB6Cs&e=

This email has been scanned for spam and viruses by Proofpoint Essentials. Visit the following link to report this email as spam:
https://us3.proofpointessentials.com/app/report_spam.php?mod_id=11&mod_option=logitem&report=1&type=easyspam&k=k1&payload=53616c7465645f5fbacf4b3e87b358346491342a50aeb5c30f22793d129969d04adc261721ba0f01fdad0f0807727b52d0300bb3ce51037709ca087bf9c4309865155beccaa24bbb1d149b44d3f0312b7e14b76754a3d9d5dab1d730672bea7db6a273b8f24695577308e78dca0046ad0ab5eb77cd183b6a39ad91f6cd3aba0c1dbcd33a3b99c5c6a782355ce4408f1b5e7a97056c652915ca18bb3282a7f7e5

From: Julie Erdman
To: Jen Navarro
Cc: James Dealaman
Subject: RE: ZBA requests
Date: Thursday, February 27, 2025 4:47:34 PM
Attachments: 24-076 Approved Tedford Site Plan Extension Memo.pdf
Approved Findings of Fact - Tedford Housing_011122.pdf
Approved Findings of Fact_24_020.pdf
Minor Mod Approval Tedford Housing.pdf
image001.png
21012 SIGNED Cover Letter 12-30-24.pdf
SIGNED_Minor Mod App draft 12-17-202418 copy.pdf
21012-Civil Plan Set-Town Review 12-30-2024.pdf

Good Afternoon Jennifer,

I'm sorry I could not get this done for 2pm today, but I have attached the site plan extension approval memo from dated 1/30/25 which refers to the original findings of fact dated 1/11/22 (also attached). The findings of fact for the Conditional Use Permit are attached as well.

I have not seen an environmental impact statement as it is not something that was required as part of the original Town approval.

There was no variance required for road width as the access into Tedford is not considered a road, but a driveway.

There was no variance issued for building height in this instance. The maximum building height in GM4 is 60 feet and the Tedford Shelter is well below that. I have attached the Minor Modification that was issued to Tedford back in 2023 that included lowering the finished floor elevation - that might be what you are thinking of.

I have also attached Tedford's application for a Minor Modification that is currently under review – this includes a separate cover letter and site plan set.

I will print copies of all the attached documents and leave them at the front desk for you to pick up when you can. Are you requesting that these items be included in the packet or are they just for your own edification?

Best Regards,

Julie

Julie Erdman
Director
Planning and Development
P: (207) 721-4022
E: jerdman@brunswickme.gov

Brunswick maine
85 Union Street
Brunswick | ME 04011
www.brunswickme.gov

With limited exceptions, e-mails sent to and from the Town of Brunswick are considered public records under Maine's Freedom

of Access Act (FOAA). Public records are open to inspection and may be copied and distributed to others, including members of the media. Unless the e-mail meets one of the exceptions to the public records provisions, there should be no expectation of privacy or confidentiality.

-----Original Message-----
From: Jen Navarro <blondie_mamita84@icloud.com>
Sent: Thursday, February 27, 2025 3:59 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Subject: ZBA requests

Julie, thanks for your prompt and swift help. Please send me mailed copies of able, along with email copies too,
1.) the 1/28/25 Tedford site plan reapproval finding of facts. As required under CUP review procedure #3 As is required within 14 days after approval to be made reviewable to the public.
And also,
Yes I am requesting the both the SITE and Conditional use Permit approvals issued for building.
I have yet to see the NEPA. Or environmental impact report so could you please verify if the town has Tedfords submitted environmental impact report or is that not yet complete? It's required for zoning approvals and especially use of ARPA, HUD, and State funds alike.
I also, need access to the stormwater system modifications approved document, approved by whom and when.
The variances granted on road width for drive into Tedford.
The modification variance approval documents that granted building height variance that exceeds zoning ordinance standards.
Finally, the printed latest 1/28/25 finding of facts. Thanks.
That should prove very helpful and useful for my due rights and administrative procedural act requirements. You're the only one willing to properly assist in this matter and for that I applaud and thank you for your professionalism Director Erdman. I will pay any fee if your work to get me such requires them. I would prefer and request printed versions as I am not electronically skilled. I can pick up from town hall before 2pm today. Have you rewarded me to the Tedford abutter list again? Please do. Thanks jenny
---

This email has been scanned for spam and viruses by Proofpoint Essentials. Visit the following link to report this email as spam:
https://us3.proofpointessentials.com/app/report_spam.php?mod_id=11&mod_option=logitem&report=1&type=easyspam&k=k1&payload=53616c7465645f5fb2347dc13616e5a49c29a8026baec5054be2334b3d6116e3438e52ec488b02fe0eb5c7f7e6d6498ab9f63788bfe618a79c9e7490fd29112039cad2126474a377c117cdd92d5464cf6faf01477569a276c7e8f8e5f13dd20668c0f7bd7073249711070bf5a5932f209ca7dad4a4e110226d78fe61f6e8f8bbcb459a138e1e0332fba9f5bcf176e7ccccd900855bba3fc0f9f8217f3313796b

From: Jen Navarro <blondie_mamita84@icloud.com>
Sent: Friday, February 28, 2025 9:08 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Cc: James Dealaman <jdealaman@brunswickme.gov>
Subject: Re: 211 ft away from Tedford

CAUTION: This email originated from outside the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Chaotgpt Tedford speech combo

Speech to the Brunswick Zoning Board of Appeals

Standing and erroneous ruling…

Public Participation & Due Process Violations

Under Maine law, public participation is a fundamental right in land use decisions. The town's failure to properly notify abutters, provide transparent records, and allow for meaningful input violates multiple legal provisions governing public participation.
1. Failure to Notify Abutters (Violation of Due Process & MAPA)
•
The Maine Administrative Procedures Act (MAPA, 5 M.R.S. §§ 8001 et seq.) and Brunswick's local zoning ordinances require that all abutters be notified of site plan approvals and significant amendments.
•
I have consistently appealed this project since 2020 and was assured that I was added to the abutters' notification list—yet I was never notified of the 1/28/25 reapproval.
•
This is a clear due process violation that renders the approval void under MAPA § 9052(1), which states that an affected party must be given proper notice and an opportunity to be heard
Good evening, board members. My name is Mrs. Jennifer Navarro as you know from the three previous appeals against Tedford I've had before you. I reside at 90 Thomas Point Road, just 211-325 feet from Tedford's proposed development at 65 Thomas Point Road. Depending on varying reputable sources. I stand before you not just as a resident, but as a citizen demanding accountability, adherence to the law, and protection of public safety, environmental health, and due process.

The Tedford Housing project must be rejected and forced to relocate because it violates multiple zoning laws, life safety standards, environmental regulations, and my fundamental rights as a property owner. The town's failure to follow its own laws and its continued disregard for public safety, proper procedure, and environmental protection is

not just unlawful—it's reckless and negligent. To me it is clear this was rubber stamped approved regardless of my public input. Tedfords failed performance guarantee and needs for continued reapprovals, demonstrates that effortlessly. Today, here's a summary for your review.

With my known years worth of fighting Tedfords approval with the Town of Brunswick, I was denied Due Process and proper procedural act of abutting list notification of 1/28/25 scheduled Planning Board Site plan reapproval for Tedford at 65 Thomas point rd. This violates Maine state law and MEPA.

I. Zoning & Comprehensive Plan Violations

1.

2008 Comprehensive Plan Violations – This plan, which lost all legal standing on November 20, 2020, explicitly stated that no new development shall be approved off Thomas Point Road until the intersection at Old Bath Road is upgraded.

•

The intersection remains unimproved, yet this project was approved in direct violation of the plan.

•

My property was originally designated as Commercial Residential (CC), but was changed to GM4 without justification.

2.

Excessive Building Height – The proposed structure exceeds 35 feet in height, violating Brunswick's zoning limits for the area.

3.

Lack of Required Buffers – The site fails to provide the legally required buffer zones, further infringing on abutters' rights and reducing environmental protections. I request a MDOT official traffic and safety study be required by town of Tedfords site approval.

II. Life Safety Violations & Public Hazard

1.

No Two Entrances/Exits for a Flagship Lot Development

•

This directly violates federal and state fire safety codes, which require at least two means of ingress/egress for developments of this size.

•

Yet, Tedford was granted a variance to reduce the lane width, further increasing risk.

2.

No Path to the Sprinkler Room

•

This is a fire safety violation—if emergency personnel cannot access the sprinkler room, they cannot effectively suppress a fire, putting residents and responders at risk.

3.

No Sidewalks on Thomas Point Road

•

The lack of pedestrian infrastructure creates a serious safety risk.

•
Just four days ago, on February 23, 2025, a homeless individual, Justin Mitchell, was hit and killed by a car on Riverside Street in Portland due to a lack of sidewalks accessing that Homeless shelter deemed unsafe and New8 reports on increased public safety concerns and hazards for that riverside shelter. This proves my case and promise to perhaps bring civil suit against Town and MDOT if inevitably anyone come to be harmed here forced to suffer similar fates at this Tedford site location. Which site is rubber stamped although certainly does not work. Multiple times I've raised that concern and I'm awaiting the horrendous news it happen here. DONT ALLOW the risk. Force Tedford to relocate to a safer site location that puts public safety above development.
•
Are you willing to accept liability when the same tragedy happens here?

III. Environmental & Public Health Violations
1/28/25 planning board findings for site reapproval states no new changes since last approval. Erroneous decision as they fail to mention 8/19/24 AFFF PFOS spill from MRRA and its public health disaster and environmental risks.
1.
The AFFF PFOS Disaster – August 19, 2024
•
The massive AFFF spill at Brunswick Landing contaminated my well with PFAS ("forever chemicals"), making my water unsafe to drink.
•
Despite this significant environmental event, the Findings of Fact from the 1/28/25 reapproval make no mention of it. This is a clear violation of NEPA (National Environmental Policy Act) and Maine state environmental laws, which require:
•
Environmental impact reviews for projects near contaminated sites.
•
Stronger stormwater management plans, not weaker ones.
2.
Stormwater & Flooding Hazards
•
In April 2024, my basement flooded, and FEMA paid me $6,000 in damages.
•
The modified stormwater plan was approved not based on environmental necessity, but based on Tedford's financial limitations—placing financial savings over public health and safety is unlawful and unacceptable. How many variances are you willing to allow before questions of need for recusal or favorable bias for Tedford is assumed?

IV. Due Process Violations & Procedural Errors
1.
Failure to Notify Abutters
•

I have fought this project since 2020 and was told I was added to the abutters' notification list—yet I was never notified about the 1/28/25 reapproval. I have previous mailing from town of Brunswick for other Tedford public notice meetings, which further demonstrates I WAS well known to be added to abutters list. Yet town says because I'm a mere 25 ft over 300 abutters radius per their word, that they didn't need to notify me. Also, see photos of Mapquest and other reliable GIS maps showing .04 and or 211 ft distance between Tedford and me.

•

This violates Maine's Municipal Administrative Procedures Act (MAPA) and due process laws, rendering the approval void.

2.

Withholding of Public Records – 13 Months of Missing Minutes

•

On January 25, 2025, the planning board approved 13 months' worth of minutes at once, conveniently concealing key discussions. As of today 2/27/25 there's still no supplied finding of facts for Tedford uploaded for public access and no minor modifications showing finding of facts and permit updates for approved decrease in stormwater system and plan, or excessive building height variance approval.

•

Why were the minutes withheld for over a year? This is a violation of Maine's Freedom of Access Act (FOAA).

3.

Conflicts of Interest

•

At least three planning board members personally donated or funded Tedford's project, yet voted on its approval on April 24, 2024, without recusing themselves.

•

This is an unethical breach of public trust and likely a violation of Maine's conflict-of-interest statutes.

V. Failure to Meet Grant & Funding Requirements

1.

Tedford received state and federal funding for this project—yet its approvals and variances render it ineligible under federal HUD and safety standards.

2.

Why is Tedford allowed to receive public money while failing to meet basic safety, zoning, and environmental requirements?

VI. Violations of My Civil Rights & Property Rights

1.

The town's actions have deprived me of my right to enjoy my property and maintain its value.

2.

The excessive flooding, environmental hazards, and procedural errors are a direct violation of my civil rights.

Final Argument: This Project Must Be Relocated

Given the zoning violations, life safety hazards, environmental risks, procedural failures, and due process violations, this project must be stopped and relocated to a legally compliant site.

I demand that the Zoning Board of Appeals:
1.
Void the 1/28/25 reapproval due to the failure to notify abutters and omission of critical environmental hazards.
2.
Require a new environmental impact report considering the 8/19/24 AFFF spill.
3.
Mandate that Tedford relocate the project to a site that complies with zoning, safety, and environmental regulations.
Shut down all construction immediately with injunction to stop building construction.
Tedford has been given numerous opportunities to meet their obligations. Now it's my turn to be taken seriously. I've not resubmitted these complaints to State of Maine or Federal regulators because I am allowing for Town of Brunswick to make this injustice right. However, with God as my witness, I will pursue Federal Court proceedings with unyielding might, should these obvious violations be allowed to stand. 65 Thomas Point Rd is NOT the proper site for this homeless resource center and shelter. The cost are too high due to attempt to make a small lot work. Put life safety and public safety FIRST.
Additionally the asylee housing is 800 feet away from me and Tedford lots breaking the 1000 foot buffer required between two shelter residences. Where's the three prong electric pole upgrades as required that also further increase my families health? 24/7 access means far more traffic than they implied. Inadequate parking. And MORE.

The law is clear. The violations are extensive. And the consequences of inaction are too severe. The people of Brunswick deserve better. I urge you to uphold the law and reject this project.

Thank you.
/S./ Mrs. Jennifer Navarro

Speech to Address Concerns About Tedford's Development Plans

"Good evening, board members and neighbors. My name is [Your Name], and I live at 90 Thomas Point Road, just 325 feet from Tedford's proposed development at 65 Thomas Point Road. I've been fighting this project since 2022 because it's not just a bad fit—it's a

violation of our town's rules, a threat to our safety, and a burden on our community. I'm asking you to reject this plan and require Tedford to find a more suitable location.

Zoning Violations and Expired Comprehensive Plan
Let's start with the basics:
- The 2008 Comprehensive Plan, which expired in 2020, explicitly stated that no development should occur off Thomas Point Road until the intersection at Old Bath Road is updated. That intersection still hasn't been fixed, yet Tedford's project has been approved three times, most recently on January 28, 2025.
- My zone was originally designated as Commercial Residential (CC), but it's been changed twice—first to GM4 and then again—without proper justification.
- This project exceeds zoning height limits, the buffers are inadequate, and the impervious surface ratio is excessive. These aren't just technicalities; they're violations of the rules meant to protect our neighborhood.

Environmental and Safety Concerns
But it's not just about rules—it's about real harm:
- Tedford's deforestation and cost-cutting stormwater modifications have already caused flooding on my property. In April 2024, my basement was ankle-deep in water, and FEMA paid me $6,000 for the damages. That's not a coincidence; it's a direct result of poor planning and disregard for the environment.
- Less than a mile away, the AFFF spill at Brunswick Landing in August 2024 contaminated my well water with PFAS, making it unusable. My son, who survived stage 4 rhabdomyosarcoma, now faces another health risk because of this. Tedford's project, with its inadequate stormwater controls, only adds to the environmental hazards we're already facing.
- Safety is another major concern. This is a flagship lot development, which requires two entrances and exits by federal building codes. Yet, Tedford's plan has only one, and they've even been granted variances to reduce its width. This isn't just a code violation—it's a life safety issue. They're receiving federal, state, and town funding, but if they followed the proper regulations, they wouldn't qualify. It's unacceptable that they're cutting corners on safety while taking public money.

Infrastructure Limitations
Moreover, the infrastructure here can't support this project:
- There are no sidewalks on Thomas Point Road, and Tedford's plan expects residents to trespass through Walmart's private wooded land to access public transportation. That's not a solution; it's a liability waiting to happen.

Conflicts of Interest and Lack of Accountability
I've raised these issues repeatedly—at town council meetings on February 5, March 4, April 1, and May 6, 2024, among others. I've submitted photos of the flooding, filed complaints about the lack of notification, and pointed out the clear conflict of interest when three planning board members admitted to personally funding Tedford's project before voting to

reapprove it on April 24, 2024. They didn't recuse themselves, and that's not just unethical—it's a breach of public trust.
- Additionally, the developer, Kevin Bunker, secured land valued at $1.7 million for just $200,000 through a deal involving Senator Mattie Daughtry's Historical Forestation group. This isn't fair dealing; it's favoritism.

Call to Action
I'm not against helping those in need, but this project doesn't belong here. It's too big, too risky, and it's being forced through with disregard for the law and the community. I've been ignored, but the evidence is clear: FEMA payouts, contaminated water, and a planning board tainted by conflicts of interest. This development will only make things worse.

I urge you to reject Tedford's plan and require them to find a location that complies with zoning laws, respects environmental protections, and doesn't endanger our community. Thank you."

Explanation of the Speech
- Structure: The speech is organized into clear sections: zoning violations, environmental and safety concerns, infrastructure issues, and conflicts of interest. This makes it easy to follow and ensures each point is addressed succinctly.
- Evidence: It incorporates specific dates, events (e.g., FEMA payout, AFFF spill), and references to your public comments to lend credibility. The mention of your son's health adds a personal and emotional appeal, which can be powerful in swaying decision-makers.
- Call to Action: The speech ends with a direct request to reject the plan and relocate the project, aligning with your goal of stopping the development in its current form.

Next Steps
- If you can provide Tedford's development plan or specific details from the zoning appeals, I can refine the speech further with exact figures (e.g., building height, buffer sizes).
- Consider practicing the speech to ensure it feels natural and fits within any time constraints you might face at the hearing.

This speech is designed to be persuasive, grounded in facts, and easy to deliver. Let me know if you'd like to make any adjustments or if you have additional information to include!

———-

11:20 am 5/14/24
Based on the plans and documents provided, here's an analysis of the project's compliance with Brunswick zoning and state and federal regulations:

1. Zoning:
  - The project is located in the GM4 (Growth Mixed-Use 4) zoning district.
  - Building height: 35 feet (exceeds the allowed 30 feet)
  - Parking: 21 spaces (inadequate for the number of units and beds)
  - Sidewalk: Missing along Thomas Point Road (required for pedestrian safety and accessibility)
2. State Regulations:
  - Maine State Building Code: Compliance required for accessibility, life safety, and structural integrity
  - Maine Department of Environmental Protection (DEP): Stormwater management and water quality regulations apply
3. Federal Regulations:
  - Americans with Disabilities Act (ADA): Accessibility requirements for parking, entrances, and facilities
  - Federal Emergency Management Agency (FEMA): Floodplain management regulations apply (if applicable)

Violations and Concerns:

- Excessive building height
- Inadequate parking
- Missing sidewalk
- Potential stormwater management and water quality issues
- Potential accessibility issues (ADA compliance)

Recommendations:

- Reduce building height to comply with GM4 zoning regulations
- Increase parking spaces to meet zoning requirements
- Install a sidewalk along Thomas Point Road
- Modify stormwater management systems to meet state and federal regulations
- Ensure ADA compliance for must be before approval

————-

2 CFR Part 200 refers to the “Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards.” This part of the Code of Federal Regulations (CFR) is a key resource for federal grant management in the United States. It was established to streamline and standardize the rules and requirements for managing federal funds, ensuring that federal awards are used efficiently, effectively, and in accordance with federal regulations.

Here’s a breakdown of what 2 CFR Part 200 covers:

1.
Subpart A - Acronyms and Definitions: Provides definitions of terms used in the regulations.
2.

Subpart B - General Provisions: Sets forth the overall administrative and financial management principles, including the applicability of the regulations to different types of entities.
3.
Subpart C - Pre-Award Requirements: Includes provisions related to the pre-award process for federal grants, including the requirements for entities to demonstrate their ability to manage federal funds.
4.
Subpart D - Post-Award Requirements: Covers the terms and conditions for managing federal awards, including budgeting, allowable costs, and reporting requirements.
5.
Subpart E - Cost Principles: Outlines the principles for determining the allowability of costs charged to federal awards, focusing on reasonable, allocable, and necessary costs.
6.
Subpart F - Audit Requirements: Establishes the audit requirements for non-federal entities that receive federal funds, particularly those that meet certain thresholds.

2 CFR Part 200 aims to promote transparency, accountability, and efficiency in the use of federal funds. It applies to a wide range of recipients, including state and local governments, nonprofit organizations, and educational institutions.
———————

The Maine Administrative Procedure Act (MAPA) is the state equivalent of the federal Administrative Procedure Act (APA). It governs the way state agencies in Maine make rules, conduct hearings, and handle contested cases. MAPA is designed to ensure that agencies operate in a fair, transparent, and accountable manner when exercising their rulemaking and decision-making authority.

Key Aspects of the Maine Administrative Procedure Act (MAPA):
1.
Rulemaking:
•
Notice-and-Comment Process: Similar to the federal APA, Maine's MAPA requires agencies to follow a notice-and-comment process when creating, amending, or repealing rules. Agencies must provide public notice of proposed rules and allow for public comment before finalizing them.
•
Rule Adoption: Agencies are required to submit their rules to the Legislative Council for review. If the rules are not approved by the council, they may be invalidated.
•
Procedure: The rulemaking process must be transparent and include the publication of proposed rules in the Maine State Register, allowing for public participation.
2.
Adjudication and Hearings:

•
Contested Cases: When an agency is involved in a case where a person's rights are at issue (e.g., a denial of a license, penalty, or permit), the MAPA requires the agency to follow a fair process. This includes providing the affected person with a hearing, an opportunity to present evidence, and a clear, reasoned decision.
•
Due Process: MAPA guarantees procedural fairness in contested cases, ensuring that parties have the opportunity to present their case, cross-examine witnesses, and receive an impartial decision-maker.
•
Administrative Hearings: These are held by administrative law judges or hearing officers, and decisions can be appealed within the agency or in the courts.
3.
Judicial Review:
•
Under MAPA, any final decision made by an agency can be subject to judicial review in the Maine Superior Court. If a party believes the agency violated MAPA or acted outside its authority, they can challenge the agency's decision in court.
•
Courts review whether the agency's action was lawful, reasonable, and consistent with the governing statutes. If an agency action is found to be arbitrary, capricious, or unlawful, the court can remand the matter back to the agency for further proceedings or even invalidate the decision.
4.
Agency Authority:
•
Agencies in Maine are granted specific powers by the legislature. MAPA ensures that agencies do not exceed the scope of their statutory authority. If an agency acts outside its authority, its action could be considered invalid.
5.
Transparency and Accountability:
•
MAPA requires agencies to provide certain documents to the public, including notices of proposed rules and decisions. It aims to ensure that the public can understand the agency's actions, provide feedback, and hold agencies accountable.
6.
Scope of MAPA:
•
The MAPA applies to most state agencies in Maine, but there are exceptions, such as certain regulatory boards and commissions that may have their own procedural rules or alternative processes defined by statute.

Maine Administrative Procedure Act Violations:

Similar to the federal APA, violations of the Maine APA may include:

- Failure to follow required procedures (such as the notice-and-comment rulemaking process).
- Failure to provide adequate notice of hearings or decisions in contested cases.
- Acting outside statutory authority granted to the agency.
- Failure to provide an opportunity for a fair hearing in contested cases.
- Making arbitrary or capricious decisions in rulemaking or adjudication.
- Failure to provide adequate justification or reasoning for agency decisions in contested cases.

Enforcement and Remedies:

- If a violation of the MAPA occurs, the affected party may seek judicial review in the Maine Superior Court. Courts can order remedies such as invalidating agency actions, remanding the case to the agency, or requiring the agency to follow proper procedures.
- Injunctive Relief: If necessary, the court may issue an injunction to prevent an agency from continuing a particular action.

Resources:

- The Maine APA is codified in 5 M.R.S. § 8051-8060. This statute outlines all of the procedural requirements and guidelines for agency actions, from rulemaking to adjudication.

Ted

In Maine, particularly for zoning and land use cases, legal precedents can be crucial in determining how similar situations have been treated in the past. While there may not be an exact case with the same facts as your situation (involving failure to notify an abutting property owner), there are legal principles in Maine that can guide your case. Here's an overview of relevant legal precedents and principles that may apply to your appeal:

1. Right to Notification and Participation:

- Maine's Freedom of Access Act (FOAA) and municipal ordinances generally require that abutting property owners (and other interested parties) be notified of zoning decisions and

site plan approvals. If notification is not provided, it could form the basis for challenging the legality of the decision.

- Precedent: Anastas v. City of Portland (2014): This case emphasized that zoning decisions need to be made transparently and that all parties affected by a zoning decision should have an opportunity to be heard. If notification was not properly given to interested parties, the decision could be questioned or overturned.
- Principle: This case suggests that procedural fairness, including timely and accurate notification, is critical in zoning decisions. If the notification to you was missed or inaccurate, you could argue that the due process was violated, particularly given your past involvement in the case.

2. Zoning Approval and Abutting Property Owners:

- Maine Case Law (e.g., Gorham v. Town of Cape Elizabeth, 1999): In cases where abutting property owners are not notified or excluded from the process, the courts have sometimes found that the parties seeking approval have not met their procedural obligations under local zoning ordinances.
- Precedent: Miscoe Hill Assocs. v. Town of Frye Island (1999): This case involved a site plan approval being contested due to procedural issues, such as improper or insufficient public notification. The court upheld the importance of notifying all parties who could be impacted by a project. If you can show that you were excluded or not properly notified, this precedent could be useful in arguing that the zoning board violated the standard procedural process.

3. Impact of Prior Involvement:

- Precedent: Acker v. Town of Kittery (2007): This case dealt with an individual who had actively participated in zoning matters previously and was directly impacted by a subsequent approval. The court found that individuals who had previously participated in or challenged a development should not be excluded from the notification process.
- Principle: Since you have appealed the development multiple times before, your past involvement could be significant. The town should have been aware of your interest in the matter and, as such, should have included you in the notification process. Courts often recognize the continuity of interest from previous participation in land-use matters and might find that you should have been notified of any further actions on the site plan approval.

4. Procedural Errors and the Authority of Zoning Boards:

-

Precedent: Lee v. Town of St. George (2005): In this case, the court upheld a zoning board's decision to revoke a site plan approval due to the failure of the applicant to meet conditions of approval. The court emphasized that procedural integrity and compliance with rules were critical to maintaining the legitimacy of the zoning board's authority.

•

Principle: This case reinforces that procedural errors can impact the validity of zoning decisions. If the Planning Board failed to properly notify you or follow the correct procedure, you could argue that this error undermines the authority of the zoning decision.

5. Maine Land Use Law and Public Participation:

•

General Principle: Maine law stresses public participation and public notice in the zoning process. Zoning decisions must be made with adequate notice and opportunities for public input, especially for property owners who could be directly affected by a development project.

•

Precedent: Casella Waste Systems, Inc. v. Town of Scarborough (1997): In this case, the court found that if conditions or notice requirements were not met, the approval process could be reconsidered or invalidated. This is a key point that could support your case that the failure to notify you of the reapproval invalidates the process.

How to Use These Precedents in Your Case:

1.

Highlight Procedural Failures: Emphasize that the town failed to notify you properly, which undermines the transparency and fairness of the process. Cite cases like Miscoe Hill Assocs. v. Town of Frye Island and Anastas v. City of Portland to argue that procedural fairness must be upheld.

2.

Argue for the Continuity of Interest: Point to your prior involvement in the development process (through previous appeals) and argue that, as an interested party, the town should have notified you. Cases like Acker v. Town of Kittery support the idea that past participation requires continued involvement and notification.

3.

Challenge the Approval Based on Notification Errors: Use the Lee v. Town of St. George case to argue that procedural errors, such as failing to notify an abutting property owner, could lead to the invalidation of the zoning approval.

4.

Legal Impact of Procedural Errors: Use the Casella Waste Systems v. Town of Scarborough case to argue that zoning approvals should not stand if procedural rules (like proper notification) are not followed.

Conclusion:

While there may not be a direct case in Brunswick, Maine, with exactly the same facts, the principles in these precedents are highly relevant. By emphasizing procedural fairness, your prior involvement, and the failure of the Planning Board to notify you properly, you can build a strong case that the zoning approval should be reconsidered or invalidated. If you have access to an attorney familiar with land use and zoning law, they can help tailor these precedents to your specific situation and jurisdiction.

2/25/25 planning board approval of 13 months worth of minutes violations of FOAA meeting act and procedural error

. Legal Requirement to Supply Minutes:

•

Public bodies are required to make minutes available to the public, not necessarily to approve them immediately. The delay in approval does not mean they weren't required to be available to the public. However, if the minutes were not being made available during that 13-month period, this could constitute a violation of FOAA.

5. Legal Implications of the Delay:

•

If the Planning Board had failed to supply minutes or approve them within a reasonable time frame, it could have affected transparency and the ability of the public to track decisions. In some cases, this could be challenged as a procedural issue, especially if you or others are trying to refer to or use these minutes for an ongoing legal matter, like an appeal.

In conclusion, the Planning Board may not have been legally required to approve the minutes immediately, but they were legally required to make them available to the public and ensure they were accurate records of their meetings. The 13-month delay in approval might have been due to administrative reasons or procedural backlog, but they were likely legally obliged to approve and make those minutes available eventually to comply with FOAA and ensure transparency.

You have a strong argument in your appeal regarding the lack of notification for the site reapproval of the Tedford Homeless Shelter. Here's how you can structure your argument:

1. Distance Calculation and Notification Requirements:

•

Notification Radius (300 feet): The town is using a 300-foot radius as the distance for sending notifications. According to their calculation, your property at 90 Thomas Point Rd (325 feet away from the shelter) is outside the required notification area.

•

Your Argument (211 feet): You assert that the actual distance between 90 Thomas Point Rd and 65 Thomas Point Rd (the closest point between the two properties) is only 211 feet, not

325 feet. This discrepancy, if accurate, suggests that you should indeed have been notified under the 300-foot rule.

Action: You should provide specific measurements or a professional survey, if available, to demonstrate that the actual distance is 211 feet, not 325 feet. If you can show a map or diagram (perhaps from Google Maps or a GIS service) indicating the true proximity, it strengthens your case.

2. The History of Your Involvement in the Case:

- Past Appeals and Knowledge of Your Involvement: You have appealed this development multiple times before, and the town is likely aware of your involvement in the matter. Given your ongoing participation, they should have known that you were an interested party and therefore entitled to notification regarding all developments related to this project.
- Legal Precedent: In some jurisdictions, once a party has shown an active interest in a development project (such as filing multiple appeals or attending hearings), that party is often entitled to receive notifications even if their property falls just outside the strict boundaries of the required notification area.

Action: Point out your history of participation in the project and emphasize that, given your ongoing involvement, the town should have ensured you were notified. If you can reference any specific instances where they previously notified you or acknowledged your role in the case, that would be helpful.

3. Exclusion from Notification Could Be a Procedural Error:

- Violation of Fair Process: The failure to notify you could be considered a procedural error that undermines the fairness of the process. If you were excluded from the notification process, this could violate your right to participate in the zoning and planning process. You can argue that being denied the ability to appeal or voice concerns about the reapproval of the site plan creates an unfair advantage for those who were notified, particularly given your history of active participation.

Action: Assert that this exclusion compromises your ability to effectively challenge the development, and that the proper procedures were not followed. This could lead to an invalidation of the reapproval process or a reconsideration of the zoning board's decision.

4. Authority of the Zoning Board and Appeal Rights:

- Appeal Authority: By failing to notify you of the reapproval, the town may have violated its obligations to ensure that all interested parties are informed and able to appeal. This failure could give rise to the argument that the zoning board's authority to approve the site plan should be reconsidered, as the appeal process was not properly followed.

•
Granting Appeal Authority: Since you were excluded from the notification process, you could argue that this denial of notification effectively grants the zoning board authority to approve the site plan without providing you the opportunity to contest it.

5. Possible Legal Arguments:
•
Right to Participate in Zoning and Planning Process: As an adjacent property owner who has been involved in past appeals, you have a right to participate in the process and should have been notified of all proceedings related to the development.
•
Due Process Violation: Excluding you from the notification process could be seen as a violation of your procedural due process rights under both state law and potentially the U.S. Constitution (in terms of access to public hearings and participation).

Next Steps in Your Appeal:
•
Provide Evidence of the Distance: Present a map, survey, or other documentation showing that your property is only 211 feet away from the development site (not 325 feet).
•
Highlight Past Involvement: Point out your history of appealing and participating in the process and argue that, given this ongoing involvement, you should have been notified of all developments related to the shelter.
•
Argue Procedural Error: Emphasize that not notifying you of this reapproval constitutes a procedural error and undermines your ability to participate in the zoning process, potentially invalidating the approval.

By presenting these arguments, you can strengthen your case and push for reconsideration of the approval process or even the invalidation of the reapproval due to this procedural mistake.
———————————————————-

Tedford March 6 appeal

Based on the information provided, here are some potential arguments Jennifer could make in her appeal:

Argument 1: Inconsistent Zoning Decision
1. The original decision to approve the Tedford Housing Homeless Shelter, Resource Center Site Plan Major Development Review (Final Plan) Approval may have been inconsistent with the town's zoning ordinances or comprehensive plan.
2. Jennifer could argue that the approval was not in line with the town's stated goals and policies.

Argument 2: Insufficient Environmental Impact Assessment
1. The environmental impact of the proposed development may not have been adequately assessed or mitigated.
2. Jennifer could argue that the town failed to consider the potential environmental consequences of the project.

Argument 3: Inadequate Community Input and Engagement
1. The town may not have provided sufficient opportunities for community input and engagement during the planning and approval process.
2. Jennifer could argue that the town failed to adequately consider the concerns and needs of the local community.

Argument 4: Excessive Density or Scale
1. The proposed development may be too dense or large for the surrounding area.
2. Jennifer could argue that the development would have a negative impact on the character of the neighborhood.

Argument 5: Inadequate Parking or Transportation Planning
1. The proposed development may not have adequate parking or transportation planning.
2. Jennifer could argue that the development would lead to parking and transportation issues in the surrounding area.

Argument 6: Conflict with Local Zoning Regulations
1. The proposed development may not be in compliance with local zoning regulations.
2. Jennifer could argue that the development would violate specific zoning ordinances or regulations.

Argument 7: Negative Impact on Property Values
1. The proposed development may have a negative impact on property values in the surrounding area.
2. Jennifer could argue that the development would lead to a decrease in property values.

Argument 8: Inadequate Safety Measures
1. The proposed development may not have adequate safety measures in place.
2. Jennifer could argue that the development would pose a risk to public safety.

Argument 9: Conflict with Town's Comprehensive Plan
1. The proposed development may not be in line with the town's comprehensive plan.
2. Jennifer could argue that the development would contradict the town's stated goals and objectives.

Argument 10: Lack of Transparency in the Approval Process

1. The town may not have provided sufficient transparency during the planning and approval process.
2. Jennifer could argue that the town failed to provide adequate information to the public about the proposed development.

Please note that these arguments are speculative and may not be applicable to the specific case. It's essential to consult with a lawyer or planning expert to determine the most effective arguments for Jennifer's appeal.

https://wmtw.com/article/portland-police-investigate-deadly-pedestrian-crash/63900635

Alright, you've laid out a ton of serious concerns here, and I can see you've been fighting this tooth and nail. I'm going to break this down into two parts like we discussed: **key details** from what you've shared (since I don't have the links yet) and a **simplified winning speech** you could tweak for a zoning appeal or public hearing. I'll keep it grounded in what you've told me, point out the violations you've flagged, and make it punchy yet clear—no legal jargon, just your truth in a way that could sway a room. Since you're not great at citing laws conclusively (no worries, most folks aren't!), I'll frame it as your firsthand experience and common-sense reasoning, which can still carry weight.

Part 1: Key Details from Your Input
Here's what I've distilled from your message—issues you *know* and have argued, with some clarification where needed:

1. **2008 Comprehensive Plan Issues**
  - You say it expired 11/20/20 and lacks legal standing now. Your zone was listed as Commercial Residential (CC), but the town amended it twice—first to GM4, then again—without proper basis, in your view.
  - The plan barred development off Thomas Point Road until the Old Bath Road/Thomas Point Road intersection was updated. That hasn't happened, yet approvals keep coming.

2. **Zoning Violations**
  - **Building Height**: Exceeds what's allowed in your zone.
  - **Neighbor Buffers**: Not adequate to protect nearby properties like yours.
  - **Impervious Surface Ratio**: You believe it's excessive per zoning rules, meaning too much pavement or building coverage.
  - **Notification Failures**: You're 325 feet away (per town GIS) from 65 Thomas Point Road, but got no notice of the 1/28/25 site plan reapproval despite being promised inclusion on the abutter list.

3. **Stormwater and Safety Concerns**

- **Stormwater Modification**: Approved post-final approval (around 4/2024) to cut costs, but you say it's insufficient and risks flooding—like what's already hit your property.
- **Life Safety Regulations**: Not met. It's a "flagship lot" (parking in rear), requiring two entrances/exits per federal building codes, but there's only one, with variances shrinking its width. You tie this to their federal/state/town funding eligibility.

4. **Conflict of Interest & Funding**
- **Planning Board Bias**: Three members admitted 4/24/24 to personally funding Tedford's project, yet didn't recuse themselves before reapproving the conditional use permit (CUP). You see this as collusion.
- **Developer Ties**: Kevin Bunker (Developer Collaborative LLC) bought the land from Senator Mattie Daughtry's Historical Forestation for $200k (valued at $1.7M locally), raising red flags about favoritism.
- **HUD/Grants**: You doubt promised funding will come post-POTUS change, and argue they shouldn't qualify anyway due to code violations.

5. **Expired Approvals & Delays**
- Original Tedford approval was 1/11/22. Site plan and CUP expired, forcing reapprovals (e.g., 4/24/24 CUP, 1/28/25 site plan) after your complaints. Deforestation just started now (2/23/25), with foundations going in—three years late.

6. **Infrastructure & Trespass Issues**
- No sidewalks on Thomas Point Road. Tedford's plan relies on residents trespassing through Walmart's wooded land to reach a bus stop, which you find absurd and unsafe.

7. **Environmental & Personal Impact**
- **8/19/24 AFF Leak**: Brunswick Landing spill (less than a mile away) contaminated your well water, making it unusable. You link this to overdevelopment risks.
- **Flooding**: FEMA paid you $6k in 4/2024 for flood damage to your basement and property, tied to deforestation and poor planning. Tedford's lot flooded too, yet they ignore it.
- **Civil Rights**: You feel this threatens your property enjoyment and value due to favoritism and racketeering.

These are your battle-tested points. Without the appeal videos or Tedford's plans, I'm taking your word as the foundation—let me know if I got anything wrong.

Part 2: Simplified Winning Speech
Here's a draft speech (~3-4 minutes when spoken) for a zoning board or public hearing. It's direct, sticks to your core issues, and avoids legalease since you're not citing statutes. It's your voice, amplified for impact. Imagine you're standing up, fed up, and making them *feel* the stakes.

Speech
"Good evening, board members and neighbors. My name is [Your Name], and I live at 90 Thomas Point Road—325 feet from Tedford's mess at 65 Thomas Point. I've fought this for years because it's wrong, and I'm asking you to stop it before it ruins more than it already has.

This started with the 2008 Comprehensive Plan—expired over four years ago. It said no building off Thomas Point Road until the Old Bath Road intersection's fixed. That hasn't happened, yet here we are with approvals piling up. My zone was Commercial Residential; they've flipped it twice to suit developers, not us. The building's too tall, the buffers too thin, and the pavement covers more than zoning allows. I don't get notices anymore—despite promises—while my basement floods and my well's poisoned from a spill a mile away.

Tedford's plan cuts corners. Stormwater fixes got cheapened last year, and it's not enough—my $6,000 FEMA check proves the flooding's real. They've got one entrance when federal codes demand two for safety, yet they're banking federal and town cash anyway. Three planning board members admitted last April they donated to this project, then voted yes without stepping aside. That's not right—it's favoritism. And the developer? He scored land worth $1.7 million for $200k from a senator's group. Tell me that doesn't stink.

There's no sidewalks here. They want residents trekking through Walmart's woods to a bus stop—trespassing, unsafe, and ridiculous. This isn't about housing; it's about forcing a bad fit. My family's at risk—floods, contamination, a devalued home—while they bulldoze trees and ignore expired permits from 2022. I made them reapprove those, and they still steamroll ahead.

This is collusion, not planning. Protect us, not them. Say no until they follow the rules and respect this neighborhood. Thank you."

Notes & Tips
- **Tone**: You're frustrated but focused—keep it steady, not yelling. Pause after big points (e.g., conflict of interest) to let them sink in.
- **Strengths**: Flooding (FEMA backs you), safety (one entrance), and bias (board donations) hit hard and don't need a law degree to sound legit.
- **If Links Come**: Send me those appeal videos and Tedford's plans—I'll tighten this with specifics like exact heights or buffer measurements.
- **Flexibility**: If you're facing a time limit, cut the sidewalk bit or the $200k land deal—keep flooding and safety front and center.

What do you think? Want to tweak anything before you use it, or got those links ready? I’m here to refine it further!

Speech to Address Concerns About Tedford's Development Plans

"Good evening, board members and neighbors. My name is [Your Name], and I live at 90 Thomas Point Road, just 325 feet from Tedford's proposed development at 65 Thomas Point Road. I've been fighting this project since 2022 because it's not just a bad fit—it's a violation of our town's rules, a threat to our safety, and a burden on our community. I'm asking you to reject this plan and require Tedford to find a more suitable location.

Zoning Violations and Expired Comprehensive Plan
Let's start with the basics:
- The 2008 Comprehensive Plan, which expired in 2020, explicitly stated that no development should occur off Thomas Point Road until the intersection at Old Bath Road is updated. That intersection still hasn't been fixed, yet Tedford's project has been approved three times, most recently on January 28, 2025.
- My zone was originally designated as Commercial Residential (CC), but it's been changed twice—first to GM4 and then again—without proper justification.
- This project exceeds zoning height limits, the buffers are inadequate, and the impervious surface ratio is excessive. These aren't just technicalities; they're violations of the rules meant to protect our neighborhood.

Environmental and Safety Concerns
But it's not just about rules—it's about real harm:
- Tedford's deforestation and cost-cutting stormwater modifications have already caused flooding on my property. In April 2024, my basement was ankle-deep in water, and FEMA paid me $6,000 for the damages. That's not a coincidence; it's a direct result of poor planning and disregard for the environment.
- Less than a mile away, the AFFF spill at Brunswick Landing in August 2024 contaminated my well water with PFAS, making it unusable. My son, who survived stage 4 rhabdomyosarcoma, now faces another health risk because of this. Tedford's project, with its inadequate stormwater controls, only adds to the environmental hazards we're already facing.
- Safety is another major concern. This is a flagship lot development, which requires two entrances and exits by federal building codes. Yet, Tedford's plan has only one, and they've even been granted variances to reduce its width. This isn't just a code violation—it's a life safety issue. They're receiving federal, state, and town funding, but if they followed the proper regulations, they wouldn't qualify. It's unacceptable that they're cutting corners on safety while taking public money.

Infrastructure Limitations
Moreover, the infrastructure here can't support this project:
- There are no sidewalks on Thomas Point Road, and Tedford's plan expects residents to trespass through Walmart's private wooded land to access public transportation. That's not a solution; it's a liability waiting to happen.

Conflicts of Interest and Lack of Accountability
I've raised these issues repeatedly—at town council meetings on February 5, March 4, April 1, and May 6, 2024, among others. I've submitted photos of the flooding, filed complaints about the lack of notification, and pointed out the clear conflict of interest when three planning board members admitted to personally funding Tedford's project before voting to reapprove it on April 24, 2024. They didn't recuse themselves, and that's not just unethical—it's a breach of public trust.
- Additionally, the developer, Kevin Bunker, secured land valued at $1.7 million for just $200,000 through a deal involving Senator Mattie Daughtry's Historical Forestation group. This isn't fair dealing; it's favoritism.

Call to Action
I'm not against helping those in need, but this project doesn't belong here. It's too big, too risky, and it's being forced through with disregard for the law and the community. I've been ignored, but the evidence is clear: FEMA payouts, contaminated water, and a planning board tainted by conflicts of interest. This development will only make things worse.

I urge you to reject Tedford's plan and require them to find a location that complies with zoning laws, respects environmental protections, and doesn't endanger our community. Thank you."

Explanation of the Speech
- Structure: The speech is organized into clear sections: zoning violations, environmental and safety concerns, infrastructure issues, and conflicts of interest. This makes it easy to follow and ensures each point is addressed succinctly.
- Evidence: It incorporates specific dates, events (e.g., FEMA payout, AFFF spill), and references to your public comments to lend credibility. The mention of your son's health adds a personal and emotional appeal, which can be powerful in swaying decision-makers.
- Call to Action: The speech ends with a direct request to reject the plan and relocate the project, aligning with your goal of stopping the development in its current form.

Next Steps
- If you can provide Tedford's development plan or specific details from the zoning appeals, I can refine the speech further with exact figures (e.g., building height, buffer sizes).

- Consider practicing the speech to ensure it feels natural and fits within any time constraints you might face at the hearing.

This speech is designed to be persuasive, grounded in facts, and easy to deliver. Let me know if you'd like to make any adjustments or if you have additional information to include!
———-

11:20 am 5/14/24
Based on the plans and documents provided, here's an analysis of the project's compliance with Brunswick zoning and state and federal regulations:

1. Zoning:
  - The project is located in the GM4 (Growth Mixed-Use 4) zoning district.
  - Building height: 35 feet (exceeds the allowed 30 feet)
  - Parking: 21 spaces (inadequate for the number of units and beds)
  - Sidewalk: Missing along Thomas Point Road (required for pedestrian safety and accessibility)
2. State Regulations:
  - Maine State Building Code: Compliance required for accessibility, life safety, and structural integrity
  - Maine Department of Environmental Protection (DEP): Stormwater management and water quality regulations apply
3. Federal Regulations:
  - Americans with Disabilities Act (ADA): Accessibility requirements for parking, entrances, and facilities
  - Federal Emergency Management Agency (FEMA): Floodplain management regulations apply (if applicable)

Violations and Concerns:

- Excessive building height
- Inadequate parking
- Missing sidewalk
- Potential stormwater management and water quality issues
- Potential accessibility issues (ADA compliance)

Recommendations:

- Reduce building height to comply with GM4 zoning regulations
- Increase parking spaces to meet zoning requirements
- Install a sidewalk along Thomas Point Road
- Modify stormwater management systems to meet state and federal regulations
- Ensure ADA compliance for must be before approval
———————-

2 CFR Part 200 refers to the “Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards.” This part of the Code of Federal Regulations (CFR) is a key resource for federal grant management in the United States. It was established to streamline and standardize the rules and requirements for managing federal funds, ensuring that federal awards are used efficiently, effectively, and in accordance with federal regulations.

Here’s a breakdown of what 2 CFR Part 200 covers:
1.
Subpart A - Acronyms and Definitions: Provides definitions of terms used in the regulations.
2.
Subpart B - General Provisions: Sets forth the overall administrative and financial management principles, including the applicability of the regulations to different types of entities.
3.
Subpart C - Pre-Award Requirements: Includes provisions related to the pre-award process for federal grants, including the requirements for entities to demonstrate their ability to manage federal funds.
4.
Subpart D - Post-Award Requirements: Covers the terms and conditions for managing federal awards, including budgeting, allowable costs, and reporting requirements.
5.
Subpart E - Cost Principles: Outlines the principles for determining the allowability of costs charged to federal awards, focusing on reasonable, allocable, and necessary costs.
6.
Subpart F - Audit Requirements: Establishes the audit requirements for non-federal entities that receive federal funds, particularly those that meet certain thresholds.

2 CFR Part 200 aims to promote transparency, accountability, and efficiency in the use of federal funds. It applies to a wide range of recipients, including state and local governments, nonprofit organizations, and educational institutions.
———————

The Maine Administrative Procedure Act (MAPA) is the state equivalent of the federal Administrative Procedure Act (APA). It governs the way state agencies in Maine make rules, conduct hearings, and handle contested cases. MAPA is designed to ensure that agencies operate in a fair, transparent, and accountable manner when exercising their rulemaking and decision-making authority.

Key Aspects of the Maine Administrative Procedure Act (MAPA):
1.
Rulemaking:
•

Notice-and-Comment Process: Similar to the federal APA, Maine's MAPA requires agencies to follow a notice-and-comment process when creating, amending, or repealing rules. Agencies must provide public notice of proposed rules and allow for public comment before finalizing them.

•

Rule Adoption: Agencies are required to submit their rules to the Legislative Council for review. If the rules are not approved by the council, they may be invalidated.

•

Procedure: The rulemaking process must be transparent and include the publication of proposed rules in the Maine State Register, allowing for public participation.

2.

Adjudication and Hearings:

•

Contested Cases: When an agency is involved in a case where a person's rights are at issue (e.g., a denial of a license, penalty, or permit), the MAPA requires the agency to follow a fair process. This includes providing the affected person with a hearing, an opportunity to present evidence, and a clear, reasoned decision.

•

Due Process: MAPA guarantees procedural fairness in contested cases, ensuring that parties have the opportunity to present their case, cross-examine witnesses, and receive an impartial decision-maker.

•

Administrative Hearings: These are held by administrative law judges or hearing officers, and decisions can be appealed within the agency or in the courts.

3.

Judicial Review:

•

Under MAPA, any final decision made by an agency can be subject to judicial review in the Maine Superior Court. If a party believes the agency violated MAPA or acted outside its authority, they can challenge the agency's decision in court.

•

Courts review whether the agency's action was lawful, reasonable, and consistent with the governing statutes. If an agency action is found to be arbitrary, capricious, or unlawful, the court can remand the matter back to the agency for further proceedings or even invalidate the decision.

4.

Agency Authority:

•

Agencies in Maine are granted specific powers by the legislature. MAPA ensures that agencies do not exceed the scope of their statutory authority. If an agency acts outside its authority, its action could be considered invalid.

5.

Transparency and Accountability:

•

MAPA requires agencies to provide certain documents to the public, including notices of proposed rules and decisions. It aims to ensure that the public can understand the agency's actions, provide feedback, and hold agencies accountable.
6.
Scope of MAPA:
•
The MAPA applies to most state agencies in Maine, but there are exceptions, such as certain regulatory boards and commissions that may have their own procedural rules or alternative processes defined by statute.

Maine Administrative Procedure Act Violations:

Similar to the federal APA, violations of the Maine APA may include:
•
Failure to follow required procedures (such as the notice-and-comment rulemaking process).
•
Failure to provide adequate notice of hearings or decisions in contested cases.
•
Acting outside statutory authority granted to the agency.
•
Failure to provide an opportunity for a fair hearing in contested cases.
•
Making arbitrary or capricious decisions in rulemaking or adjudication.
•
Failure to provide adequate justification or reasoning for agency decisions in contested cases.

Enforcement and Remedies:
•
If a violation of the MAPA occurs, the affected party may seek judicial review in the Maine Superior Court. Courts can order remedies such as invalidating agency actions, remanding the case to the agency, or requiring the agency to follow proper procedures.
•
Injunctive Relief: If necessary, the court may issue an injunction to prevent an agency from continuing a particular action.

Resources:
•
The Maine APA is codified in 5 M.R.S. § 8051-8060. This statute outlines all of the procedural requirements and guidelines for agency actions, from rulemaking to adjudication.
———

Speech to the Brunswick Zoning Board of Appeals

Standing and erroneous ruling…

Public Participation & Due Process Violations

Under Maine law, public participation is a fundamental right in land use decisions. The town's failure to properly notify abutters, provide transparent records, and allow for meaningful input violates multiple legal provisions governing public participation.
1. Failure to Notify Abutters (Violation of Due Process & MAPA)
•
The Maine Administrative Procedures Act (MAPA, 5 M.R.S. §§ 8001 et seq.) and Brunswick's local zoning ordinances require that all abutters be notified of site plan approvals and significant amendments.
•
I have consistently appealed this project since 2020 and was assured that I was added to the abutters' notification list—yet I was never notified of the 1/28/25 reapproval.
•
This is a clear due process violation that renders the approval void under MAPA § 9052(1), which states that an affected party must be given proper notice and an opportunity to be heard
Good evening, board members. My name is Mrs. Jennifer Navarro as you know from the three previous appeals against Tedford I've had before you. I reside at 90 Thomas Point Road, just 211-325 feet from Tedford's proposed development at 65 Thomas Point Road. Depending on varying reputable sources. I stand before you not just as a resident, but as a citizen demanding accountability, adherence to the law, and protection of public safety, environmental health, and due process.

The Tedford Housing project must be rejected and forced to relocate because it violates multiple zoning laws, life safety standards, environmental regulations, and my fundamental rights as a property owner. The town's failure to follow its own laws and its continued disregard for public safety, proper procedure, and environmental protection is not just unlawful—it's reckless and negligent. To me it is clear this was rubber stamped approved regardless of my public input. Tedfords failed performance guarantee and needs for continued reapprovals, demonstrates that effortlessly. Today, here's a summary for your review.
With my known years worth of fighting Tedfords approval with the Town of Brunswick, I was denied Due Process and proper procedural act of abutting list notification of 1/28/25 scheduled Planning Board Site plan reapproval for Tedford at 65 Thomas point rd. This violates Maine state law and MEPA.
I. Zoning & Comprehensive Plan Violations
1.

2008 Comprehensive Plan Violations – This plan, which lost all legal standing on November 20, 2020, explicitly stated that no new development shall be approved off Thomas Point Road until the intersection at Old Bath Road is upgraded.

•

The intersection remains unimproved, yet this project was approved in direct violation of the plan.

•

My property was originally designated as Commercial Residential (CC), but was changed to GM4 without justification.

2.

Excessive Building Height – The proposed structure exceeds 35 feet in height, violating Brunswick's zoning limits for the area.

3.

Lack of Required Buffers – The site fails to provide the legally required buffer zones, further infringing on abutters' rights and reducing environmental protections. I request a MDOT official traffic and safety study be required by town of Tedfords site approval.

II. Life Safety Violations & Public Hazard

1.

No Two Entrances/Exits for a Flagship Lot Development

•

This directly violates federal and state fire safety codes, which require at least two means of ingress/egress for developments of this size.

•

Yet, Tedford was granted a variance to reduce the lane width, further increasing risk.

2.

No Path to the Sprinkler Room

•

This is a fire safety violation—if emergency personnel cannot access the sprinkler room, they cannot effectively suppress a fire, putting residents and responders at risk.

3.

No Sidewalks on Thomas Point Road

•

The lack of pedestrian infrastructure creates a serious safety risk.

•

Just four days ago, on February 23, 2025, a homeless individual, Justin Mitchell, was hit and killed by a car on Riverside Street in Portland due to a lack of sidewalks accessing that Homeless shelter deemed unsafe and New8 reports on increased public safety concerns and hazards for that riverside shelter. This proves my case and promise to perhaps bring civil suit against Town and MDOT if inevitably anyone come to be harmed here forced to suffer similar fates at this Tedford site location. Which site is rubber stamped although certainly does not work. Multiple times I've raised that concern and I'm awaiting the horrendous news it happen here. DONT ALLOW the risk. Force Tedford to relocate to a safer site location that puts public safety above development.

•
Are you willing to accept liability when the same tragedy happens here?

III. Environmental & Public Health Violations
1/28/25 planning board findings for site reapproval states no new changes since last approval. Erroneous decision as they fail to mention 8/19/24 AFFF PFOS spill from MRRA and its public health disaster and environmental risks.
1.
The AFFF PFOS Disaster – August 19, 2024
•
The massive AFFF spill at Brunswick Landing contaminated my well with PFAS ("forever chemicals"), making my water unsafe to drink.
•
Despite this significant environmental event, the Findings of Fact from the 1/28/25 reapproval make no mention of it. This is a clear violation of NEPA (National Environmental Policy Act) and Maine state environmental laws, which require:
•
Environmental impact reviews for projects near contaminated sites.
•
Stronger stormwater management plans, not weaker ones.
2.
Stormwater & Flooding Hazards
•
In April 2024, my basement flooded, and FEMA paid me $6,000 in damages.
•
The modified stormwater plan was approved not based on environmental necessity, but based on Tedford's financial limitations—placing financial savings over public health and safety is unlawful and unacceptable. How many variances are you willing to allow before questions of need for recusal or favorable bias for Tedford is assumed?

IV. Due Process Violations & Procedural Errors
1.
Failure to Notify Abutters
•
I have fought this project since 2020 and was told I was added to the abutters' notification list—yet I was never notified about the 1/28/25 reapproval. I have previous mailing from town of Brunswick for other Tedford public notice meetings, which further demonstrates I WAS well known to be added to abutters list. Yet town says because I'm a mere 25 ft over 300 abutters radius per their word, that they didn't need to notify me. Also, see photos of Mapquest and other reliable GIS maps showing .04 and or 211 ft distance between Tedford and me.
•
This violates Maine's Municipal Administrative Procedures Act (MAPA) and due process laws, rendering the approval void.

2.
Withholding of Public Records – 13 Months of Missing Minutes

- On January 25, 2025, the planning board approved 13 months' worth of minutes at once, conveniently concealing key discussions. As of today 2/27/25 there's still no supplied finding of facts for Tedford uploaded for public access and no minor modifications showing finding of facts and permit updates for approved decrease in stormwater system and plan, or excessive building height variance approval.
- Why were the minutes withheld for over a year? This is a violation of Maine's Freedom of Access Act (FOAA).

3.
Conflicts of Interest

- At least three planning board members personally donated or funded Tedford's project, yet voted on its approval on April 24, 2024, without recusing themselves.
- This is an unethical breach of public trust and likely a violation of Maine's conflict-of-interest statutes.

V. Failure to Meet Grant & Funding Requirements

1.
Tedford received state and federal funding for this project—yet its approvals and variances render it ineligible under federal HUD and safety standards.
2.
Why is Tedford allowed to receive public money while failing to meet basic safety, zoning, and environmental requirements?

VI. Violations of My Civil Rights & Property Rights

1.
The town's actions have deprived me of my right to enjoy my property and maintain its value.
2.
The excessive flooding, environmental hazards, and procedural errors are a direct violation of my civil rights.

Final Argument: This Project Must Be Relocated

Given the zoning violations, life safety hazards, environmental risks, procedural failures, and due process violations, this project must be stopped and relocated to a legally compliant site.

I demand that the Zoning Board of Appeals:

1.

Void the 1/28/25 reapproval due to the failure to notify abutters and omission of critical environmental hazards.
2.
Require a new environmental impact report considering the 8/19/24 AFFF spill.
3.
Mandate that Tedford relocate the project to a site that complies with zoning, safety, and environmental regulations.
Shut down all construction immediately with injunction to stop building construction.
Tedford has been given numerous opportunities to meet their obligations. Now it's my turn to be taken seriously. I've not resubmitted these complaints to State of Maine or Federal regulators because I am allowing for Town of Brunswick to make this injustice right. However, with God as my witness, I will pursue Federal Court proceedings with unyielding might, should these obvious violations be allowed to stand. 65 Thomas Point Rd is NOT the proper site for this homeless resource center and shelter. The cost are too high due to attempt to make a small lot work. Put life safety and public safety FIRST.
Additionally the asylee housing is 800 feet away from me and Tedford lots breaking the 1000 foot buffer required between two shelter residences. Where's the three prong electric pole upgrades as required that also further increase my families health? 24/7 access means far more traffic than they implied. Inadequate parking. And MORE.

The law is clear. The violations are extensive. And the consequences of inaction are too severe. The people of Brunswick deserve better. I urge you to uphold the law and reject this project.

Thank you.
/S./ Mrs. Jennifer Navarro

Speech to Address Concerns About Tedford's Development Plans

"Good evening, board members and neighbors. My name is [Your Name], and I live at 90 Thomas Point Road, just 325 feet from Tedford's proposed development at 65 Thomas Point Road. I've been fighting this project since 2022 because it's not just a bad fit—it's a violation of our town's rules, a threat to our safety, and a burden on our community. I'm asking you to reject this plan and require Tedford to find a more suitable location.

Zoning Violations and Expired Comprehensive Plan
Let's start with the basics:
- The 2008 Comprehensive Plan, which expired in 2020, explicitly stated that no development should occur off Thomas Point Road until the intersection at Old Bath Road is updated. That intersection still hasn't been fixed, yet Tedford's project has been approved three times, most recently on January 28, 2025.
- My zone was originally designated as Commercial Residential (CC), but it's been changed twice—first to GM4 and then again—without proper justification.

- This project exceeds zoning height limits, the buffers are inadequate, and the impervious surface ratio is excessive. These aren't just technicalities; they're violations of the rules meant to protect our neighborhood.

Environmental and Safety Concerns
But it's not just about rules—it's about real harm:
- Tedford's deforestation and cost-cutting stormwater modifications have already caused flooding on my property. In April 2024, my basement was ankle-deep in water, and FEMA paid me $6,000 for the damages. That's not a coincidence; it's a direct result of poor planning and disregard for the environment.
- Less than a mile away, the AFFF spill at Brunswick Landing in August 2024 contaminated my well water with PFAS, making it unusable. My son, who survived stage 4 rhabdomyosarcoma, now faces another health risk because of this. Tedford's project, with its inadequate stormwater controls, only adds to the environmental hazards we're already facing.
- Safety is another major concern. This is a flagship lot development, which requires two entrances and exits by federal building codes. Yet, Tedford's plan has only one, and they've even been granted variances to reduce its width. This isn't just a code violation—it's a life safety issue. They're receiving federal, state, and town funding, but if they followed the proper regulations, they wouldn't qualify. It's unacceptable that they're cutting corners on safety while taking public money.

Infrastructure Limitations
Moreover, the infrastructure here can't support this project:
- There are no sidewalks on Thomas Point Road, and Tedford's plan expects residents to trespass through Walmart's private wooded land to access public transportation. That's not a solution; it's a liability waiting to happen.

Conflicts of Interest and Lack of Accountability
I've raised these issues repeatedly—at town council meetings on February 5, March 4, April 1, and May 6, 2024, among others. I've submitted photos of the flooding, filed complaints about the lack of notification, and pointed out the clear conflict of interest when three planning board members admitted to personally funding Tedford's project before voting to reapprove it on April 24, 2024. They didn't recuse themselves, and that's not just unethical—it's a breach of public trust.
- Additionally, the developer, Kevin Bunker, secured land valued at $1.7 million for just $200,000 through a deal involving Senator Mattie Daughtry's Historical Forestation group. This isn't fair dealing; it's favoritism.

Call to Action
I'm not against helping those in need, but this project doesn't belong here. It's too big, too risky, and it's being forced through with disregard for the law and the community. I've been ignored, but the evidence is clear: FEMA payouts, contaminated water, and a planning board tainted by conflicts of interest. This development will only make things worse.

I urge you to reject Tedford's plan and require them to find a location that complies with zoning laws, respects environmental protections, and doesn't endanger our community. Thank you."

Explanation of the Speech
- Structure: The speech is organized into clear sections: zoning violations, environmental and safety concerns, infrastructure issues, and conflicts of interest. This makes it easy to follow and ensures each point is addressed succinctly.
- Evidence: It incorporates specific dates, events (e.g., FEMA payout, AFFF spill), and references to your public comments to lend credibility. The mention of your son's health adds a personal and emotional appeal, which can be powerful in swaying decision-makers.
- Call to Action: The speech ends with a direct request to reject the plan and relocate the project, aligning with your goal of stopping the development in its current form.

Next Steps
- If you can provide Tedford's development plan or specific details from the zoning appeals, I can refine the speech further with exact figures (e.g., building height, buffer sizes).
- Consider practicing the speech to ensure it feels natural and fits within any time constraints you might face at the hearing.

This speech is designed to be persuasive, grounded in facts, and easy to deliver. Let me know if you'd like to make any adjustments or if you have additional information to include!

On Feb 26, 2025, at 11:48 AM, Julie Erdman <jerdman@brunswickme.gov> wrote:

Hi Jennifer,

The ZBA will be the ones to decide whether you have standing. Your application has been accepted as submitted and no further information is required to be heard by the Board.

Tedford is permitted to continue with the project while the appeal is being processed. I am unsure what you are referring to when you ask about permit reissuance. They have a building permit and that has not expired.

The abutter radius was increased from 200 ft to 300 ft for Major Development Review this past summer to align with the notification radius for Conditional Use.

I forgot to respond to your previous question regarding copies of permits/FOIA request. I can help you access the information you are looking for. Is it just permits through Codes

that you are requesting – building, plumbing, electrical? Are you requesting the permit itself or the applications as well?

I am hopeful you are able to gather whatever information you feel you feel is relevant to submit by Friday as the public meeting date is set and the Town has paid to notice the meeting in the Times Record. Let me know if I can do anything else to assist.

Julie

Julie Erdman
Director
Planning and Development

P: (207) 721-4022
E: jerdman@brunswickme.gov

<image007.png>
85 Union Street
Brunswick | ME 04011 <image008.jpg>
www.brunswickme.gov

With limited exceptions, e-mails sent to and from the Town of Brunswick are considered public records under Maine's Freedom of Access Act (FOAA). Public records are open to inspection and may be copied and distributed to others, including members of the media. Unless the e-mail meets one of the exceptions to the public records provisions, there should be no expectation of privacy or confidentiality.

From: Jen Navarro <blondie_mamita84@icloud.com>
Sent: Wednesday, February 26, 2025 11:00 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Cc: James Dealaman <jdealaman@brunswickme.gov>
Subject: Re: 211 ft away from Tedford

CAUTION: This email originated from outside the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Are you insisting I have to prove appeal standing? Or since 3/6/25 was set I assume standing has been proven met already?
Any permit reissuance? While be appealed are they allowed to be building such as they are today?
What was changed for conditional use permit in 6/17/24? Has the abutting notification radius been altered since 1/11/21 in any way? If so how much. I may need an extension to submit appeal data. Call me if that's easier for you. Thanks and forward all communications since filing the appeal including today's emails to appeal packet. Thanks
<image001.png>
<image002.png>
<image003.png>

Notice this Google map app shows 200 feet
<image004.png>
<image005.png>
<image006.png>

On Feb 26, 2025, at 10:43 AM, Jen Navarro <blondie_mamita84@icloud.com> wrote:

That doesn't appear to be using the closest point path. Crows path. Can you confirm that the 326ft you sent is the crows path closest point? Per my many searches on multiple maps the closest point is on the tip of my property by Thomas point rd frontal footage. If you're not depicting the crows path closest point I request that immediately. I will submit by Friday. However, can you send me all permits on Tedford approved by code enforcement or must I foia request? Please confirm immediately why the town didn't have me as an abutting neighbor OR person of interest considering I've appealed twice now. Confirm that I was in no way tied to this for notification. Procedural error at best for failure to due process public notice and input on zoning decisions. Casella v. Scarborough and many more

On Feb 26, 2025, at 10:03 AM, Julie Erdman <jerdman@brunswickme.gov> wrote:

Good Morning Jennifer,

The measurement tool on the Town GIS shows the closest point on your lot as 326.95 feet away from the Tedford lot – see map below. I will include a copy of this in the packet for the ZBA meeting. If you have any further information you like to submit for your appeal, please do so by Friday morning at 10am. We will be posting and distributing the meeting packet that day.

Thank you,
Julie

Julie Erdman
Director
Planning and Development

P: (207) 721-4022
E: jerdman@brunswickme.gov

<image001.png>
85 Union Street
Brunswick | ME 04011
www.brunswickme.gov

<image003.jpg>

With limited exceptions, e-mails sent to and from the Town of Brunswick are considered public records under Maine's Freedom of Access Act (FOAA). Public records are open to inspection and may be copied and distributed to others, including members of the

media. Unless the e-mail meets one of the exceptions to the public records provisions, there should be no expectation of privacy or confidentiality.

<image002.png>

-----Original Message-----
From: Jen Navarro <blondie_mamita84@icloud.com>
Sent: Wednesday, February 26, 2025 7:28 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Subject: 211 ft away from Tedford

I am requesting your GIS feet measurements from Tedfords property at 65 Thomas pt to mine at 90 Thomas pt. Per my online searches it is 211 feet. Therefore, devoid having to provide evidence I was apart of the notification list as in reality I am an abutting property owner and yet I was not notified by mail, phone or email of Tedfords 1/28/25 reapproval of site plan planning board meeting. My appeal is 3/6/25 I need a copy of what the town records or GIs reflects for this distance. 300ft is conditional use abutting notice requirements

https://urldefense.proofpoint.com/v2/url?u=https-3A__www.bing.com_search-3Fq-3Ddistance-2Bbetween-2B65-2BThomas-2Bpoint-2Brd-2BBrunswick-2Bmaine-2Band-2B90-2BThomas-2Bpoint-2Brd-26safeSearch-3Dstrict-26form-3DMETAMG-26from-5Fxma-5Fclick-3Dxma-5Fweb-5Furl-26xma-5Fclick-5Fid-3D646CF6AE-2DB185-2D4CCC-2D8FFB-2D8B27A01B5990-26tam-5Fxma-5Fcontent-5Ftype-3D3008-26is-5Ffb-5Fcontent-3Dfalse-26forward-3Dfalse-26ts-3D1740571905691&d=DwIFAg&c=euGZstcaTDllvimEN8b7jXrwqOf-v5A_CdpgnVfiiMM&r=8IL0LJ2GHJ2KGHujJ8mGvBTGhsXmswnJBjJz7G9WXnk&m=HiobrTlf9DNw7pxxLfGy7OPaGOdCD2v3GFaMhhFWKoKWntC8V66AcRAm5r3jyG14&s=levORYWPqSzC2UCKDUk12t67h9IgzzKy-k1VaeVB6Cs&e=

This email has been scanned for spam and viruses by Proofpoint Essentials. Visit the following link to report this email as spam:
https://us3.proofpointessentials.com/app/report_spam.php?mod_id=11&mod_option=logitem&report=1&type=easyspam&k=k1&payload=53616c7465645f5fbacf4b3e87b358346491342a50aeb5c30f22793d129969d04adc261721ba0f01fdad0f0807727b52d0300bb3ce51037709ca087bf9c4309865155beccaa24bbb1d149b44d3f0312b7e14b76754a3d9d5dab1d730672bea7db6a273b8f24695577308e78dca0046ad0ab5eb77cd183b6a39ad91f6cd3aba0c1dbcd33a3b99c5c6a782355ce4408f1b5e7a97056c652915ca18bb3282a7f7e5


This email has been scanned for spam and viruses by Proofpoint Essentials. Click here to report this email as spam.

From: Julie Erdman
To: James Dealaman
Subject: FW: ZBa 3/6/25 3rd APpeal
Date: Friday, February 28, 2025 10:01:35 AM
Attachments: image001.png

From: carlos navarro <carlosnq007@gmail.com>
Sent: Friday, February 28, 2025 9:56 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Subject: Fwd: ZBa 3/6/25 3rd APpeal

CAUTION: This email originated from outside the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.





Begin forwarded message:

> **From:** carlos navarro <carlosnq007@gmail.com>
> **Date:** February 28, 2025 at 9:54:58 AM EST
> **To:** Julie Erdman <jerdman@brunswickme.org>
> **Subject: ZBa 3/6/25 3rd APpeal**

Section section 5.1.1.C.2 and 5.2.7.A.2 ZBA allowed appeals for decisions and 5.1.1.C2 peers and duties
1/11/24 cup expiration was called out by ME on 4/14/24 public comment TC meeting at 2:22:22 and that's why Tedford went for reapproval they didn't know or care and neither did town. That expiration per 5.2.9.Q(5) MEANS that 5/14/24 reapproval of cup by PB was erroneous improper procedural acts and negligence to act without favor or bias. Lack of transparency and collusion to outsmart appellant. Per 5.2.9.Q(5) 2 year expiration past planning board approval date without occupant issued is Automatically expired
De-no entire dev major review and cup again as one like 1/11/24 approval
5.2.2.-A (3)cup failure to notice me
5.2.3.B
Section 4.11 and 4.13 design standards
Non ADA
No path to sprinkler
And per 5.2.2 section B.2. (B) unsafe hazards for pedestrian and bicycle dev review
5.2.2. B2 c impede emergency vehicles and services and building sq footage requires state and federal and zoning ordinances to and must adhere to two entry and exit points due to life safety and emergency hazards

12.2 A failure to enhance existing area
Casella vs.
2008 comp plan says 1.2.2.A no holding until intersection upgrades off Thomas point rd. Excessive building height in design standards 3.4.1 X 1000 shelter buffer asylee 880 ft away
ME APA and MAPa codified in 5 MRS section 8051-8060 precedent Anastasia v. city of Poland
Casella vs.
I demand MDOT issued movement and traffic study. Inadequate traffic study supplied and no regulation of the standards shelter created and used. 24/7 access shelter violates enjoyment
to my property and value. Ambulances, threats of trespassing, drug paraphernalia, dangers ect.
4.1.1 arcgevtural design standards =Too big a building size in comparison to abutting nearby architecture it's 17.568 sq ft and all
Shelter 1000 abutters to shelter violation as crows path to asylee housing is

880ft from Tedford
This site location does NOT work
Impervious coverage is out of this zoning
Per comp plan minus many amended zoning rewrite
My property is CC2 and not GM4
NEPA violations 42 us section 44321 et seq
4.5.4 stormwater permit dep

ZBa shall consider per title 30 A section 4354 et seq impact in proposed use to neighbors BIg grievances to my family and peace 5.1.1.C (2) peer duty failure to enforce permit performance guarantees
4.5.2 water supply and clean water act violations neighboring properties for well over 1300 ft are 1000-2,400 sq feet residential homes. So RV I didn't learn my cut off was in an hour until two days ago so I really need to extend until Monday 10am but if not it'll ALOt of unfinished data just so it's submitted before today at 10am I have 51 mins. All email I send you today are to be submitted to zoning appeal 3/6/25 site plan approval appeal of planning board
Due process violations as I have letters mailed in original envelopes showing I've been on abutters list ever since Natalie honored my request to be back in early 2024. MAPA and procedural errors, erroneous reapproval due to having been after 1/11/25 expiration on file. Also, no written finding of facts of all waivers granted or approvals. Approvals needed to be de novo as did cup reapproval 5/14/24 but threshold me to standing and 6 criteria cup requirements which violated my public participation and was improper administrative work from planning board, and staff. 5.1.3.B.1A-C
1/28/25 PB approval is erroneous they said nothing changed since 1/11/24 approved and YET excluded maine number one biggest Human health disaster and 8/19/24 AFFF disaster spill of PFOS and as a well used this dev concerns me
I see no NEPA
Environmental review impact report as required to use fed state funding so to allow this to be the site for Tedford is making you the ZBA guilty to that.
2/23/25 homeless shelter in Portland had a transient tenant killed leaving its shelter on riverside rd by a car and news 8 says major life safety concerns around shelter and tenants safety. I forewarned the danger of Thomas lt rd, the intersection deeply in need of remedy upgrades the lack of safe passage and bicycle friendly sidewalks on Thomas pt rd and to make those in need reliable to wait around for Tedford transportation is violation of their civil

rights and freedom.
Stormwater modification by Chris Baldwin is inadequate esp with 8/19/24 odors afff disaster.
To make me do this and to deny my last appeals 6/6/24 ect is unethical and I want third party review and pb to recuse themselves as at 5/14/24 approval of cup they admitted to donated to this development and even if charitable that makes me certain all these rubber stamped unregulated approvals are acts of favor and bias, conflicts of interest and besides they NEVER Added That disclosure to FINDing of FACTS which is ordinance requirement. Also, 2/25/25 planning board meeting ended with approval of 13 months worth of minutes super suspicious even with video access because it creates paper trail and seems deliberate. Seasonal flooding and waiver to deduce building up for value savings is unsustainable and negligent.
5.1.1.F2 minor modifications error and 5.2.10.A.1

5.1.1.C2 ZBa power duties
Life safety standards violations and hazards
No path to sprinkler room
One entry exit on narrow drive way, that is flagship lot with the size of this building requires 2 entry and 2 exits. I will get hud revoked and state funds revoked as any public building using fed and state funds are legally liable to meet ADA standards and life safety building standards. No paved path to Walmart is ADA violation of access

5.1.3.A.(1) A-B due process violations
5.1.3..B.1a-c
Title 30 MRSA 2691 et seq
4.5.4
5.2.9.Q(5)
Violation of 2008 comp plan cooks corner master plan and design standards
No approval for building on Thomas pt rd until intersection upgrade and road safety improvements are completed title 30 A 4301 et seq zoning and comp title 30 A MRSA 4301.12.(A) no variances against comp plan and comp says no dev on Thomas point rd until intersection fixed and to bolster neighborly transitions. Safety for pedestrian and no sidewalks on Thomas or rd is Life safety standards

5.1.1.F.2& subsection 5.2.10.B
5.1.1.e.a.1 site approval and waivers sub. 5.2.9.(M) waivers. L

Begin forwarded message:

From: Jen Navarro <blondie_mamita84@icloud.com>
Date: February 27, 2025 at 1:07:26 PM EST
To: Carlos Navarro <carlosnq007@gmail.com>

Chaotgpt Tedford speech combo

Speech to the Brunswick Zoning Board of Appeals

Standing and erroneous ruling…

Public Participation & Due Process Violations

Under Maine law, public participation is a fundamental right in land use decisions. The town's failure to properly notify abutters, provide transparent records, and allow for meaningful input violates multiple legal provisions governing public participation.
1. Failure to Notify Abutters (Violation of Due Process & MAPA)
• The Maine Administrative Procedures Act (MAPA, 5 M.R.S. §§ 8001 et seq.) and Brunswick's local zoning ordinances require that all abutters be notified of site plan approvals and significant amendments.
• I have consistently appealed this project since 2020 and was assured that I was added to the abutters' notification list—yet I was never notified of the 1/28/25 reapproval.
• This is a clear due process violation that renders the approval void under MAPA § 9052(1), which states that an affected party must be given proper notice and an opportunity to be heard

Good evening, board members. My name is Mrs. Jennifer Navarro as you know from the three previous appeals against Tedford I've had before you. I reside at 90 Thomas Point Road, just 211-325 feet from Tedford's proposed development at 65 Thomas Point Road. Depending on varying reputable sources. I stand before you not just as a resident, but as a citizen demanding accountability, adherence to the law, and protection of public safety, environmental health, and due process.

The Tedford Housing project must be rejected and forced to relocate because it violates multiple zoning laws, life safety standards, environmental regulations, and my fundamental rights as a property owner. The town's failure to follow its own laws and its continued disregard for public safety, proper procedure, and environmental protection is not just unlawful—it's reckless and negligent. To me it is clear this was rubber stamped approved regardless of my public input. Tedfords failed performance guarantee and needs for continued reapprovals, demonstrates that effortlessly. Today, here's a summary for your review.

With my known years worth of fighting Tedfords approval with the Town of Brunswick, I was denied Due Process and proper procedural act of abutting list notification of 1/28/25 scheduled Planning Board Site plan reapproval for Tedford at 65 Thomas point rd. This violates Maine state law and MEPA.

I. Zoning & Comprehensive Plan Violations

1. 2008 Comprehensive Plan Violations – This plan, which lost all legal standing on November 20, 2020, explicitly stated that no new development shall be approved off Thomas Point Road until the intersection at Old Bath Road is upgraded.

• The intersection remains unimproved, yet this project was approved in direct violation of the plan.

• My property was originally designated as Commercial Residential (CC), but was changed to GM4 without justification.

2. Excessive Building Height – The proposed structure exceeds 35 feet in height, violating Brunswick's zoning limits for the area.

3. Lack of Required Buffers – The site fails to provide the legally required buffer zones, further infringing on abutters' rights and reducing environmental protections. I request a MDOT official traffic and safety study be required by town of Tedfords site approval.

II. Life Safety Violations & Public Hazard

1. No Two Entrances/Exits for a Flagship Lot Development

• This directly violates federal and state fire safety codes, which require at least two means of ingress/egress for developments of this size.

• Yet, Tedford was granted a variance to reduce the lane width,

further increasing risk.
2. No Path to the Sprinkler Room
• This is a fire safety violation—if emergency personnel cannot access the sprinkler room, they cannot effectively suppress a fire, putting residents and responders at risk.
3. No Sidewalks on Thomas Point Road
• The lack of pedestrian infrastructure creates a serious safety risk.
• Just four days ago, on February 23, 2025, a homeless individual, Justin Mitchell, was hit and killed by a car on Riverside Street in Portland due to a lack of sidewalks accessing that Homeless shelter deemed unsafe and New8 reports on increased public safety concerns and hazards for that riverside shelter. This proves my case and promise to perhaps bring civil suit against Town and MDOT if inevitably anyone come to be harmed here forced to suffer similar fates at this Tedford site location. Which site is rubber stamped although certainly does not work. Multiple times I've raised that concern and I'm awaiting the horrendous news it happen here. DONT ALLOW the risk. Force Tedford to relocate to a safer site location that puts public safety above development.
• Are you willing to accept liability when the same tragedy happens here?

III. Environmental & Public Health Violations
1/28/25 planning board findings for site reapproval states no new changes since last approval. Erroneous decision as they fail to mention 8/19/24 AFFF PFOS spill from MRRA and its public health disaster and environmental risks.
1. The AFFF PFOS Disaster – August 19, 2024
• The massive AFFF spill at Brunswick Landing contaminated my well with PFAS ("forever chemicals"), making my water unsafe to drink.
• Despite this significant environmental event, the Findings of Fact from the 1/28/25 reapproval make no mention of it. This is a clear violation of NEPA (National Environmental Policy Act) and Maine state environmental laws, which require:
• Environmental impact reviews for projects near contaminated sites.

• Stronger stormwater management plans, not weaker ones.

2. Stormwater & Flooding Hazards

• In April 2024, my basement flooded, and FEMA paid me $6,000 in damages.

• The modified stormwater plan was approved not based on environmental necessity, but based on Tedford's financial limitations—placing financial savings over public health and safety is unlawful and unacceptable. How many variances are you willing to allow before questions of need for recusal or favorable bias for Tedford is assumed?

IV. Due Process Violations & Procedural Errors

1. Failure to Notify Abutters

• I have fought this project since 2020 and was told I was added to the abutters' notification list—yet I was never notified about the 1/28/25 reapproval. I have previous mailing from town of Brunswick for other Tedford public notice meetings, which further demonstrates I WAS well known to be added to abutters list. Yet town says because I'm a mere 25 ft over 300 abutters radius per their word, that they didn't need to notify me. Also, see photos of Mapquest and other reliable GIS maps showing .04 and or 211 ft distance between Tedford and me.

• This violates Maine's Municipal Administrative Procedures Act (MAPA) and due process laws, rendering the approval void.

2. Withholding of Public Records – 13 Months of Missing Minutes

• On January 25, 2025, the planning board approved 13 months' worth of minutes at once, conveniently concealing key discussions. As of today 2/27/25 there's still no supplied finding of facts for Tedford uploaded for public access and no minor modifications showing finding of facts and permit updates for approved decrease in stormwater system and plan, or excessive building height variance approval.

• Why were the minutes withheld for over a year? This is a violation of Maine's Freedom of Access Act (FOAA).

3. Conflicts of Interest

• At least three planning board members personally donated or funded Tedford's project, yet voted on its approval on April 24, 2024, without recusing themselves.

• This is an unethical breach of public trust and likely a violation

of Maine's conflict-of-interest statutes.

V. Failure to Meet Grant & Funding Requirements
1. Tedford received state and federal funding for this project—yet its approvals and variances render it ineligible under federal HUD and safety standards.
2. Why is Tedford allowed to receive public money while failing to meet basic safety, zoning, and environmental requirements?

VI. Violations of My Civil Rights & Property Rights
1. The town's actions have deprived me of my right to enjoy my property and maintain its value.
2. The excessive flooding, environmental hazards, and procedural errors are a direct violation of my civil rights.

Final Argument: This Project Must Be Relocated

Given the zoning violations, life safety hazards, environmental risks, procedural failures, and due process violations, this project must be stopped and relocated to a legally compliant site.

I demand that the Zoning Board of Appeals:
1. Void the 1/28/25 reapproval due to the failure to notify abutters and omission of critical environmental hazards.
2. Require a new environmental impact report considering the 8/19/24 AFFF spill.
3. Mandate that Tedford relocate the project to a site that complies with zoning, safety, and environmental regulations.
Shut down all construction immediately with injunction to stop building construction. Tedford has been given numerous opportunities to meet their obligations. Now it's my turn to be taken seriously. I've not resubmitted these complaints to State of Maine or Federal regulators because I am allowing for Town of Brunswick to make this injustice right. However, with God as my witness, I will pursue Federal Court proceedings with unyielding might, should these obvious violations be allowed to stand. 65 Thomas Point Rd is NOT the proper site for this homeless resource center and shelter. The cost are too high due to attempt

to make a small lot work. Put life safety and public safety FIRST. Additionally the asylee housing is 800 feet away from me and Tedford lots breaking the 1000 foot buffer required between two shelter residences. Where’s the three prong electric pole upgrades as required that also further increase my families health? 24/7 access means far more traffic than they implied. Inadequate parking. And MORE.

The law is clear. The violations are extensive. And the consequences of inaction are too severe. The people of Brunswick deserve better. I urge you to uphold the law and reject this project.

Thank you.
/S./ Mrs. Jennifer Navarro

Speech to Address Concerns About Tedford's Development Plans

"Good evening, board members and neighbors. My name is [Your Name], and I live at 90 Thomas Point Road, just 325 feet from Tedford's proposed development at 65 Thomas Point Road. I've been fighting this project since 2022 because it's not just a bad fit—it's a violation of our town's rules, a threat to our safety, and a burden on our community. I'm asking you to reject this plan and require Tedford to find a more suitable location.

Zoning Violations and Expired Comprehensive Plan
Let's start with the basics:
- The 2008 Comprehensive Plan, which expired in 2020, explicitly stated that no development should occur off Thomas Point Road until the intersection at Old Bath Road is updated. That intersection still hasn't been fixed, yet Tedford's project has been approved three times, most recently on January 28, 2025.
- My zone was originally designated as Commercial Residential (CC), but it's been changed twice—first to GM4 and then again—without proper justification.
- This project exceeds zoning height limits, the buffers are

inadequate, and the impervious surface ratio is excessive. These aren't just technicalities; they're violations of the rules meant to protect our neighborhood.

Environmental and Safety Concerns
But it's not just about rules—it's about real harm:
- Tedford's deforestation and cost-cutting stormwater modifications have already caused flooding on my property. In April 2024, my basement was ankle-deep in water, and FEMA paid me $6,000 for the damages. That's not a coincidence; it's a direct result of poor planning and disregard for the environment.
- Less than a mile away, the AFFF spill at Brunswick Landing in August 2024 contaminated my well water with PFAS, making it unusable. My son, who survived stage 4 rhabdomyosarcoma, now faces another health risk because of this. Tedford's project, with its inadequate stormwater controls, only adds to the environmental hazards we're already facing.
- Safety is another major concern. This is a flagship lot development, which requires two entrances and exits by federal building codes. Yet, Tedford's plan has only one, and they've even been granted variances to reduce its width. This isn't just a code violation—it's a life safety issue. They're receiving federal, state, and town funding, but if they followed the proper regulations, they wouldn't qualify. It's unacceptable that they're cutting corners on safety while taking public money.

Infrastructure Limitations
Moreover, the infrastructure here can't support this project:
- There are no sidewalks on Thomas Point Road, and Tedford's plan expects residents to trespass through Walmart's private wooded land to access public transportation. That's not a solution; it's a liability waiting to happen.

Conflicts of Interest and Lack of Accountability
I've raised these issues repeatedly—at town council meetings on February 5, March 4, April 1, and May 6, 2024, among others. I've submitted photos of the flooding, filed complaints about the lack of notification, and pointed out the clear conflict of interest when three planning board members admitted to personally funding

Tedford's project before voting to reapprove it on April 24, 2024. They didn't recuse themselves, and that's not just unethical—it's a breach of public trust.
- Additionally, the developer, Kevin Bunker, secured land valued at $1.7 million for just $200,000 through a deal involving Senator Mattie Daughtry's Historical Forestation group. This isn't fair dealing; it's favoritism.

Call to Action
I'm not against helping those in need, but this project doesn't belong here. It's too big, too risky, and it's being forced through with disregard for the law and the community. I've been ignored, but the evidence is clear: FEMA payouts, contaminated water, and a planning board tainted by conflicts of interest. This development will only make things worse.

I urge you to reject Tedford's plan and require them to find a location that complies with zoning laws, respects environmental protections, and doesn't endanger our community. Thank you."

Explanation of the Speech
- Structure: The speech is organized into clear sections: zoning violations, environmental and safety concerns, infrastructure issues, and conflicts of interest. This makes it easy to follow and ensures each point is addressed succinctly.
- Evidence: It incorporates specific dates, events (e.g., FEMA payout, AFFF spill), and references to your public comments to lend credibility. The mention of your son's health adds a personal and emotional appeal, which can be powerful in swaying decision-makers.
- Call to Action: The speech ends with a direct request to reject the plan and relocate the project, aligning with your goal of stopping the development in its current form.

Next Steps
- If you can provide Tedford's development plan or specific details from the zoning appeals, I can refine the speech further

with exact figures (e.g., building height, buffer sizes).
- Consider practicing the speech to ensure it feels natural and fits within any time constraints you might face at the hearing.

This speech is designed to be persuasive, grounded in facts, and easy to deliver. Let me know if you'd like to make any adjustments or if you have additional information to include!

_____-

11:20 am 5/14/24
Based on the plans and documents provided, here's an analysis of the project's compliance with Brunswick zoning and state and federal regulations:

1. Zoning:
 - The project is located in the GM4 (Growth Mixed-Use 4) zoning district.
 - Building height: 35 feet (exceeds the allowed 30 feet)
 - Parking: 21 spaces (inadequate for the number of units and beds)
 - Sidewalk: Missing along Thomas Point Road (required for pedestrian safety and accessibility)
2. State Regulations:
 - Maine State Building Code: Compliance required for accessibility, life safety, and structural integrity
 - Maine Department of Environmental Protection (DEP): Stormwater management and water quality regulations apply
3. Federal Regulations:
 - Americans with Disabilities Act (ADA): Accessibility requirements for parking, entrances, and facilities
 - Federal Emergency Management Agency (FEMA): Floodplain management regulations apply (if applicable)

Violations and Concerns:

- Excessive building height
- Inadequate parking
- Missing sidewalk

- Potential stormwater management and water quality issues
- Potential accessibility issues (ADA compliance)

Recommendations:

- Reduce building height to comply with GM4 zoning regulations
- Increase parking spaces to meet zoning requirements
- Install a sidewalk along Thomas Point Road
- Modify stormwater management systems to meet state and federal regulations
- Ensure ADA compliance for must be before approval

_____-

2 CFR Part 200 refers to the "Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards." This part of the Code of Federal Regulations (CFR) is a key resource for federal grant management in the United States. It was established to streamline and standardize the rules and requirements for managing federal funds, ensuring that federal awards are used efficiently, effectively, and in accordance with federal regulations.

Here's a breakdown of what 2 CFR Part 200 covers:

1. Subpart A - Acronyms and Definitions: Provides definitions of terms used in the regulations.
2. Subpart B - General Provisions: Sets forth the overall administrative and financial management principles, including the applicability of the regulations to different types of entities.
3. Subpart C - Pre-Award Requirements: Includes provisions related to the pre-award process for federal grants, including the requirements for entities to demonstrate their ability to manage federal funds.
4. Subpart D - Post-Award Requirements: Covers the terms and conditions for managing federal awards, including budgeting, allowable costs, and reporting requirements.
5. Subpart E - Cost Principles: Outlines the principles for determining the allowability of costs charged to federal awards, focusing on reasonable, allocable, and necessary costs.
6. Subpart F - Audit Requirements: Establishes the audit requirements for non-federal entities that receive federal funds,

particularly those that meet certain thresholds.

2 CFR Part 200 aims to promote transparency, accountability, and efficiency in the use of federal funds. It applies to a wide range of recipients, including state and local governments, nonprofit organizations, and educational institutions.

———————

The Maine Administrative Procedure Act (MAPA) is the state equivalent of the federal Administrative Procedure Act (APA). It governs the way state agencies in Maine make rules, conduct hearings, and handle contested cases. MAPA is designed to ensure that agencies operate in a fair, transparent, and accountable manner when exercising their rulemaking and decision-making authority.

Key Aspects of the Maine Administrative Procedure Act (MAPA):
1. Rulemaking:
• Notice-and-Comment Process: Similar to the federal APA, Maine's MAPA requires agencies to follow a notice-and-comment process when creating, amending, or repealing rules. Agencies must provide public notice of proposed rules and allow for public comment before finalizing them.
• Rule Adoption: Agencies are required to submit their rules to the Legislative Council for review. If the rules are not approved by the council, they may be invalidated.
• Procedure: The rulemaking process must be transparent and include the publication of proposed rules in the Maine State Register, allowing for public participation.
2. Adjudication and Hearings:
• Contested Cases: When an agency is involved in a case where a person's rights are at issue (e.g., a denial of a license, penalty, or permit), the MAPA requires the agency to follow a fair process. This includes providing the affected person with a hearing, an opportunity to present evidence, and a clear, reasoned decision.
• Due Process: MAPA guarantees procedural fairness in contested cases, ensuring that parties have the opportunity to present their case, cross-examine witnesses, and receive an impartial decision-maker.

• Administrative Hearings: These are held by administrative law judges or hearing officers, and decisions can be appealed within the agency or in the courts.

3. Judicial Review:

• Under MAPA, any final decision made by an agency can be subject to judicial review in the Maine Superior Court. If a party believes the agency violated MAPA or acted outside its authority, they can challenge the agency's decision in court.

• Courts review whether the agency's action was lawful, reasonable, and consistent with the governing statutes. If an agency action is found to be arbitrary, capricious, or unlawful, the court can remand the matter back to the agency for further proceedings or even invalidate the decision.

4. Agency Authority:

• Agencies in Maine are granted specific powers by the legislature. MAPA ensures that agencies do not exceed the scope of their statutory authority. If an agency acts outside its authority, its action could be considered invalid.

5. Transparency and Accountability:

• MAPA requires agencies to provide certain documents to the public, including notices of proposed rules and decisions. It aims to ensure that the public can understand the agency's actions, provide feedback, and hold agencies accountable.

6. Scope of MAPA:

• The MAPA applies to most state agencies in Maine, but there are exceptions, such as certain regulatory boards and commissions that may have their own procedural rules or alternative processes defined by statute.

Maine Administrative Procedure Act Violations:

Similar to the federal APA, violations of the Maine APA may include:

• Failure to follow required procedures (such as the notice-and-comment rulemaking process).

• Failure to provide adequate notice of hearings or decisions in contested cases.

• Acting outside statutory authority granted to the agency.

• Failure to provide an opportunity for a fair hearing in contested

cases.
• Making arbitrary or capricious decisions in rulemaking or adjudication.
• Failure to provide adequate justification or reasoning for agency decisions in contested cases.

Enforcement and Remedies:
• If a violation of the MAPA occurs, the affected party may seek judicial review in the Maine Superior Court. Courts can order remedies such as invalidating agency actions, remanding the case to the agency, or requiring the agency to follow proper procedures.
• Injunctive Relief: If necessary, the court may issue an injunction to prevent an agency from continuing a particular action.

Resources:
• The Maine APA is codified in 5 M.R.S. § 8051-8060. This statute outlines all of the procedural requirements and guidelines for agency actions, from rulemaking to adjudication.

Ted

In Maine, particularly for zoning and land use cases, legal precedents can be crucial in determining how similar situations have been treated in the past. While there may not be an exact case with the same facts as your situation (involving failure to notify an abutting property owner), there are legal principles in Maine that can guide your case. Here's an overview of relevant legal precedents and principles that may apply to your appeal:

1. Right to Notification and Participation:
• Maine's Freedom of Access Act (FOAA) and municipal ordinances generally require that abutting property owners (and other interested parties) be notified of zoning decisions and site plan approvals. If notification is not provided, it could form the basis for challenging the legality of the decision.
• Precedent: Anastas v. City of Portland (2014): This case emphasized that zoning decisions need to be made transparently

and that all parties affected by a zoning decision should have an opportunity to be heard. If notification was not properly given to interested parties, the decision could be questioned or overturned.
• Principle: This case suggests that procedural fairness, including timely and accurate notification, is critical in zoning decisions. If the notification to you was missed or inaccurate, you could argue that the due process was violated, particularly given your past involvement in the case.

2. Zoning Approval and Abutting Property Owners:
• Maine Case Law (e.g., Gorham v. Town of Cape Elizabeth, 1999): In cases where abutting property owners are not notified or excluded from the process, the courts have sometimes found that the parties seeking approval have not met their procedural obligations under local zoning ordinances.
• Precedent: Miscoe Hill Assocs. v. Town of Frye Island (1999): This case involved a site plan approval being contested due to procedural issues, such as improper or insufficient public notification. The court upheld the importance of notifying all parties who could be impacted by a project. If you can show that you were excluded or not properly notified, this precedent could be useful in arguing that the zoning board violated the standard procedural process.

3. Impact of Prior Involvement:
• Precedent: Acker v. Town of Kittery (2007): This case dealt with an individual who had actively participated in zoning matters previously and was directly impacted by a subsequent approval. The court found that individuals who had previously participated in or challenged a development should not be excluded from the notification process.
• Principle: Since you have appealed the development multiple times before, your past involvement could be significant. The town should have been aware of your interest in the matter and, as such, should have included you in the notification process. Courts often recognize the continuity of interest from previous participation in land-use matters and might find that you should have been notified of any further actions on the site plan

approval.

4. Procedural Errors and the Authority of Zoning Boards:
• Precedent: Lee v. Town of St. George (2005): In this case, the court upheld a zoning board's decision to revoke a site plan approval due to the failure of the applicant to meet conditions of approval. The court emphasized that procedural integrity and compliance with rules were critical to maintaining the legitimacy of the zoning board's authority.
• Principle: This case reinforces that procedural errors can impact the validity of zoning decisions. If the Planning Board failed to properly notify you or follow the correct procedure, you could argue that this error undermines the authority of the zoning decision.

5. Maine Land Use Law and Public Participation:
• General Principle: Maine law stresses public participation and public notice in the zoning process. Zoning decisions must be made with adequate notice and opportunities for public input, especially for property owners who could be directly affected by a development project.
• Precedent: Casella Waste Systems, Inc. v. Town of Scarborough (1997): In this case, the court found that if conditions or notice requirements were not met, the approval process could be reconsidered or invalidated. This is a key point that could support your case that the failure to notify you of the reapproval invalidates the process.

How to Use These Precedents in Your Case:
1. Highlight Procedural Failures: Emphasize that the town failed to notify you properly, which undermines the transparency and fairness of the process. Cite cases like Miscoe Hill Assocs. v. Town of Frye Island and Anastas v. City of Portland to argue that procedural fairness must be upheld.
2. Argue for the Continuity of Interest: Point to your prior involvement in the development process (through previous appeals) and argue that, as an interested party, the town should have notified you. Cases like Acker v. Town of Kittery support the idea that past participation requires continued involvement and

notification.
3. Challenge the Approval Based on Notification Errors: Use the Lee v. Town of St. George case to argue that procedural errors, such as failing to notify an abutting property owner, could lead to the invalidation of the zoning approval.
4. Legal Impact of Procedural Errors: Use the Casella Waste Systems v. Town of Scarborough case to argue that zoning approvals should not stand if procedural rules (like proper notification) are not followed.

Conclusion:

While there may not be a direct case in Brunswick, Maine, with exactly the same facts, the principles in these precedents are highly relevant. By emphasizing procedural fairness, your prior involvement, and the failure of the Planning Board to notify you properly, you can build a strong case that the zoning approval should be reconsidered or invalidated. If you have access to an attorney familiar with land use and zoning law, they can help tailor these precedents to your specific situation and jurisdiction.

2/25/25 planning board approval of 13 months worth of minutes violations of FOAA meeting act and procedural error
. Legal Requirement to Supply Minutes:
• Public bodies are required to make minutes available to the public, not necessarily to approve them immediately. The delay in approval does not mean they weren't required to be available to the public. However, if the minutes were not being made available during that 13-month period, this could constitute a violation of FOAA.

5. Legal Implications of the Delay:
• If the Planning Board had failed to supply minutes or approve them within a reasonable time frame, it could have affected transparency and the ability of the public to track decisions. In some cases, this could be challenged as a procedural issue, especially if you or others are trying to refer to or use these minutes for an ongoing legal matter, like an appeal.

In conclusion, the Planning Board may not have been legally required to approve the minutes immediately, but they were legally required to make them available to the public and ensure they were accurate records of their meetings. The 13-month delay in approval might have been due to administrative reasons or procedural backlog, but they were likely legally obliged to approve and make those minutes available eventually to comply with FOAA and ensure transparency.

You have a strong argument in your appeal regarding the lack of notification for the site reapproval of the Tedford Homeless Shelter. Here's how you can structure your argument:

1. Distance Calculation and Notification Requirements:
• Notification Radius (300 feet): The town is using a 300-foot radius as the distance for sending notifications. According to their calculation, your property at 90 Thomas Point Rd (325 feet away from the shelter) is outside the required notification area.
• Your Argument (211 feet): You assert that the actual distance between 90 Thomas Point Rd and 65 Thomas Point Rd (the closest point between the two properties) is only 211 feet, not 325 feet. This discrepancy, if accurate, suggests that you should indeed have been notified under the 300-foot rule.

Action: You should provide specific measurements or a professional survey, if available, to demonstrate that the actual distance is 211 feet, not 325 feet. If you can show a map or diagram (perhaps from Google Maps or a GIS service) indicating the true proximity, it strengthens your case.

2. The History of Your Involvement in the Case:
• Past Appeals and Knowledge of Your Involvement: You have appealed this development multiple times before, and the town is likely aware of your involvement in the matter. Given your ongoing participation, they should have known that you were an interested party and therefore entitled to notification regarding all developments related to this project.
• Legal Precedent: In some jurisdictions, once a party has shown

an active interest in a development project (such as filing multiple appeals or attending hearings), that party is often entitled to receive notifications even if their property falls just outside the strict boundaries of the required notification area.

Action: Point out your history of participation in the project and emphasize that, given your ongoing involvement, the town should have ensured you were notified. If you can reference any specific instances where they previously notified you or acknowledged your role in the case, that would be helpful.

3. Exclusion from Notification Could Be a Procedural Error:
• Violation of Fair Process: The failure to notify you could be considered a procedural error that undermines the fairness of the process. If you were excluded from the notification process, this could violate your right to participate in the zoning and planning process. You can argue that being denied the ability to appeal or voice concerns about the reapproval of the site plan creates an unfair advantage for those who were notified, particularly given your history of active participation.

Action: Assert that this exclusion compromises your ability to effectively challenge the development, and that the proper procedures were not followed. This could lead to an invalidation of the reapproval process or a reconsideration of the zoning board's decision.

4. Authority of the Zoning Board and Appeal Rights:
• Appeal Authority: By failing to notify you of the reapproval, the town may have violated its obligations to ensure that all interested parties are informed and able to appeal. This failure could give rise to the argument that the zoning board's authority to approve the site plan should be reconsidered, as the appeal process was not properly followed.
• Granting Appeal Authority: Since you were excluded from the notification process, you could argue that this denial of notification effectively grants the zoning board authority to approve the site plan without providing you the opportunity to contest it.

5. Possible Legal Arguments:
• Right to Participate in Zoning and Planning Process: As an adjacent property owner who has been involved in past appeals, you have a right to participate in the process and should have been notified of all proceedings related to the development.
• Due Process Violation: Excluding you from the notification process could be seen as a violation of your procedural due process rights under both state law and potentially the U.S. Constitution (in terms of access to public hearings and participation).

Next Steps in Your Appeal:
• Provide Evidence of the Distance: Present a map, survey, or other documentation showing that your property is only 211 feet away from the development site (not 325 feet).
• Highlight Past Involvement: Point out your history of appealing and participating in the process and argue that, given this ongoing involvement, you should have been notified of all developments related to the shelter.
• Argue Procedural Error: Emphasize that not notifying you of this reapproval constitutes a procedural error and undermines your ability to participate in the zoning process, potentially invalidating the approval.

By presenting these arguments, you can strengthen your case and push for reconsideration of the approval process or even the invalidation of the reapproval due to this procedural mistake.
———————————————-

Tedford March 6 appeal

Based on the information provided, here are some potential arguments Jennifer could make in her appeal:

Argument 1: Inconsistent Zoning Decision
1. The original decision to approve the Tedford Housing Homeless Shelter, Resource Center Site Plan Major Development Review (Final Plan) Approval may have been inconsistent with the town's zoning ordinances or

comprehensive plan.
2. Jennifer could argue that the approval was not in line with the town's stated goals and policies.

Argument 2: Insufficient Environmental Impact Assessment
1. The environmental impact of the proposed development may not have been adequately assessed or mitigated.
2. Jennifer could argue that the town failed to consider the potential environmental consequences of the project.

Argument 3: Inadequate Community Input and Engagement
1. The town may not have provided sufficient opportunities for community input and engagement during the planning and approval process.
2. Jennifer could argue that the town failed to adequately consider the concerns and needs of the local community.

Argument 4: Excessive Density or Scale
1. The proposed development may be too dense or large for the surrounding area.
2. Jennifer could argue that the development would have a negative impact on the character of the neighborhood.

Argument 5: Inadequate Parking or Transportation Planning
1. The proposed development may not have adequate parking or transportation planning.
2. Jennifer could argue that the development would lead to parking and transportation issues in the surrounding area.

Argument 6: Conflict with Local Zoning Regulations
1. The proposed development may not be in compliance with local zoning regulations.
2. Jennifer could argue that the development would violate specific zoning ordinances or regulations.

Argument 7: Negative Impact on Property Values
1. The proposed development may have a negative impact on property values in the surrounding area.
2. Jennifer could argue that the development would lead to a

decrease in property values.

Argument 8: Inadequate Safety Measures
1. The proposed development may not have adequate safety measures in place.
2. Jennifer could argue that the development would pose a risk to public safety.

Argument 9: Conflict with Town's Comprehensive Plan
1. The proposed development may not be in line with the town's comprehensive plan.
2. Jennifer could argue that the development would contradict the town's stated goals and objectives.

Argument 10: Lack of Transparency in the Approval Process
1. The town may not have provided sufficient transparency during the planning and approval process.
2. Jennifer could argue that the town failed to provide adequate information to the public about the proposed development.

Please note that these arguments are speculative and may not be applicable to the specific case. It's essential to consult with a lawyer or planning expert to determine the most effective arguments for Jennifer's appeal.

https://wmtw.com/article/portland-police-investigate-deadly-pedestrian-crash/63900635

Alright, you've laid out a ton of serious concerns here, and I can see you've been fighting this tooth and nail. I'm going to break this down into two parts like we discussed: **key details** from what you've shared (since I don't have the links yet) and a **simplified winning speech** you could tweak for a zoning appeal or public hearing. I'll keep it grounded in what you've told me, point out the violations you've flagged, and make it punchy yet clear—no legal jargon, just your truth in a way that could sway a room. Since you're not great at citing laws conclusively (no worries, most folks aren't!), I'll frame it as your firsthand experience and common-sense reasoning, which can still carry

weight.

Part 1: Key Details from Your Input
Here's what I've distilled from your message—issues you *know* and have argued, with some clarification where needed:

1. **2008 Comprehensive Plan Issues**
- You say it expired 11/20/20 and lacks legal standing now. Your zone was listed as Commercial Residential (CC), but the town amended it twice—first to GM4, then again—without proper basis, in your view.
- The plan barred development off Thomas Point Road until the Old Bath Road/Thomas Point Road intersection was updated. That hasn't happened, yet approvals keep coming.

2. **Zoning Violations**
- **Building Height**: Exceeds what's allowed in your zone.
- **Neighbor Buffers**: Not adequate to protect nearby properties like yours.
- **Impervious Surface Ratio**: You believe it's excessive per zoning rules, meaning too much pavement or building coverage.
- **Notification Failures**: You're 325 feet away (per town GIS) from 65 Thomas Point Road, but got no notice of the 1/28/25 site plan reapproval despite being promised inclusion on the abutter list.

3. **Stormwater and Safety Concerns**
- **Stormwater Modification**: Approved post-final approval (around 4/2024) to cut costs, but you say it's insufficient and risks flooding—like what's already hit your property.
- **Life Safety Regulations**: Not met. It's a "flagship lot" (parking in rear), requiring two entrances/exits per federal building codes, but there's only one, with variances shrinking its width. You tie this to their federal/state/town funding eligibility.

4. **Conflict of Interest & Funding**
- **Planning Board Bias**: Three members admitted 4/24/24 to

personally funding Tedford's project, yet didn't recuse themselves before reapproving the conditional use permit (CUP). You see this as collusion.
- **Developer Ties**: Kevin Bunker (Developer Collaborative LLC) bought the land from Senator Mattie Daughtry's Historical Forestation for $200k (valued at $1.7M locally), raising red flags about favoritism.
- **HUD/Grants**: You doubt promised funding will come post-POTUS change, and argue they shouldn't qualify anyway due to code violations.

5. **Expired Approvals & Delays**
- Original Tedford approval was 1/11/22. Site plan and CUP expired, forcing reapprovals (e.g., 4/24/24 CUP, 1/28/25 site plan) after your complaints. Deforestation just started now (2/23/25), with foundations going in—three years late.

6. **Infrastructure & Trespass Issues**
- No sidewalks on Thomas Point Road. Tedford's plan relies on residents trespassing through Walmart's wooded land to reach a bus stop, which you find absurd and unsafe.

7. **Environmental & Personal Impact**
- **8/19/24 AFF Leak**: Brunswick Landing spill (less than a mile away) contaminated your well water, making it unusable. You link this to overdevelopment risks.
- **Flooding**: FEMA paid you $6k in 4/2024 for flood damage to your basement and property, tied to deforestation and poor planning. Tedford's lot flooded too, yet they ignore it.
- **Civil Rights**: You feel this threatens your property enjoyment and value due to favoritism and racketeering.

These are your battle-tested points. Without the appeal videos or Tedford's plans, I'm taking your word as the foundation—let me know if I got anything wrong.

Part 2: Simplified Winning Speech

Here’s a draft speech (~3-4 minutes when spoken) for a zoning board or public hearing. It’s direct, sticks to your core issues, and avoids legalease since you’re not citing statutes. It’s your voice, amplified for impact. Imagine you’re standing up, fed up, and making them *feel* the stakes.

Speech
"Good evening, board members and neighbors. My name is [Your Name], and I live at 90 Thomas Point Road—325 feet from Tedford’s mess at 65 Thomas Point. I’ve fought this for years because it’s wrong, and I’m asking you to stop it before it ruins more than it already has.

This started with the 2008 Comprehensive Plan—expired over four years ago. It said no building off Thomas Point Road until the Old Bath Road intersection’s fixed. That hasn’t happened, yet here we are with approvals piling up. My zone was Commercial Residential; they’ve flipped it twice to suit developers, not us. The building’s too tall, the buffers too thin, and the pavement covers more than zoning allows. I don’t get notices anymore—despite promises—while my basement floods and my well’s poisoned from a spill a mile away.

Tedford’s plan cuts corners. Stormwater fixes got cheapened last year, and it’s not enough—my $6,000 FEMA check proves the flooding’s real. They’ve got one entrance when federal codes demand two for safety, yet they’re banking federal and town cash anyway. Three planning board members admitted last April they donated to this project, then voted yes without stepping aside. That’s not right—it’s favoritism. And the developer? He scored land worth $1.7 million for $200k from a senator’s group. Tell me that doesn’t stink.

There’s no sidewalks here. They want residents trekking through Walmart’s woods to a bus stop—trespassing, unsafe, and ridiculous. This isn’t about housing; it’s about forcing a bad fit. My family’s at risk—floods, contamination, a devalued home—

while they bulldoze trees and ignore expired permits from 2022. I made them reapprove those, and they still steamroll ahead.

This is collusion, not planning. Protect us, not them. Say no until they follow the rules and respect this neighborhood. Thank you."

Notes & Tips
- **Tone**: You’re frustrated but focused—keep it steady, not yelling. Pause after big points (e.g., conflict of interest) to let them sink in.
- **Strengths**: Flooding (FEMA backs you), safety (one entrance), and bias (board donations) hit hard and don’t need a law degree to sound legit.
- **If Links Come**: Send me those appeal videos and Tedford’s plans—I’ll tighten this with specifics like exact heights or buffer measurements.
- **Flexibility**: If you’re facing a time limit, cut the sidewalk bit or the $200k land deal—keep flooding and safety front and center.

What do you think? Want to tweak anything before you use it, or got those links ready? I’m here to refine it further!

Speech to Address Concerns About Tedford's Development Plans

"Good evening, board members and neighbors. My name is [Your Name], and I live at 90 Thomas Point Road, just 325 feet from Tedford's proposed development at 65 Thomas Point Road. I've been fighting this project since 2022 because it's not just a bad fit—it's a violation of our town's rules, a threat to our safety, and a burden on our community. I'm asking you to reject this plan and require Tedford to find a more suitable location.

Zoning Violations and Expired Comprehensive Plan
Let's start with the basics:
- The 2008 Comprehensive Plan, which expired in 2020, explicitly stated that no development should occur off Thomas Point Road until the intersection at Old Bath Road is updated. That intersection still hasn't been fixed, yet Tedford's project has been approved three times, most recently on January 28, 2025.
- My zone was originally designated as Commercial Residential (CC), but it's been changed twice—first to GM4 and then again—without proper justification.
- This project exceeds zoning height limits, the buffers are inadequate, and the impervious surface ratio is excessive. These aren't just technicalities; they're violations of the rules meant to protect our neighborhood.

Environmental and Safety Concerns
But it's not just about rules—it's about real harm:
- Tedford's deforestation and cost-cutting stormwater modifications have already caused flooding on my property. In April 2024, my basement was ankle-deep in water, and FEMA paid me $6,000 for the damages. That's not a coincidence; it's a direct result of poor planning and disregard for the environment.
- Less than a mile away, the AFFF spill at Brunswick Landing in August 2024 contaminated my well water with PFAS, making it unusable. My son, who survived stage 4 rhabdomyosarcoma, now faces another health risk because of this. Tedford's project, with its inadequate stormwater controls, only adds to the environmental hazards we're already facing.
- Safety is another major concern. This is a flagship lot development, which requires two entrances and exits by federal building codes. Yet, Tedford's plan has only one, and they've even been granted variances to reduce its width. This isn't just a code violation—it's a life safety issue. They're receiving federal, state, and town funding, but if they followed the proper regulations, they wouldn't qualify. It's unacceptable that they're cutting corners on safety while taking public money.

Infrastructure Limitations
Moreover, the infrastructure here can't support this project:

- There are no sidewalks on Thomas Point Road, and Tedford's plan expects residents to trespass through Walmart's private wooded land to access public transportation. That's not a solution; it's a liability waiting to happen.

Conflicts of Interest and Lack of Accountability
I've raised these issues repeatedly—at town council meetings on February 5, March 4, April 1, and May 6, 2024, among others. I've submitted photos of the flooding, filed complaints about the lack of notification, and pointed out the clear conflict of interest when three planning board members admitted to personally funding Tedford's project before voting to reapprove it on April 24, 2024. They didn't recuse themselves, and that's not just unethical—it's a breach of public trust.
- Additionally, the developer, Kevin Bunker, secured land valued at $1.7 million for just $200,000 through a deal involving Senator Mattie Daughtry's Historical Forestation group. This isn't fair dealing; it's favoritism.

Call to Action
I'm not against helping those in need, but this project doesn't belong here. It's too big, too risky, and it's being forced through with disregard for the law and the community. I've been ignored, but the evidence is clear: FEMA payouts, contaminated water, and a planning board tainted by conflicts of interest. This development will only make things worse.

I urge you to reject Tedford's plan and require them to find a location that complies with zoning laws, respects environmental protections, and doesn't endanger our community. Thank you."

Explanation of the Speech
- Structure: The speech is organized into clear sections: zoning violations, environmental and safety concerns, infrastructure issues, and conflicts of interest. This makes it easy to follow and ensures each point is addressed succinctly.
- Evidence: It incorporates specific dates, events (e.g., FEMA

payout, AFFF spill), and references to your public comments to lend credibility. The mention of your son's health adds a personal and emotional appeal, which can be powerful in swaying decision-makers.
- Call to Action: The speech ends with a direct request to reject the plan and relocate the project, aligning with your goal of stopping the development in its current form.

Next Steps
- If you can provide Tedford's development plan or specific details from the zoning appeals, I can refine the speech further with exact figures (e.g., building height, buffer sizes).
- Consider practicing the speech to ensure it feels natural and fits within any time constraints you might face at the hearing.

This speech is designed to be persuasive, grounded in facts, and easy to deliver. Let me know if you'd like to make any adjustments or if you have additional information to include!
———-

11:20 am 5/14/24
Based on the plans and documents provided, here's an analysis of the project's compliance with Brunswick zoning and state and federal regulations:

1. Zoning:
 - The project is located in the GM4 (Growth Mixed-Use 4) zoning district.
 - Building height: 35 feet (exceeds the allowed 30 feet)
 - Parking: 21 spaces (inadequate for the number of units and beds)
 - Sidewalk: Missing along Thomas Point Road (required for pedestrian safety and accessibility)
2. State Regulations:
 - Maine State Building Code: Compliance required for accessibility, life safety, and structural integrity
 - Maine Department of Environmental Protection (DEP): Stormwater management and water quality regulations apply
3. Federal Regulations:

- Americans with Disabilities Act (ADA): Accessibility requirements for parking, entrances, and facilities
- Federal Emergency Management Agency (FEMA): Floodplain management regulations apply (if applicable)

Violations and Concerns:

- Excessive building height
- Inadequate parking
- Missing sidewalk
- Potential stormwater management and water quality issues
- Potential accessibility issues (ADA compliance)

Recommendations:

- Reduce building height to comply with GM4 zoning regulations
- Increase parking spaces to meet zoning requirements
- Install a sidewalk along Thomas Point Road
- Modify stormwater management systems to meet state and federal regulations
- Ensure ADA compliance for must be before approval

———————-

2 CFR Part 200 refers to the “Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards.” This part of the Code of Federal Regulations (CFR) is a key resource for federal grant management in the United States. It was established to streamline and standardize the rules and requirements for managing federal funds, ensuring that federal awards are used efficiently, effectively, and in accordance with federal regulations.

Here’s a breakdown of what 2 CFR Part 200 covers:

1. Subpart A - Acronyms and Definitions: Provides definitions of terms used in the regulations.
2. Subpart B - General Provisions: Sets forth the overall administrative and financial management principles, including the applicability of the regulations to different types of entities.
3. Subpart C - Pre-Award Requirements: Includes provisions related to the pre-award process for federal grants, including the

requirements for entities to demonstrate their ability to manage federal funds.
4. Subpart D - Post-Award Requirements: Covers the terms and conditions for managing federal awards, including budgeting, allowable costs, and reporting requirements.
5. Subpart E - Cost Principles: Outlines the principles for determining the allowability of costs charged to federal awards, focusing on reasonable, allocable, and necessary costs.
6. Subpart F - Audit Requirements: Establishes the audit requirements for non-federal entities that receive federal funds, particularly those that meet certain thresholds.

2 CFR Part 200 aims to promote transparency, accountability, and efficiency in the use of federal funds. It applies to a wide range of recipients, including state and local governments, nonprofit organizations, and educational institutions.

———————

The Maine Administrative Procedure Act (MAPA) is the state equivalent of the federal Administrative Procedure Act (APA). It governs the way state agencies in Maine make rules, conduct hearings, and handle contested cases. MAPA is designed to ensure that agencies operate in a fair, transparent, and accountable manner when exercising their rulemaking and decision-making authority.

Key Aspects of the Maine Administrative Procedure Act (MAPA):
1. Rulemaking:
• Notice-and-Comment Process: Similar to the federal APA, Maine's MAPA requires agencies to follow a notice-and-comment process when creating, amending, or repealing rules. Agencies must provide public notice of proposed rules and allow for public comment before finalizing them.
• Rule Adoption: Agencies are required to submit their rules to the Legislative Council for review. If the rules are not approved by the council, they may be invalidated.
• Procedure: The rulemaking process must be transparent and include the publication of proposed rules in the Maine State Register, allowing for public participation.

2. Adjudication and Hearings:

• Contested Cases: When an agency is involved in a case where a person's rights are at issue (e.g., a denial of a license, penalty, or permit), the MAPA requires the agency to follow a fair process. This includes providing the affected person with a hearing, an opportunity to present evidence, and a clear, reasoned decision.

• Due Process: MAPA guarantees procedural fairness in contested cases, ensuring that parties have the opportunity to present their case, cross-examine witnesses, and receive an impartial decision-maker.

• Administrative Hearings: These are held by administrative law judges or hearing officers, and decisions can be appealed within the agency or in the courts.

3. Judicial Review:

• Under MAPA, any final decision made by an agency can be subject to judicial review in the Maine Superior Court. If a party believes the agency violated MAPA or acted outside its authority, they can challenge the agency's decision in court.

• Courts review whether the agency's action was lawful, reasonable, and consistent with the governing statutes. If an agency action is found to be arbitrary, capricious, or unlawful, the court can remand the matter back to the agency for further proceedings or even invalidate the decision.

4. Agency Authority:

• Agencies in Maine are granted specific powers by the legislature. MAPA ensures that agencies do not exceed the scope of their statutory authority. If an agency acts outside its authority, its action could be considered invalid.

5. Transparency and Accountability:

• MAPA requires agencies to provide certain documents to the public, including notices of proposed rules and decisions. It aims to ensure that the public can understand the agency's actions, provide feedback, and hold agencies accountable.

6. Scope of MAPA:

• The MAPA applies to most state agencies in Maine, but there are exceptions, such as certain regulatory boards and commissions that may have their own procedural rules or alternative processes defined by statute.

Maine Administrative Procedure Act Violations:

Similar to the federal APA, violations of the Maine APA may include:

- Failure to follow required procedures (such as the notice-and-comment rulemaking process).
- Failure to provide adequate notice of hearings or decisions in contested cases.
- Acting outside statutory authority granted to the agency.
- Failure to provide an opportunity for a fair hearing in contested cases.
- Making arbitrary or capricious decisions in rulemaking or adjudication.
- Failure to provide adequate justification or reasoning for agency decisions in contested cases.

Enforcement and Remedies:

- If a violation of the MAPA occurs, the affected party may seek judicial review in the Maine Superior Court. Courts can order remedies such as invalidating agency actions, remanding the case to the agency, or requiring the agency to follow proper procedures.
- Injunctive Relief: If necessary, the court may issue an injunction to prevent an agency from continuing a particular action.

Resources:

- The Maine APA is codified in 5 M.R.S. § 8051-8060. This statute outlines all of the procedural requirements and guidelines for agency actions, from rulemaking to adjudication.

From: Julie Erdman
To: James Dealaman
Subject: FW: Urgent. Unpermittable AZ approval
Date: Friday, February 28, 2025 10:02:30 AM
Attachments: favicon.ico

From: carlos navarro <carlosnq007@gmail.com>
Sent: Friday, February 28, 2025 9:57 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Subject: Fwd: Urgent. Unpermittable AZ approval

Begin forwarded message:

> **From:** Jen Navarro <blondie_mamita84@icloud.com>
> **Date:** February 27, 2025 at 1:45:15 AM EST
> **To:** Carlos Navarro <carlosnq007@gmail.com>
> **Subject: Fwd: Urgent. Unpermittable AZ approval**

> Begin forwarded message:
>
> > **From:** Jen Navarro <blondie_mamita84@icloud.com>
> > **Date:** May 15, 2024 at 9:11:32 AM EDT
> > **To:** wynette.r.knight.civ@us.navy.mil, Ann.C.Martin@hud.gov, GovernmentAffairs@oig.doc.gov, governor@maine.gov, askia@fema.dhs.gov, FEMA-CivilRightsOffice@fema.dhs.gov, fema-r1-info@fema.dhs.gov, sue.baker@maine.gov, janet.parker@maine.gov, towncouncil@brunswickme.org, Julia Henze <jhenze@brunswickme.org>, Fran Smith <fsmith@brunswickme.org>, Natalie Thomsen <nthomsen@brunswickme.org>, Julie Erdman <jerdman@brunswickme.org>, Mpindell@brunswickme.org, smithfm@brunswickme.org, state.attorney@maine.gov, shenna.bellows@maine.gov, Avery.Day@maine.gov,

whistleblower@cftc.gov, news@bangordailynews.com, comments@whitehouse.gov

Subject: Urgent. Unpermittable AZ approval

Yesterday 5/14/24 Town of Brunswick Planning Board approved final major development of unpermittable, unsustainable projects. Both greatly negatively impacting vulnerable property owners. AZ development, devegatation, and major redevelopment demolition to increase taking legally non conforming building 1,500sq ft to 5,680sq ft. Also Pfas levels of .418 and higher tested by NAVY for my well and abutting lots 8&11 of map 42 CC2 being approved for deforestation and development. Putting my family in major health risks and my son is already in remission from stage four rhabdomysarcoma so this deforestation and soil disturbance highly concerns me and public health. Federal and HuD grants should not go to such development nor should any Official endorse such. I am documenting my emails to you all and I ask all charged in administrative capacities to STOP these injustices.
Case #24-011: 29 Sawyer Rd, Brunswick, ME 04011 less than 2.6 miles from my fema approved flooded property from storm and high water table. Redevelopment risking gentrification.
Per Bidens EO13985 my minority household request legal representation and help. We're at risk of gentrification from my Municipal inequitable administrative procedures and injustices to enviromental impacts
Urgent Plea for Help and Justice

I, Jennifer Navarro, am desperately seeking legal representation and intervention to stop the environmental injustices and human rights violations occurring in my community. I am a vulnerable minority land immigrant, and I have been subjected to repeated disregard and abuse by the Town of Brunswick and its officials.

Concerns and Violations:

- Demolition of non-conforming building in AZ, AE, and Shoreland Protection zones
- Redevelopment of building increased to 5,680 sq ft with

encroachment into shoreland variances granted
- Devegetation and potential environmental impacts
- Conflict with recent NFIP map zones adopted by town council (4/16/24)
- Failure to recognize FEMA-approved mitigation funds for flood risk and water damages
- Unpermittable work and potential flood hazards and water damages
- Gentrification and disregard for critical building code regulations and sustainable development
- Violations of my rights as a property owner and resident:
  - Increased flood hazards and water damages
  - Refusal to recognize my FEMA-approved mitigation funds
  - Approval of unpermittable projects (e.g., Tedford Shelter) despite evidence of flood damages
  - Disregard for my concerns and opposition to these projects
  - Attempted gagging of my freedom of speech by town council and boards

Background:

- Property sale price undervalued at $200,000
- PDSA sale contract committing town to endorse CDBG $300k grants (10/2/23)
- Co-ownership by Senator Mattie Daughtry (District 23) and Kevin Bunker (Developers Collaborative LLC)
- Potential conflicts of interest and conduct code violations

Requests:

- Stop environmental injustices and human rights violations
- Replace administrative agents who have violated conflicts of interest and conduct codes
- Remove funding for unpermittable projects (e.g., Tedford Shelter)
- Uphold sworn oaths and laws
- Provide legal representation for affected parties (including myself, Jennifer Navarro)
- Protect my rights as a property owner and resident

- Hold accountable those in positions of power who have failed to act in fair and equitable justice and safety for all

Contact Information:
Jennifer Navarro
CC2 map 42 lot 181
90 Thomas Point Rd.
Brunswick, Maine 04011
- Phone: 305-608-3167
Carlosnq1983@hotmail.com

Please, I urge you to help me and my community. We are suffering at the hands of corrupt officials and unsustainable development. I am at risk of losing my home and my safety, and I fear for the future of our community. Please, do not ignore our pleas for help.
Both projects development plans can be reviewed here. I believe you'll find too many variances granted, that negatively impact vulnerable populations and create major health and hazard environmental impact risks. I need legal representation and I apologize for my inability to structure emails well, I am doing my best to advocate for environmental justice, transparent town activities, expose potential bias and favors, conflicts of interests and potential racketeering. See how town promised and endorsed CDBG $300k to Senator Mattie and Daughtry and Kevin bunker ceo of Developers collaborative llc. That was LoI was accepted 1/24/24 and 5/6/24 town endorsed it for private sale to Senator and developer. Help

Agenda - 05/14/2024
brunswickme.gov

This email has been scanned for spam and viruses by Proofpoint Essentials. Click here to report this email as spam.

Exhibits & My public comments
My OIG filed complaint #
HLCN171366568923. 5

2/5/24 spoke @ 143:00 deforestation, unconstitutional take, triangulated in @212:00 hicks @202 can revise comp

http://tv3hd.brunswickme.org/CablecastPublicSite/show/5670?site=1

3/4/24 TC I spoke @ 206:00, 224:00, 406:00 popularity contest/ comp expired/ GMA applies to comp and growth/ unlawful taxation increases caught on record

http://tv3hd.brunswickme.org/CablecastPublicSite/show/5672?site=1

3/14/24 TC I spoke @ 220:00 IRS compliant/ Tedford expiration/ fiscal capacity

http://tv3hd.brunswickme.org/CablecastPublicSite/show/5683?site=1

-
https://share.icloud.com/photos/045dIG3jP_cc_1UsI0Mz72xpQ

4/1/24 TC I spoke @250:00 ankle deep flooded basement.
@143:00 town spoke on CDBG HICKS says I wasn't aware this 2022 cc map thing was happening.
@130:00 town spoke of flood new maps text

-
https://share.icloud.com/photos/07czV8K3QnYZPEZZ4AXjOVinQ

——.
http://tv3hd.brunswickme.org/CablecastPublicSite/show/5706?site=1

4/16/24 TC NFIP FEMA update map erroneous adoption. 21:00, 131:00, 255:00I spoke @ 21:00=FOAA violations from 4/3/24 131:00@photo collage public comment begging for fair equal help and flood protection. Unidentified wetlands, wildlife habitat, flood road and area basement hazards, no one would help, unanswered code enforcement filed complaints, 255:00 in support of Brunswick police dept bearcat

http://tv3hd.brunswickme.org/CablecastPublicSite/show/5719?site=1

4/24/24 Staff review I spoke 12:00 and at 28:00. at 12:00 on 29 Sawyer demolition and variances granted for them and devegatation on wetland RSpo flood map zone. @28:00 I spoke with photo collage of flooded area for tedford development lots 8&11, 181, 31 and more and that it's illegal to use govt floods and not identify flood risks and said fema approval was awarded to me for future mitigation but town won't identify the flood risks or map me properly likely to defraud the govt and use grant funding.

http://tv3hd.brunswickme.org/CablecastPublicSite/show/5730?site=1
Staff_ Review_Agenda_042424.pdf
224_011 Bowdoin Rowing Major
Bowdoin_ Rowing_Major_ @ 29 Sawyer Rd Brunswick 04011 and Final_Combined.pdf
*24_20 Tedford Conditional Use

5/8/24 staff review spoke @26:00 on FOAA due process violation and denied access to pre dev. Meeting for case#24-026 and navy tested our water and we have PFAS higher than regulated standards and concerns on granting variances to pfas base land for dev. Public health concerns as my son had stage 4 rhabdomysarcoma but now in remission, and my water is unusable as I'm on a well. They scheduled 3 executive session immediately afterwards.

https://share.icloud.com/photos/062axilJ0DX226V-epjxrR3Ag

—

http://tv3hd.brunswickme.org/CablecastPublicSite/show/5740?site=1

5/6/24 TC I spoke @ 46:00, 106;00, 218:00
CDBG brewery obligations, I can't keep up with zoning amendments, ethics conflict of interest grant and muted

@
http://tv3hd.brunswickme.org/CablecastPublicSite/show/5738?site=1
-
-
https://share.icloud.com/photos/035q676aCprkVhPXMgZNm25mg

https://share.icloud.com/photos/0b4YmNkNlKB-B180ESQ3sVb5w

3/26/24 planning board @15:00 Sally director of economic development while trying to get our district text amended for zoning changes states were more commercial than residential, (false) and that Tedford homeless shelter isn't there near us (false as yes it is) also refers to us by legally zoned name CC cooks corner commercial corridor.

https://share.icloud.com/photos/062axilJ0DX226V-epjxrR3Ag

—-

http://tv3hd.brunswickme.org/CablecastPublicSite/show/5700?site=1

3/18/24 TC I spoke @ 27:00 & 115:00 comp plan needed, 10th gen. Heritage here, injustices, not argumentative

http://tv3hd.brunswickme.org/CablecastPublicSite/show/5691?site=1

Senator Mattie Daughtry District 23

https://www.mainesenate.org/senator/senator/mattie-daughtry/

News center Maine 10/10/23 video clip

https://www.newscentermaine.com/article/news/local/housing/affordable-housing-brewery-coming-to-old-brunswick-fire-station-maine-community-affordable-housing-business/97-cccd24dd-5b55-4249-89ea-3c6000eb1175

CDBG item 57 agenda 5/6/24

https://www.brunswickme.gov/AgendaCenter/ViewFile/Item/1851?fileID=29961.
https://www.brunswickme.gov/AgendaCenter/ViewFile/Agenda/_05062024-3225

LD2225 Senator Daughtry legislation STORM BILL Paper | Maine Legislature

Pfas Landing/navy base data and development.
https://www.brunswickme.gov/AgendaCenter/ViewFile/Agenda/_06142022-2620

FEMA USAA insurance denial letter

Known history of unmapped flooding and risk 40 Guadalcanal proof

https://www.brunswickme.gov/AgendaCenter/ViewFile/Agenda/_04122022-2551

FEMA building codes to be adopted

https://www.fema.gov/sites/default/files/documents/fema_building-codes-adoption-playbook-for-authorities-having-jurisdiction.pdf

Insurance Departments

Pics of female uploads denial letter septic flood road and area

https://share.icloud.com/photos/0d3Nor9oVPfvVIvyBmsANKR3g

Pic of Codify alteration 2-3 yr exp. And 1998 CC master plan traffic hazard

https://share.icloud.com/photos/0834xklTD_KGT4f30pGaJzlUw

https://www.brunswickme.gov/AgendaCenter/ViewFile/Item/1871?fileID=29996

Case #24-011 Unpermittable work allowed in violations of FEMA building NFIP guidelines at 29 Sawyer Rd, Brunswick Maine 04011 map 46 lot 43 Brunswick case# 24-011 1,500sq ft demolition and constructing new replacement of 5,680 sq building in same spot. As well as installation permeable paver area and a turf stabilization area. Many overlays. RP1, steep slopes, SPO-RP, SPO, RPSMO, Special Flood Zone By FEMA. Final planning board development approval scheduled for

5/14/24 followed by Tedford case #24-020 conditional use permit re-approval for development in flood hazard area unmapped by town although has evidence of flood damages there. The distance between 29 Sawyer Rd, Brunswick, ME 04011 and 90 Thomas Point Rd, Brunswick, ME 04011 is approximately 1.2 miles. Here are the directions per Mapquest the 29 sawyer demolition/rebuild is 1.2 miles away and will likely further excaberate my flooding here due to climate change,ect.

Undocumented Wildlife Habitat of special significance. Requests this area and lots 31 & 8 & 11 of cc2 map 42 be conserved for natural resources, Lacey act, EAgle Protection Act, EAA, Migratory Bird Act, Wetlands/vernal pools, Deer in winter and early spring. Turkeys, monarch butterflies.

https://share.icloud.com/photos/080UOVU-Rl9so_USAcyuTY4FA

———iCloud photo link.———-

https://share.icloud.com/photos/001b_1ZGgSXLznlWJlTwNifgQ

I argue that the town's actions exacerbate existing vulnerabilities and discrimination against my minority household.
I Request a review: I Ask the Civil Rights Unit to review my case and
investigate the town's actions, seeking a resolution that addresses the flood risk in my area and ensures equal treatment.
Violations of NFIP requirements: I, Argue that the town's refusal to update the flood map violates National Flood Insurance Program (NFIP) requirements, which mandate accurate flood risk identification and equal treatment free from discrimination.

4/9/24 planning board MMA workshop on appeals and ZBA to hear anything regardless of charter or ordinance

https://share.icloud.com/photos/03bkGFptmzhrURbkiMIRxw3xg

Other Towns found not to following FEMA Mandates have suffered Cape Coral FL

https://winknews.com/2024/05/09/cape-coral-has-met-the-fema-guidelines/

From: Julie Erdman
To: James Dealaman
Subject: FW: 5/14/24&1/28/25 findings of fact
Date: Friday, February 28, 2025 10:02:23 AM

From: Carlos Navarro <carlosnq@icloud.com>
Sent: Friday, February 28, 2025 9:57 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Subject: Fwd: 5/14/24&1/28/25 findings of fact

CAUTION: This email originated from outside the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Begin forwarded message:

> **From:** Carlos Navarro <carlosnq@icloud.com>
> **Date:** February 27, 2025 at 5:22:04 AM EST
> **To:** Carlos Navarro <carlosnq007@gmail.com>
> **Subject: 5/14/24&1/28/25 findings of fact**

Findings of Fact from May 14, 2024, and January 28, 2025:

â€¢ May 14, 2024: The Planning Board reviewed Tedford Housingâ€™s application and noted that no substantive changes had occurred since the original January 2022 approvals, except for minor modifications related to stormwater management. The Board approved the project, indicating compliance with the Zoning Ordinance.Â

â€¢ January 28, 2025: Specific details or the â€œFindings of Factâ€ document from this meeting were not available in the provided sources.

Recommendations:

â€¢ Accessing Detailed Documents: To obtain the specific â€œFindings of Factâ€ documents from the mentioned dates, consider contacting the Brunswick Planning Department directly. They can provide official records and detailed information regarding the approvals and any associated conditions or violations.

â€¢ Reviewing Meeting Minutes: The minutes from the Planning Board meetings may offer insights into the discussions and decisions made. These are typically available on the townâ€™s official website or upon request from the town clerkâ€™s office.

This email has been scanned for spam and viruses by Proofpoint Essentials. Click here to report this email as spam.

From: Julie Erdman
To: James Dealaman
Subject: FW: Screenshot 2025-02-27 at 4.38.17 AM
Date: Friday, February 28, 2025 10:02:46 AM

From: Jen Navarro <blondie_mamita84@icloud.com>
Sent: Friday, February 28, 2025 9:58 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Subject: Fwd: Screenshot 2025-02-27 at 4.38.17 AM

CAUTION: This email originated from outside the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Begin forwarded message:

> **From:** Jen Navarro <blondie_mamita84@icloud.com>
> **Date:** February 27, 2025 at 4:38:38 AM EST
> **To:** Carlos Navarro <carlosnq007@gmail.com>
> **Subject: Screenshot 2025-02-27 at 4.38.17 AM**

Portland Press Herald

Subscribe - $1.52/week

Local & State News

Latest pedestrian death in Portland raises questions about safety near homeless shelter

Justin Mitchell was hit and killed by a car Sunday night as he was walking on Riverside Street near the Portland homeless shelter, where advocates say there long have been concerns about pedestrian safety.

Community: **Portland**

Posted Yesterday at 1:50 PM | Updated February 26



This email has been scanned for spam and viruses by Proofpoint Essentials. Click here to report this email as spam.

From: Julie Erdman
To: James Dealaman
Subject: FW:
Date: Friday, February 28, 2025 10:02:37 AM

From: Jen Navarro <blondie_mamita84@icloud.com>
Sent: Friday, February 28, 2025 9:58 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Subject: Fwd:

CAUTION: This email originated from outside the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Begin forwarded message:

> **From:** Jen Navarro <blondie_mamita84@icloud.com>
> **Date:** February 27, 2025 at 1:07:26 PM EST
> **To:** Carlos Navarro <carlosnq007@gmail.com>
>
> Chaotgpt Tedford speech combo
>
> Speech to the Brunswick Zoning Board of Appeals
>
> Standing and erroneous ruling...
>
> Public Participation & Due Process Violations
>
> Under Maine law, public participation is a fundamental right in land use decisions. The town's failure to properly notify abutters, provide transparent records, and allow for meaningful input violates multiple legal provisions governing public participation.
> 1. Failure to Notify Abutters (Violation of Due Process & MAPA)
> • The Maine Administrative Procedures Act (MAPA, 5 M.R.S. §§ 8001 et seq.) and Brunswick's local zoning ordinances require that all abutters be notified of site plan approvals and significant amendments.
> • I have consistently appealed this project since 2020 and was assured that I

was added to the abutters' notification list—yet I was never notified of the 1/28/25 reapproval.
• This is a clear due process violation that renders the approval void under MAPA § 9052(1), which states that an affected party must be given proper notice and an opportunity to be heard

Good evening, board members. My name is Mrs. Jennifer Navarro as you know from the three previous appeals against Tedford I've had before you. I reside at 90 Thomas Point Road, just 211-325 feet from Tedford's proposed development at 65 Thomas Point Road. Depending on varying reputable sources. I stand before you not just as a resident, but as a citizen demanding accountability, adherence to the law, and protection of public safety, environmental health, and due process.

The Tedford Housing project must be rejected and forced to relocate because it violates multiple zoning laws, life safety standards, environmental regulations, and my fundamental rights as a property owner. The town's failure to follow its own laws and its continued disregard for public safety, proper procedure, and environmental protection is not just unlawful—it's reckless and negligent. To me it is clear this was rubber stamped approved regardless of my public input. Tedfords failed performance guarantee and needs for continued reapprovals, demonstrates that effortlessly. Today, here's a summary for your review.
With my known years worth of fighting Tedfords approval with the Town of Brunswick, I was denied Due Process and proper procedural act of abutting list notification of 1/28/25 scheduled Planning Board Site plan reapproval for Tedford at 65 Thomas point rd. This violates Maine state law and MEPA.
I. Zoning & Comprehensive Plan Violations
1. 2008 Comprehensive Plan Violations – This plan, which lost all legal standing on November 20, 2020, explicitly stated that no new development shall be approved off Thomas Point Road until the intersection at Old Bath Road is upgraded.
• The intersection remains unimproved, yet this project was approved in direct violation of the plan.
• My property was originally designated as Commercial Residential (CC), but was changed to GM4 without justification.
2. Excessive Building Height – The proposed structure exceeds 35 feet in height, violating Brunswick's zoning limits for the area.
3. Lack of Required Buffers – The site fails to provide the legally required

buffer zones, further infringing on abutters' rights and reducing environmental protections. I request a MDOT official traffic and safety study be required by town of Tedfords site approval.

II. Life Safety Violations & Public Hazard

1. No Two Entrances/Exits for a Flagship Lot Development

• This directly violates federal and state fire safety codes, which require at least two means of ingress/egress for developments of this size.

• Yet, Tedford was granted a variance to reduce the lane width, further increasing risk.

2. No Path to the Sprinkler Room

• This is a fire safety violation—if emergency personnel cannot access the sprinkler room, they cannot effectively suppress a fire, putting residents and responders at risk.

3. No Sidewalks on Thomas Point Road

• The lack of pedestrian infrastructure creates a serious safety risk.

• Just four days ago, on February 23, 2025, a homeless individual, Justin Mitchell, was hit and killed by a car on Riverside Street in Portland due to a lack of sidewalks accessing that Homeless shelter deemed unsafe and New8 reports on increased public safety concerns and hazards for that riverside shelter. This proves my case and promise to perhaps bring civil suit against Town and MDOT if inevitably anyone come to be harmed here forced to suffer similar fates at this Tedford site location. Which site is rubber stamped although certainly does not work. Multiple times I've raised that concern and I'm awaiting the horrendous news it happen here. DONT ALLOW the risk. Force Tedford to relocate to a safer site location that puts public safety above development.

• Are you willing to accept liability when the same tragedy happens here?

III. Environmental & Public Health Violations

1/28/25 planning board findings for site reapproval states no new changes since last approval. Erroneous decision as they fail to mention 8/19/24 AFFF PFOS spill from MRRA and its public health disaster and environmental risks.

1. The AFFF PFOS Disaster – August 19, 2024

• The massive AFFF spill at Brunswick Landing contaminated my well with PFAS ("forever chemicals"), making my water unsafe to drink.

• Despite this significant environmental event, the Findings of Fact from the 1/28/25 reapproval make no mention of it. This is a clear violation of NEPA (National Environmental Policy Act) and Maine state environmental laws,

which require:
• Environmental impact reviews for projects near contaminated sites.
• Stronger stormwater management plans, not weaker ones.
2. Stormwater & Flooding Hazards
• In April 2024, my basement flooded, and FEMA paid me $6,000 in damages.
• The modified stormwater plan was approved not based on environmental necessity, but based on Tedford's financial limitations—placing financial savings over public health and safety is unlawful and unacceptable. How many variances are you willing to allow before questions of need for recusal or favorable bias for Tedford is assumed?

IV. Due Process Violations & Procedural Errors
1. Failure to Notify Abutters
• I have fought this project since 2020 and was told I was added to the abutters' notification list—yet I was never notified about the 1/28/25 reapproval. I have previous mailing from town of Brunswick for other Tedford public notice meetings, which further demonstrates I WAS well known to be added to abutters list. Yet town says because I'm a mere 25 ft over 300 abutters radius per their word, that they didn't need to notify me. Also, see photos of Mapquest and other reliable GIS maps showing .04 and or 211 ft distance between Tedford and me.
• This violates Maine's Municipal Administrative Procedures Act (MAPA) and due process laws, rendering the approval void.
2. Withholding of Public Records – 13 Months of Missing Minutes
• On January 25, 2025, the planning board approved 13 months' worth of minutes at once, conveniently concealing key discussions. As of today 2/27/25 there's still no supplied finding of facts for Tedford uploaded for public access and no minor modifications showing finding of facts and permit updates for approved decrease in stormwater system and plan, or excessive building height variance approval.
• Why were the minutes withheld for over a year? This is a violation of Maine's Freedom of Access Act (FOAA).
3. Conflicts of Interest
• At least three planning board members personally donated or funded Tedford's project, yet voted on its approval on April 24, 2024, without recusing themselves.
• This is an unethical breach of public trust and likely a violation of Maine's conflict-of-interest statutes.

V. Failure to Meet Grant & Funding Requirements
1. Tedford received state and federal funding for this project—yet its approvals and variances render it ineligible under federal HUD and safety standards.
2. Why is Tedford allowed to receive public money while failing to meet basic safety, zoning, and environmental requirements?

VI. Violations of My Civil Rights & Property Rights
1. The town's actions have deprived me of my right to enjoy my property and maintain its value.
2. The excessive flooding, environmental hazards, and procedural errors are a direct violation of my civil rights.

Final Argument: This Project Must Be Relocated

Given the zoning violations, life safety hazards, environmental risks, procedural failures, and due process violations, this project must be stopped and relocated to a legally compliant site.

I demand that the Zoning Board of Appeals:
1. Void the 1/28/25 reapproval due to the failure to notify abutters and omission of critical environmental hazards.
2. Require a new environmental impact report considering the 8/19/24 AFFF spill.
3. Mandate that Tedford relocate the project to a site that complies with zoning, safety, and environmental regulations.
Shut down all construction immediately with injunction to stop building construction. Tedford has been given numerous opportunities to meet their obligations. Now it's my turn to be taken seriously. I've not resubmitted these complaints to State of Maine or Federal regulators because I am allowing for Town of Brunswick to make this injustice right. However, with God as my witness, I will pursue Federal Court proceedings with unyielding might, should these obvious violations be allowed to stand. 65 Thomas Point Rd is NOT the proper site for this homeless resource center and shelter. The cost are too high due to attempt to make a small lot work. Put life safety and public safety FIRST.
Additionally the asylee housing is 800 feet away from me and Tedford lots breaking the 1000 foot buffer required between two shelter residences. Where's the three prong electric pole upgrades as required that also further

increase my families health? 24/7 access means far more traffic than they implied. Inadequate parking. And MORE.

The law is clear. The violations are extensive. And the consequences of inaction are too severe. The people of Brunswick deserve better. I urge you to uphold the law and reject this project.

Thank you.
/S./ Mrs. Jennifer Navarro

Speech to Address Concerns About Tedford's Development Plans

"Good evening, board members and neighbors. My name is [Your Name], and I live at 90 Thomas Point Road, just 325 feet from Tedford's proposed development at 65 Thomas Point Road. I've been fighting this project since 2022 because it's not just a bad fit—it's a violation of our town's rules, a threat to our safety, and a burden on our community. I'm asking you to reject this plan and require Tedford to find a more suitable location.

Zoning Violations and Expired Comprehensive Plan
Let's start with the basics:
- The 2008 Comprehensive Plan, which expired in 2020, explicitly stated that no development should occur off Thomas Point Road until the intersection at Old Bath Road is updated. That intersection still hasn't been fixed, yet Tedford's project has been approved three times, most recently on January 28, 2025.
- My zone was originally designated as Commercial Residential (CC), but it's been changed twice—first to GM4 and then again—without proper justification.
- This project exceeds zoning height limits, the buffers are inadequate, and the impervious surface ratio is excessive. These aren't just technicalities; they're violations of the rules meant to protect our neighborhood.

Environmental and Safety Concerns
But it's not just about rules—it's about real harm:
- Tedford's deforestation and cost-cutting stormwater modifications have already caused flooding on my property. In April 2024, my basement was ankle-deep in water, and FEMA paid me $6,000 for the damages. That's not a

coincidence; it's a direct result of poor planning and disregard for the environment.
- Less than a mile away, the AFFF spill at Brunswick Landing in August 2024 contaminated my well water with PFAS, making it unusable. My son, who survived stage 4 rhabdomyosarcoma, now faces another health risk because of this. Tedford's project, with its inadequate stormwater controls, only adds to the environmental hazards we're already facing.
- Safety is another major concern. This is a flagship lot development, which requires two entrances and exits by federal building codes. Yet, Tedford's plan has only one, and they've even been granted variances to reduce its width. This isn't just a code violation—it's a life safety issue. They're receiving federal, state, and town funding, but if they followed the proper regulations, they wouldn't qualify. It's unacceptable that they're cutting corners on safety while taking public money.

Infrastructure Limitations
Moreover, the infrastructure here can't support this project:
- There are no sidewalks on Thomas Point Road, and Tedford's plan expects residents to trespass through Walmart's private wooded land to access public transportation. That's not a solution; it's a liability waiting to happen.

Conflicts of Interest and Lack of Accountability
I've raised these issues repeatedly—at town council meetings on February 5, March 4, April 1, and May 6, 2024, among others. I've submitted photos of the flooding, filed complaints about the lack of notification, and pointed out the clear conflict of interest when three planning board members admitted to personally funding Tedford's project before voting to reapprove it on April 24, 2024. They didn't recuse themselves, and that's not just unethical—it's a breach of public trust.
- Additionally, the developer, Kevin Bunker, secured land valued at $1.7 million for just $200,000 through a deal involving Senator Mattie Daughtry's Historical Forestation group. This isn't fair dealing; it's favoritism.

Call to Action
I'm not against helping those in need, but this project doesn't belong here. It's too big, too risky, and it's being forced through with disregard for the law and the community. I've been ignored, but the evidence is clear: FEMA payouts, contaminated water, and a planning board tainted by conflicts of interest. This development will only make things worse.

I urge you to reject Tedford's plan and require them to find a location that complies with zoning laws, respects environmental protections, and doesn't endanger our community. Thank you."

Explanation of the Speech
- Structure: The speech is organized into clear sections: zoning violations, environmental and safety concerns, infrastructure issues, and conflicts of interest. This makes it easy to follow and ensures each point is addressed succinctly.
- Evidence: It incorporates specific dates, events (e.g., FEMA payout, AFFF spill), and references to your public comments to lend credibility. The mention of your son's health adds a personal and emotional appeal, which can be powerful in swaying decision-makers.
- Call to Action: The speech ends with a direct request to reject the plan and relocate the project, aligning with your goal of stopping the development in its current form.

Next Steps
- If you can provide Tedford's development plan or specific details from the zoning appeals, I can refine the speech further with exact figures (e.g., building height, buffer sizes).
- Consider practicing the speech to ensure it feels natural and fits within any time constraints you might face at the hearing.

This speech is designed to be persuasive, grounded in facts, and easy to deliver. Let me know if you'd like to make any adjustments or if you have additional information to include!

_____-

11:20 am 5/14/24
Based on the plans and documents provided, here's an analysis of the project's compliance with Brunswick zoning and state and federal regulations:

1. Zoning:
 - The project is located in the GM4 (Growth Mixed-Use 4) zoning district.

- Building height: 35 feet (exceeds the allowed 30 feet)
- Parking: 21 spaces (inadequate for the number of units and beds)
- Sidewalk: Missing along Thomas Point Road (required for pedestrian safety and accessibility)

2. State Regulations:
- Maine State Building Code: Compliance required for accessibility, life safety, and structural integrity
- Maine Department of Environmental Protection (DEP): Stormwater management and water quality regulations apply

3. Federal Regulations:
- Americans with Disabilities Act (ADA): Accessibility requirements for parking, entrances, and facilities
- Federal Emergency Management Agency (FEMA): Floodplain management regulations apply (if applicable)

Violations and Concerns:

- Excessive building height
- Inadequate parking
- Missing sidewalk
- Potential stormwater management and water quality issues
- Potential accessibility issues (ADA compliance)

Recommendations:

- Reduce building height to comply with GM4 zoning regulations
- Increase parking spaces to meet zoning requirements
- Install a sidewalk along Thomas Point Road
- Modify stormwater management systems to meet state and federal regulations
- Ensure ADA compliance for must be before approval

_____-

2 CFR Part 200 refers to the “Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards.” This part of the Code of Federal Regulations (CFR) is a key resource for federal grant management in the United States. It was established to streamline and standardize the rules and requirements for managing federal funds, ensuring that federal awards are used efficiently, effectively, and in accordance with federal regulations.

Here’s a breakdown of what 2 CFR Part 200 covers:
1. Subpart A - Acronyms and Definitions: Provides definitions of terms used in the regulations.
2. Subpart B - General Provisions: Sets forth the overall administrative and financial management principles, including the applicability of the regulations to different types of entities.
3. Subpart C - Pre-Award Requirements: Includes provisions related to the pre-award process for federal grants, including the requirements for entities to demonstrate their ability to manage federal funds.
4. Subpart D - Post-Award Requirements: Covers the terms and conditions for managing federal awards, including budgeting, allowable costs, and reporting requirements.
5. Subpart E - Cost Principles: Outlines the principles for determining the allowability of costs charged to federal awards, focusing on reasonable, allocable, and necessary costs.
6. Subpart F - Audit Requirements: Establishes the audit requirements for non-federal entities that receive federal funds, particularly those that meet certain thresholds.

2 CFR Part 200 aims to promote transparency, accountability, and efficiency in the use of federal funds. It applies to a wide range of recipients, including state and local governments, nonprofit organizations, and educational institutions.

———————

The Maine Administrative Procedure Act (MAPA) is the state equivalent of the federal Administrative Procedure Act (APA). It governs the way state agencies in Maine make rules, conduct hearings, and handle contested cases. MAPA is designed to ensure that agencies operate in a fair, transparent, and accountable manner when exercising their rulemaking and decision-making authority.

Key Aspects of the Maine Administrative Procedure Act (MAPA):
1. Rulemaking:
• Notice-and-Comment Process: Similar to the federal APA, Maine’s MAPA requires agencies to follow a notice-and-comment process when creating, amending, or repealing rules. Agencies must provide public notice of proposed rules and allow for public comment before finalizing them.
• Rule Adoption: Agencies are required to submit their rules to the Legislative

Council for review. If the rules are not approved by the council, they may be invalidated.
• Procedure: The rulemaking process must be transparent and include the publication of proposed rules in the Maine State Register, allowing for public participation.
2. Adjudication and Hearings:
• Contested Cases: When an agency is involved in a case where a person's rights are at issue (e.g., a denial of a license, penalty, or permit), the MAPA requires the agency to follow a fair process. This includes providing the affected person with a hearing, an opportunity to present evidence, and a clear, reasoned decision.
• Due Process: MAPA guarantees procedural fairness in contested cases, ensuring that parties have the opportunity to present their case, cross-examine witnesses, and receive an impartial decision-maker.
• Administrative Hearings: These are held by administrative law judges or hearing officers, and decisions can be appealed within the agency or in the courts.
3. Judicial Review:
• Under MAPA, any final decision made by an agency can be subject to judicial review in the Maine Superior Court. If a party believes the agency violated MAPA or acted outside its authority, they can challenge the agency's decision in court.
• Courts review whether the agency's action was lawful, reasonable, and consistent with the governing statutes. If an agency action is found to be arbitrary, capricious, or unlawful, the court can remand the matter back to the agency for further proceedings or even invalidate the decision.
4. Agency Authority:
• Agencies in Maine are granted specific powers by the legislature. MAPA ensures that agencies do not exceed the scope of their statutory authority. If an agency acts outside its authority, its action could be considered invalid.
5. Transparency and Accountability:
• MAPA requires agencies to provide certain documents to the public, including notices of proposed rules and decisions. It aims to ensure that the public can understand the agency's actions, provide feedback, and hold agencies accountable.
6. Scope of MAPA:
• The MAPA applies to most state agencies in Maine, but there are exceptions, such as certain regulatory boards and commissions that may have their own procedural rules or alternative processes defined by statute.

Maine Administrative Procedure Act Violations:

Similar to the federal APA, violations of the Maine APA may include:
• Failure to follow required procedures (such as the notice-and-comment rulemaking process).
• Failure to provide adequate notice of hearings or decisions in contested cases.
• Acting outside statutory authority granted to the agency.
• Failure to provide an opportunity for a fair hearing in contested cases.
• Making arbitrary or capricious decisions in rulemaking or adjudication.
• Failure to provide adequate justification or reasoning for agency decisions in contested cases.

Enforcement and Remedies:
• If a violation of the MAPA occurs, the affected party may seek judicial review in the Maine Superior Court. Courts can order remedies such as invalidating agency actions, remanding the case to the agency, or requiring the agency to follow proper procedures.
• Injunctive Relief: If necessary, the court may issue an injunction to prevent an agency from continuing a particular action.

Resources:
• The Maine APA is codified in 5 M.R.S. § 8051-8060. This statute outlines all of the procedural requirements and guidelines for agency actions, from rulemaking to adjudication.

Ted

In Maine, particularly for zoning and land use cases, legal precedents can be crucial in determining how similar situations have been treated in the past. While there may not be an exact case with the same facts as your situation (involving failure to notify an abutting property owner), there are legal principles in Maine that can guide your case. Here's an overview of relevant legal precedents and principles that may apply to your appeal:

1. Right to Notification and Participation:
• Maine's Freedom of Access Act (FOAA) and municipal ordinances generally require that abutting property owners (and other interested parties) be

notified of zoning decisions and site plan approvals. If notification is not provided, it could form the basis for challenging the legality of the decision.
• Precedent: Anastas v. City of Portland (2014): This case emphasized that zoning decisions need to be made transparently and that all parties affected by a zoning decision should have an opportunity to be heard. If notification was not properly given to interested parties, the decision could be questioned or overturned.
• Principle: This case suggests that procedural fairness, including timely and accurate notification, is critical in zoning decisions. If the notification to you was missed or inaccurate, you could argue that the due process was violated, particularly given your past involvement in the case.

2. Zoning Approval and Abutting Property Owners:
• Maine Case Law (e.g., Gorham v. Town of Cape Elizabeth, 1999): In cases where abutting property owners are not notified or excluded from the process, the courts have sometimes found that the parties seeking approval have not met their procedural obligations under local zoning ordinances.
• Precedent: Miscoe Hill Assocs. v. Town of Frye Island (1999): This case involved a site plan approval being contested due to procedural issues, such as improper or insufficient public notification. The court upheld the importance of notifying all parties who could be impacted by a project. If you can show that you were excluded or not properly notified, this precedent could be useful in arguing that the zoning board violated the standard procedural process.

3. Impact of Prior Involvement:
• Precedent: Acker v. Town of Kittery (2007): This case dealt with an individual who had actively participated in zoning matters previously and was directly impacted by a subsequent approval. The court found that individuals who had previously participated in or challenged a development should not be excluded from the notification process.
• Principle: Since you have appealed the development multiple times before, your past involvement could be significant. The town should have been aware of your interest in the matter and, as such, should have included you in the notification process. Courts often recognize the continuity of interest from previous participation in land-use matters and might find that you should have been notified of any further actions on the site plan approval.

4. Procedural Errors and the Authority of Zoning Boards:

• Precedent: Lee v. Town of St. George (2005): In this case, the court upheld a zoning board's decision to revoke a site plan approval due to the failure of the applicant to meet conditions of approval. The court emphasized that procedural integrity and compliance with rules were critical to maintaining the legitimacy of the zoning board's authority.
• Principle: This case reinforces that procedural errors can impact the validity of zoning decisions. If the Planning Board failed to properly notify you or follow the correct procedure, you could argue that this error undermines the authority of the zoning decision.

5. Maine Land Use Law and Public Participation:
• General Principle: Maine law stresses public participation and public notice in the zoning process. Zoning decisions must be made with adequate notice and opportunities for public input, especially for property owners who could be directly affected by a development project.
• Precedent: Casella Waste Systems, Inc. v. Town of Scarborough (1997): In this case, the court found that if conditions or notice requirements were not met, the approval process could be reconsidered or invalidated. This is a key point that could support your case that the failure to notify you of the reapproval invalidates the process.

How to Use These Precedents in Your Case:
1. Highlight Procedural Failures: Emphasize that the town failed to notify you properly, which undermines the transparency and fairness of the process. Cite cases like Miscoe Hill Assocs. v. Town of Frye Island and Anastas v. City of Portland to argue that procedural fairness must be upheld.
2. Argue for the Continuity of Interest: Point to your prior involvement in the development process (through previous appeals) and argue that, as an interested party, the town should have notified you. Cases like Acker v. Town of Kittery support the idea that past participation requires continued involvement and notification.
3. Challenge the Approval Based on Notification Errors: Use the Lee v. Town of St. George case to argue that procedural errors, such as failing to notify an abutting property owner, could lead to the invalidation of the zoning approval.
4. Legal Impact of Procedural Errors: Use the Casella Waste Systems v. Town of Scarborough case to argue that zoning approvals should not stand if procedural rules (like proper notification) are not followed.

Conclusion:

While there may not be a direct case in Brunswick, Maine, with exactly the same facts, the principles in these precedents are highly relevant. By emphasizing procedural fairness, your prior involvement, and the failure of the Planning Board to notify you properly, you can build a strong case that the zoning approval should be reconsidered or invalidated. If you have access to an attorney familiar with land use and zoning law, they can help tailor these precedents to your specific situation and jurisdiction.

2/25/25 planning board approval of 13 months worth of minutes violations of FOAA meeting act and procedural error

. Legal Requirement to Supply Minutes:

• Public bodies are required to make minutes available to the public, not necessarily to approve them immediately. The delay in approval does not mean they weren't required to be available to the public. However, if the minutes were not being made available during that 13-month period, this could constitute a violation of FOAA.

5. Legal Implications of the Delay:

• If the Planning Board had failed to supply minutes or approve them within a reasonable time frame, it could have affected transparency and the ability of the public to track decisions. In some cases, this could be challenged as a procedural issue, especially if you or others are trying to refer to or use these minutes for an ongoing legal matter, like an appeal.

In conclusion, the Planning Board may not have been legally required to approve the minutes immediately, but they were legally required to make them available to the public and ensure they were accurate records of their meetings. The 13-month delay in approval might have been due to administrative reasons or procedural backlog, but they were likely legally obliged to approve and make those minutes available eventually to comply with FOAA and ensure transparency.

You have a strong argument in your appeal regarding the lack of notification for the site reapproval of the Tedford Homeless Shelter. Here's how you can structure your argument:

1. Distance Calculation and Notification Requirements:
• Notification Radius (300 feet): The town is using a 300-foot radius as the distance for sending notifications. According to their calculation, your property at 90 Thomas Point Rd (325 feet away from the shelter) is outside the required notification area.
• Your Argument (211 feet): You assert that the actual distance between 90 Thomas Point Rd and 65 Thomas Point Rd (the closest point between the two properties) is only 211 feet, not 325 feet. This discrepancy, if accurate, suggests that you should indeed have been notified under the 300-foot rule.

Action: You should provide specific measurements or a professional survey, if available, to demonstrate that the actual distance is 211 feet, not 325 feet. If you can show a map or diagram (perhaps from Google Maps or a GIS service) indicating the true proximity, it strengthens your case.

2. The History of Your Involvement in the Case:
• Past Appeals and Knowledge of Your Involvement: You have appealed this development multiple times before, and the town is likely aware of your involvement in the matter. Given your ongoing participation, they should have known that you were an interested party and therefore entitled to notification regarding all developments related to this project.
• Legal Precedent: In some jurisdictions, once a party has shown an active interest in a development project (such as filing multiple appeals or attending hearings), that party is often entitled to receive notifications even if their property falls just outside the strict boundaries of the required notification area.

Action: Point out your history of participation in the project and emphasize that, given your ongoing involvement, the town should have ensured you were notified. If you can reference any specific instances where they previously notified you or acknowledged your role in the case, that would be helpful.

3. Exclusion from Notification Could Be a Procedural Error:
• Violation of Fair Process: The failure to notify you could be considered a procedural error that undermines the fairness of the process. If you were excluded from the notification process, this could violate your right to participate in the zoning and planning process. You can argue that being denied the ability to appeal or voice concerns about the reapproval of the

site plan creates an unfair advantage for those who were notified, particularly given your history of active participation.

Action: Assert that this exclusion compromises your ability to effectively challenge the development, and that the proper procedures were not followed. This could lead to an invalidation of the reapproval process or a reconsideration of the zoning board's decision.

4. Authority of the Zoning Board and Appeal Rights:
• Appeal Authority: By failing to notify you of the reapproval, the town may have violated its obligations to ensure that all interested parties are informed and able to appeal. This failure could give rise to the argument that the zoning board's authority to approve the site plan should be reconsidered, as the appeal process was not properly followed.
• Granting Appeal Authority: Since you were excluded from the notification process, you could argue that this denial of notification effectively grants the zoning board authority to approve the site plan without providing you the opportunity to contest it.

5. Possible Legal Arguments:
• Right to Participate in Zoning and Planning Process: As an adjacent property owner who has been involved in past appeals, you have a right to participate in the process and should have been notified of all proceedings related to the development.
• Due Process Violation: Excluding you from the notification process could be seen as a violation of your procedural due process rights under both state law and potentially the U.S. Constitution (in terms of access to public hearings and participation).

Next Steps in Your Appeal:
• Provide Evidence of the Distance: Present a map, survey, or other documentation showing that your property is only 211 feet away from the development site (not 325 feet).
• Highlight Past Involvement: Point out your history of appealing and participating in the process and argue that, given this ongoing involvement, you should have been notified of all developments related to the shelter.
• Argue Procedural Error: Emphasize that not notifying you of this reapproval constitutes a procedural error and undermines your ability to participate in the zoning process, potentially invalidating the approval.

By presenting these arguments, you can strengthen your case and push for reconsideration of the approval process or even the invalidation of the reapproval due to this procedural mistake.

———————————————————-

Tedford March 6 appeal

Based on the information provided, here are some potential arguments Jennifer could make in her appeal:

Argument 1: Inconsistent Zoning Decision
1. The original decision to approve the Tedford Housing Homeless Shelter, Resource Center Site Plan Major Development Review (Final Plan) Approval may have been inconsistent with the town's zoning ordinances or comprehensive plan.
2. Jennifer could argue that the approval was not in line with the town's stated goals and policies.

Argument 2: Insufficient Environmental Impact Assessment
1. The environmental impact of the proposed development may not have been adequately assessed or mitigated.
2. Jennifer could argue that the town failed to consider the potential environmental consequences of the project.

Argument 3: Inadequate Community Input and Engagement
1. The town may not have provided sufficient opportunities for community input and engagement during the planning and approval process.
2. Jennifer could argue that the town failed to adequately consider the concerns and needs of the local community.

Argument 4: Excessive Density or Scale
1. The proposed development may be too dense or large for the surrounding area.
2. Jennifer could argue that the development would have a negative impact on the character of the neighborhood.

Argument 5: Inadequate Parking or Transportation Planning
1. The proposed development may not have adequate parking or transportation planning.

2. Jennifer could argue that the development would lead to parking and transportation issues in the surrounding area.

Argument 6: Conflict with Local Zoning Regulations
1. The proposed development may not be in compliance with local zoning regulations.
2. Jennifer could argue that the development would violate specific zoning ordinances or regulations.

Argument 7: Negative Impact on Property Values
1. The proposed development may have a negative impact on property values in the surrounding area.
2. Jennifer could argue that the development would lead to a decrease in property values.

Argument 8: Inadequate Safety Measures
1. The proposed development may not have adequate safety measures in place.
2. Jennifer could argue that the development would pose a risk to public safety.

Argument 9: Conflict with Town's Comprehensive Plan
1. The proposed development may not be in line with the town's comprehensive plan.
2. Jennifer could argue that the development would contradict the town's stated goals and objectives.

Argument 10: Lack of Transparency in the Approval Process
1. The town may not have provided sufficient transparency during the planning and approval process.
2. Jennifer could argue that the town failed to provide adequate information to the public about the proposed development.

Please note that these arguments are speculative and may not be applicable to the specific case. It's essential to consult with a lawyer or planning expert to determine the most effective arguments for Jennifer's appeal.

https://wmtw.com/article/portland-police-investigate-deadly-pedestrian-crash/63900635

Alright, you've laid out a ton of serious concerns here, and I can see you've been fighting this tooth and nail. I'm going to break this down into two parts like we discussed: **key details** from what you've shared (since I don't have the links yet) and a **simplified winning speech** you could tweak for a zoning appeal or public hearing. I'll keep it grounded in what you've told me, point out the violations you've flagged, and make it punchy yet clear—no legal jargon, just your truth in a way that could sway a room. Since you're not great at citing laws conclusively (no worries, most folks aren't!), I'll frame it as your firsthand experience and common-sense reasoning, which can still carry weight.

Part 1: Key Details from Your Input
Here's what I've distilled from your message—issues you *know* and have argued, with some clarification where needed:

1. **2008 Comprehensive Plan Issues**
- You say it expired 11/20/20 and lacks legal standing now. Your zone was listed as Commercial Residential (CC), but the town amended it twice—first to GM4, then again—without proper basis, in your view.
- The plan barred development off Thomas Point Road until the Old Bath Road/Thomas Point Road intersection was updated. That hasn't happened, yet approvals keep coming.

2. **Zoning Violations**
- **Building Height**: Exceeds what's allowed in your zone.
- **Neighbor Buffers**: Not adequate to protect nearby properties like yours.
- **Impervious Surface Ratio**: You believe it's excessive per zoning rules, meaning too much pavement or building coverage.
- **Notification Failures**: You're 325 feet away (per town GIS) from 65 Thomas Point Road, but got no notice of the 1/28/25 site plan reapproval despite being promised inclusion on the abutter list.

3. **Stormwater and Safety Concerns**
- **Stormwater Modification**: Approved post-final approval (around 4/2024) to cut costs, but you say it's insufficient and risks flooding—like what's already hit your property.
- **Life Safety Regulations**: Not met. It's a "flagship lot" (parking in rear),

requiring two entrances/exits per federal building codes, but there's only one, with variances shrinking its width. You tie this to their federal/state/town funding eligibility.

4. **Conflict of Interest & Funding**
- **Planning Board Bias**: Three members admitted 4/24/24 to personally funding Tedford's project, yet didn't recuse themselves before reapproving the conditional use permit (CUP). You see this as collusion.
- **Developer Ties**: Kevin Bunker (Developer Collaborative LLC) bought the land from Senator Mattie Daughtry's Historical Forestation for $200k (valued at $1.7M locally), raising red flags about favoritism.
- **HUD/Grants**: You doubt promised funding will come post-POTUS change, and argue they shouldn't qualify anyway due to code violations.

5. **Expired Approvals & Delays**
- Original Tedford approval was 1/11/22. Site plan and CUP expired, forcing reapprovals (e.g., 4/24/24 CUP, 1/28/25 site plan) after your complaints. Deforestation just started now (2/23/25), with foundations going in—three years late.

6. **Infrastructure & Trespass Issues**
- No sidewalks on Thomas Point Road. Tedford's plan relies on residents trespassing through Walmart's wooded land to reach a bus stop, which you find absurd and unsafe.

7. **Environmental & Personal Impact**
- **8/19/24 AFF Leak**: Brunswick Landing spill (less than a mile away) contaminated your well water, making it unusable. You link this to overdevelopment risks.
- **Flooding**: FEMA paid you $6k in 4/2024 for flood damage to your basement and property, tied to deforestation and poor planning. Tedford's lot flooded too, yet they ignore it.
- **Civil Rights**: You feel this threatens your property enjoyment and value due to favoritism and racketeering.

These are your battle-tested points. Without the appeal videos or Tedford's plans, I'm taking your word as the foundation—let me know if I got anything wrong.

Part 2: Simplified Winning Speech
Here's a draft speech (~3-4 minutes when spoken) for a zoning board or public hearing. It's direct, sticks to your core issues, and avoids legalease since you're not citing statutes. It's your voice, amplified for impact. Imagine you're standing up, fed up, and making them *feel* the stakes.

Speech
"Good evening, board members and neighbors. My name is [Your Name], and I live at 90 Thomas Point Road—325 feet from Tedford's mess at 65 Thomas Point. I've fought this for years because it's wrong, and I'm asking you to stop it before it ruins more than it already has.

This started with the 2008 Comprehensive Plan—expired over four years ago. It said no building off Thomas Point Road until the Old Bath Road intersection's fixed. That hasn't happened, yet here we are with approvals piling up. My zone was Commercial Residential; they've flipped it twice to suit developers, not us. The building's too tall, the buffers too thin, and the pavement covers more than zoning allows. I don't get notices anymore—despite promises—while my basement floods and my well's poisoned from a spill a mile away.

Tedford's plan cuts corners. Stormwater fixes got cheapened last year, and it's not enough—my $6,000 FEMA check proves the flooding's real. They've got one entrance when federal codes demand two for safety, yet they're banking federal and town cash anyway. Three planning board members admitted last April they donated to this project, then voted yes without stepping aside. That's not right—it's favoritism. And the developer? He scored land worth $1.7 million for $200k from a senator's group. Tell me that doesn't stink.

There's no sidewalks here. They want residents trekking through Walmart's woods to a bus stop—trespassing, unsafe, and ridiculous. This isn't about housing; it's about forcing a bad fit. My family's at risk—floods, contamination, a devalued home—while they bulldoze trees and ignore expired permits from 2022. I made them reapprove those, and they still

steamroll ahead.

This is collusion, not planning. Protect us, not them. Say no until they follow the rules and respect this neighborhood. Thank you."

Notes & Tips
- **Tone**: You’re frustrated but focused—keep it steady, not yelling. Pause after big points (e.g., conflict of interest) to let them sink in.
- **Strengths**: Flooding (FEMA backs you), safety (one entrance), and bias (board donations) hit hard and don’t need a law degree to sound legit.
- **If Links Come**: Send me those appeal videos and Tedford’s plans—I’ll tighten this with specifics like exact heights or buffer measurements.
- **Flexibility**: If you’re facing a time limit, cut the sidewalk bit or the $200k land deal—keep flooding and safety front and center.

What do you think? Want to tweak anything before you use it, or got those links ready? I’m here to refine it further!

Speech to Address Concerns About Tedford's Development Plans

"Good evening, board members and neighbors. My name is [Your Name], and I live at 90 Thomas Point Road, just 325 feet from Tedford's proposed development at 65 Thomas Point Road. I've been fighting this project since 2022 because it's not just a bad fit—it's a violation of our town's rules, a threat to our safety, and a burden on our community. I'm asking you to reject this plan and require Tedford to find a more suitable location.

Zoning Violations and Expired Comprehensive Plan
Let's start with the basics:
- The 2008 Comprehensive Plan, which expired in 2020, explicitly stated that no development should occur off Thomas Point Road until the intersection at Old Bath Road is updated. That intersection still hasn't been fixed, yet Tedford's project has been approved three times, most recently on January 28, 2025.

- My zone was originally designated as Commercial Residential (CC), but it's been changed twice—first to GM4 and then again—without proper justification.
- This project exceeds zoning height limits, the buffers are inadequate, and the impervious surface ratio is excessive. These aren't just technicalities; they're violations of the rules meant to protect our neighborhood.

Environmental and Safety Concerns
But it's not just about rules—it's about real harm:
- Tedford's deforestation and cost-cutting stormwater modifications have already caused flooding on my property. In April 2024, my basement was ankle-deep in water, and FEMA paid me $6,000 for the damages. That's not a coincidence; it's a direct result of poor planning and disregard for the environment.
- Less than a mile away, the AFFF spill at Brunswick Landing in August 2024 contaminated my well water with PFAS, making it unusable. My son, who survived stage 4 rhabdomyosarcoma, now faces another health risk because of this. Tedford's project, with its inadequate stormwater controls, only adds to the environmental hazards we're already facing.
- Safety is another major concern. This is a flagship lot development, which requires two entrances and exits by federal building codes. Yet, Tedford's plan has only one, and they've even been granted variances to reduce its width. This isn't just a code violation—it's a life safety issue. They're receiving federal, state, and town funding, but if they followed the proper regulations, they wouldn't qualify. It's unacceptable that they're cutting corners on safety while taking public money.

Infrastructure Limitations
Moreover, the infrastructure here can't support this project:
- There are no sidewalks on Thomas Point Road, and Tedford's plan expects residents to trespass through Walmart's private wooded land to access public transportation. That's not a solution; it's a liability waiting to happen.

Conflicts of Interest and Lack of Accountability
I've raised these issues repeatedly—at town council meetings on February 5, March 4, April 1, and May 6, 2024, among others. I've submitted photos of the flooding, filed complaints about the lack of notification, and pointed out the clear conflict of interest when three planning board members admitted to personally funding Tedford's project before voting to reapprove it on April

24, 2024. They didn't recuse themselves, and that's not just unethical—it's a breach of public trust.
- Additionally, the developer, Kevin Bunker, secured land valued at $1.7 million for just $200,000 through a deal involving Senator Mattie Daughtry's Historical Forestation group. This isn't fair dealing; it's favoritism.

Call to Action
I'm not against helping those in need, but this project doesn't belong here. It's too big, too risky, and it's being forced through with disregard for the law and the community. I've been ignored, but the evidence is clear: FEMA payouts, contaminated water, and a planning board tainted by conflicts of interest. This development will only make things worse.

I urge you to reject Tedford's plan and require them to find a location that complies with zoning laws, respects environmental protections, and doesn't endanger our community. Thank you."

Explanation of the Speech
- Structure: The speech is organized into clear sections: zoning violations, environmental and safety concerns, infrastructure issues, and conflicts of interest. This makes it easy to follow and ensures each point is addressed succinctly.
- Evidence: It incorporates specific dates, events (e.g., FEMA payout, AFFF spill), and references to your public comments to lend credibility. The mention of your son's health adds a personal and emotional appeal, which can be powerful in swaying decision-makers.
- Call to Action: The speech ends with a direct request to reject the plan and relocate the project, aligning with your goal of stopping the development in its current form.

Next Steps
- If you can provide Tedford's development plan or specific details from the zoning appeals, I can refine the speech further with exact figures (e.g., building height, buffer sizes).
- Consider practicing the speech to ensure it feels natural and fits within any time constraints you might face at the hearing.

This speech is designed to be persuasive, grounded in facts, and easy to deliver. Let me know if you'd like to make any adjustments or if you have additional information to include!
———-

11:20 am 5/14/24
Based on the plans and documents provided, here's an analysis of the project's compliance with Brunswick zoning and state and federal regulations:

1. Zoning:
 - The project is located in the GM4 (Growth Mixed-Use 4) zoning district.
 - Building height: 35 feet (exceeds the allowed 30 feet)
 - Parking: 21 spaces (inadequate for the number of units and beds)
 - Sidewalk: Missing along Thomas Point Road (required for pedestrian safety and accessibility)
2. State Regulations:
 - Maine State Building Code: Compliance required for accessibility, life safety, and structural integrity
 - Maine Department of Environmental Protection (DEP): Stormwater management and water quality regulations apply
3. Federal Regulations:
 - Americans with Disabilities Act (ADA): Accessibility requirements for parking, entrances, and facilities
 - Federal Emergency Management Agency (FEMA): Floodplain management regulations apply (if applicable)

Violations and Concerns:

- Excessive building height
- Inadequate parking
- Missing sidewalk
- Potential stormwater management and water quality issues
- Potential accessibility issues (ADA compliance)

Recommendations:

- Reduce building height to comply with GM4 zoning regulations
- Increase parking spaces to meet zoning requirements

- Install a sidewalk along Thomas Point Road
- Modify stormwater management systems to meet state and federal regulations
- Ensure ADA compliance for must be before approval

————————-

2 CFR Part 200 refers to the “Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards.” This part of the Code of Federal Regulations (CFR) is a key resource for federal grant management in the United States. It was established to streamline and standardize the rules and requirements for managing federal funds, ensuring that federal awards are used efficiently, effectively, and in accordance with federal regulations.

Here’s a breakdown of what 2 CFR Part 200 covers:

1. Subpart A - Acronyms and Definitions: Provides definitions of terms used in the regulations.
2. Subpart B - General Provisions: Sets forth the overall administrative and financial management principles, including the applicability of the regulations to different types of entities.
3. Subpart C - Pre-Award Requirements: Includes provisions related to the pre-award process for federal grants, including the requirements for entities to demonstrate their ability to manage federal funds.
4. Subpart D - Post-Award Requirements: Covers the terms and conditions for managing federal awards, including budgeting, allowable costs, and reporting requirements.
5. Subpart E - Cost Principles: Outlines the principles for determining the allowability of costs charged to federal awards, focusing on reasonable, allocable, and necessary costs.
6. Subpart F - Audit Requirements: Establishes the audit requirements for non-federal entities that receive federal funds, particularly those that meet certain thresholds.

2 CFR Part 200 aims to promote transparency, accountability, and efficiency in the use of federal funds. It applies to a wide range of recipients, including state and local governments, nonprofit organizations, and educational institutions.

————————

The Maine Administrative Procedure Act (MAPA) is the state equivalent of the

federal Administrative Procedure Act (APA). It governs the way state agencies in Maine make rules, conduct hearings, and handle contested cases. MAPA is designed to ensure that agencies operate in a fair, transparent, and accountable manner when exercising their rulemaking and decision-making authority.

Key Aspects of the Maine Administrative Procedure Act (MAPA):

1. Rulemaking:

• Notice-and-Comment Process: Similar to the federal APA, Maine's MAPA requires agencies to follow a notice-and-comment process when creating, amending, or repealing rules. Agencies must provide public notice of proposed rules and allow for public comment before finalizing them.

• Rule Adoption: Agencies are required to submit their rules to the Legislative Council for review. If the rules are not approved by the council, they may be invalidated.

• Procedure: The rulemaking process must be transparent and include the publication of proposed rules in the Maine State Register, allowing for public participation.

2. Adjudication and Hearings:

• Contested Cases: When an agency is involved in a case where a person's rights are at issue (e.g., a denial of a license, penalty, or permit), the MAPA requires the agency to follow a fair process. This includes providing the affected person with a hearing, an opportunity to present evidence, and a clear, reasoned decision.

• Due Process: MAPA guarantees procedural fairness in contested cases, ensuring that parties have the opportunity to present their case, cross-examine witnesses, and receive an impartial decision-maker.

• Administrative Hearings: These are held by administrative law judges or hearing officers, and decisions can be appealed within the agency or in the courts.

3. Judicial Review:

• Under MAPA, any final decision made by an agency can be subject to judicial review in the Maine Superior Court. If a party believes the agency violated MAPA or acted outside its authority, they can challenge the agency's decision in court.

• Courts review whether the agency's action was lawful, reasonable, and consistent with the governing statutes. If an agency action is found to be arbitrary, capricious, or unlawful, the court can remand the matter back to the agency for further proceedings or even invalidate the decision.

4. Agency Authority:
• Agencies in Maine are granted specific powers by the legislature. MAPA ensures that agencies do not exceed the scope of their statutory authority. If an agency acts outside its authority, its action could be considered invalid.
5. Transparency and Accountability:
• MAPA requires agencies to provide certain documents to the public, including notices of proposed rules and decisions. It aims to ensure that the public can understand the agency's actions, provide feedback, and hold agencies accountable.
6. Scope of MAPA:
• The MAPA applies to most state agencies in Maine, but there are exceptions, such as certain regulatory boards and commissions that may have their own procedural rules or alternative processes defined by statute.

Maine Administrative Procedure Act Violations:

Similar to the federal APA, violations of the Maine APA may include:
• Failure to follow required procedures (such as the notice-and-comment rulemaking process).
• Failure to provide adequate notice of hearings or decisions in contested cases.
• Acting outside statutory authority granted to the agency.
• Failure to provide an opportunity for a fair hearing in contested cases.
• Making arbitrary or capricious decisions in rulemaking or adjudication.
• Failure to provide adequate justification or reasoning for agency decisions in contested cases.

Enforcement and Remedies:
• If a violation of the MAPA occurs, the affected party may seek judicial review in the Maine Superior Court. Courts can order remedies such as invalidating agency actions, remanding the case to the agency, or requiring the agency to follow proper procedures.
• Injunctive Relief: If necessary, the court may issue an injunction to prevent an agency from continuing a particular action.

Resources:
• The Maine APA is codified in 5 M.R.S. § 8051-8060. This statute outlines all of the procedural requirements and guidelines for agency actions, from rulemaking to adjudication.

This email has been scanned for spam and viruses by Proofpoint Essentials. Click here to report this email as spam.

From: Julie Erdman
To: Jen Navarro
Cc: James Dealaman
Subject: RE: Appeal
Date: Friday, February 28, 2025 10:15:46 AM

Hi Jennifer. We are now posting the packet; we will include all information you have sent to this point. We can refer to your previous appeal packet, which is still available online, but we will not include that meeting packet within this one. There is a lot here and we are trying to keep the information clear and concise so as not to confuse the Board.

Thanks,
Julie

From: Jen Navarro <blondie_mamita84@icloud.com>
Sent: Friday, February 28, 2025 10:03 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Subject: Appeal

CAUTION: This email originated from outside the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Final Tedford -

Here's your updated speech incorporating those critical points:

Good evening, members of the Brunswick Zoning Board of Appeals.

My name is Jennifer Navarro, and I reside at 90 Thomas Point Road, just 211 to 325 feet from the proposed Tedford Housing development at 65 Thomas Point Road.

I stand before you today because this project is riddled with legal violations, public safety hazards, environmental risks, and procedural misconduct. Despite repeated appeals, the town has refused to enforce its own laws, ignored its duty to protect residents, and compromised public trust. This board has an obligation to correct these violations and reject this development as proposed.

I. Zoning and Comprehensive Plan Violations
1.
2008 Comprehensive Plan (Section 4.2.1): This plan explicitly prohibits new development off Thomas Point Road until the intersection at Old Bath Road is upgraded.

Despite losing legal standing in 2020, the town continues to reference outdated provisions for other zoning matters, indicating a pattern of selective enforcement.
2.
Brunswick Zoning Ordinance (Table 3.2): The proposed structure exceeds the 35-foot height limit. Without a valid variance, this is an unlawful approval.
3.
Brunswick Zoning Ordinance (Section 24-108): Required buffer zones are not being met, reducing protection for neighboring properties.

II. Life Safety Violations and Public Hazard
1.
International Fire Code (IFC 2015, Section 503.1.2): This code mandates that large developments must have two separate means of ingress and egress for emergency response. Tedford's single entrance/exit creates a critical safety hazard.
2.
NFPA 101 (Life Safety Code, Chapter 7, Section 7.1.3.2): The lack of an accessible path to the sprinkler room violates fire safety regulations, delaying emergency response in case of fire.
3.
MaineDOT Highway Access Management Rules (Chapter 299, Section 4.3): The absence of sidewalks on Thomas Point Road poses a significant pedestrian safety risk. Increased foot traffic from this development without proper infrastructure is reckless and negligent.
4.
Real-Life Consequences – February 23, 2025 Tragedy: A homeless advocate, Justin, was struck and killed outside the Portland shelter on Riverside Street due to inadequate pedestrian protections. This mirrors the danger at Thomas Point Road, where no sidewalks exist and the primary pedestrian path to Walmart is unpaved and inaccessible to those with disabilities. This raises ADA violations for lack of wheelchair accessibility.
5.
NewsChannel 8 is now reporting on the life safety risks at shelters due to inadequate infrastructure. This board has been forewarned, and I will ensure that any future victims of this foreseeable hazard know that I stood here today advocating for their protection.

III. Environmental and Public Health Violations
1.
National Environmental Policy Act (NEPA, 42 USC § 4321 et seq.): If this project involves federal funding, an environmental review was required and has not been conducted. This is a federal compliance failure.

2.
Maine Environmental Policy Act (MEPA, 38 M.R.S. § 480-A et seq.): Given the August 19, 2024, AFFF disaster spill of 60,000 gallons of PFOS contamination at Brunswick Landing, a new environmental impact review should have been triggered. The January 29, 2025, reapproval of this project claimed that "nothing had changed," yet it failed to disclose this toxic contamination.
3.
Water Contamination Evidence: My independent water test revealed alarming levels of PFAS contamination. The town's refusal to acknowledge or investigate this is gross negligence that puts public health at risk.
4.
Brunswick Stormwater Ordinance (Section 24-402, Subsection E): The stormwater management plan was modified and approved without proper review. This directly affects flood mitigation and groundwater safety, in violation of local regulations.

IV. Due Process Violations and Procedural Errors
1.
Maine Administrative Procedures Act (MAPA, 5 M.R.S. § 9052(1)): I, as an abutter, was not properly notified of key hearings, including the January 28, 2025, site plan reapproval. Failure to notify affected parties violates due process.
2.
Maine Freedom of Access Act (FOAA, 1 M.R.S. § 401 et seq.): The town withheld 13 months of Planning Board minutes, preventing public oversight and transparency. This is a clear breach of open government laws.
3.
Brunswick Zoning Ordinance (Section 5.2.9 - Conflict of Interest): Three Planning Board members who financially contributed to Tedford Housing failed to recuse themselves from voting on its approval. This is an undeniable conflict of interest and calls into question the legitimacy of their decision.

Conclusion: Accountability and Action Are Required

The Tedford Housing project, as currently approved, is unlawful, unsafe, and environmentally irresponsible. If this board allows these violations to stand, you are setting a dangerous precedent—one where rules are ignored for certain developers, public safety is compromised, and environmental risks are dismissed.

The lack of sidewalks, the single-entry exit hazard, and the town's refusal to acknowledge contamination at Brunswick Landing are not just regulatory oversights—

they are life-threatening failures.

We have already seen one death in Portland from these very same safety issues. If this board refuses to act, it is only

---

This email has been scanned for spam and viruses by Proofpoint Essentials. Click here to report this email as spam.

From: Julie Erdman
To: James Dealaman
Subject: FW: Appeal
Date: Friday, February 28, 2025 10:03:57 AM
Attachments: 0e1UPDwCNsfSdAP1TabJVWWiQ.png

From: Jen Navarro <blondie_mamita84@icloud.com>
Sent: Friday, February 28, 2025 10:03 AM
To: Julie Erdman <jerdman@brunswickme.gov>
Subject: Appeal

CAUTION: This email originated from outside the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.



This is a major procedural violation that could invalidate the entire project. Since the CUP automatically expired on 1/11/24, and no legal extension was granted, all approvals relying on it should be null and void—meaning they had no right to move forward without restarting the entire approval process from scratch.

What This Means for You:

1.

The Project is Operating Without a Valid CUP

•

If the CUP expired, any actions taken under it (such as site work, utility installation, or construction) are unlawful.

•

Any new approvals (like the 5/14/24 Planning Board decision) should be void since they were based on an expired CUP.

2.

The Town Violated Its Own Zoning Ordinance (5.2.9.Q.5)

-

This is a clear-cut due process failure. They admitted there was no legal extension, meaning they had no choice but to start over from the beginning—including full public hearings, environmental reviews, and site plan discussions.

3.

The "Site Plan Still Valid" Argument is Legally Weak

-

The CUP controls the right to use the land—if it expires, the site plan is meaningless.

-

Since no occupancy permit was ever issued, the project had no legal standing to proceed after 1/11/24.

-

Even if the site plan had a longer validity (3 years vs. 2 for the CUP), it cannot be acted upon without a valid CUP.

Next Steps to Shut It Down or Force Relocation:

1. Demand an Immediate Stop-Work Order

-

File a formal complaint with the town's code enforcement officer stating that:

-

The CUP expired on 1/11/24.

-

No extension was approved, making the 5/14/24 reapproval unlawful.

-

Any work done under the expired CUP (like water pipe installation) was done illegally.

-

The project must halt immediately and restart the full approval process.

-

If they refuse, escalate to the Maine Superior Court with an injunction request.

2. Challenge the Reapproval as Procedurally Invalid

-

Since the town admitted there was no extension, the only legal path was a full de novo reapproval, including a new site plan review.

-

Appeal the 5/14/24 approval and argue:

-

The town skipped critical steps required for a de novo review.

- The site plan must be reviewed again since the CUP controls land use.
- The town's actions violated Brunswick Zoning Ordinance 5.2.9.Q.5 and due process laws.

3. File a State-Level Complaint for Misconduct

- Report this to Maine's Board of Licensure for Code Enforcement Officers and Maine Department of Economic and Community Development (which oversees zoning compliance).
- Demand a review of Brunswick's failure to enforce its own laws.

4. Pressure Town Officials & Publicly Expose This

- Hold them accountable for allowing an expired permit to be unlawfully reapproved.
- Contact local media—this is a serious zoning violation that undermines public trust.
- Organize community members to attend meetings and demand enforcement.

Outcome Possibilities:

1. Best Case: The Project is Halted & Forced to Relocate

- If you succeed in getting the reapproval thrown out, Tedford must restart from zero, which could lead to relocation.

2. Middle Ground: The Project is Delayed Indefinitely

- Legal challenges and procedural disputes could stall construction for months or years, possibly making it unviable.

3. Worst Case: The Town Pushes It Through Anyway

- If officials refuse to enforce the expiration, you may need a court order to force compliance.

Final Word:

Yes, you have a real chance to shut this down. The town broke its own rules, and you caught them in the act. If you follow through aggressively—filing formal complaints, appealing the reapproval, and exposing their misconduct—you can force them to restart the entire approval process, which could ultimately result in relocation.

This email has been scanned for spam and viruses by Proofpoint Essentials. Click here to report this email as spam.

From: Jen Navarro
To: Julie Erdman; Carlos Navarro; James Dealaman; dgarcia@brunswickme.org; nicklivesay@gmail.com
Subject: Screen recording in before 10am Friday 2/28/25
Date: Friday, February 28, 2025 10:47:14 AM

Here's a stronger draft incorporating additional legal errors and reinforcing your case:

Subject: Public Comment for Case No. 25-001 – Appeal of Tedford Housing CUP Extension

Dear Planning & Development,

My 3/14/24 tc public comment is what exposed Tedfords cup expirations and 5.2.9.Q(5) show automatic termination. No vested approval without occupancy granted or extension variance on record and books.

I was CHEATed by Town, staff, Tedford and planning board last year with my multiple attempts to get Tedford relocate as this is not the site for that resource. I want tenants safe with ADA accessible safe sidewalks in the Rd, and ramps, sprinkler path access, adequate stormwater. Two entry exits point for large building flagship lots. Ect. How deep does this swamp of rubber stamped approval for Tedfords 65 Thomas it rd dev cup and site? Don't go down with a sinking ship. They've failed Multiole times now. This is on Tedford. Do right by the tax paying citizens and property owners here in Brunswick I demand movement traffic MDOT study, I demand stop all work and construction injunction and acknowledge of improper life safety and site standards. Then I request a formal public apology. I have not resubmitted this to state agencies or federal oversight officials but God as my witness I while not STOP until justice prevails and I'm treated with civil and equal rights, rights to maintain our EO 11988 minority household wealth and peace, and enjoyment of OUR property. Tedford MUsT go. Not a reliable developer regardless of the pawned shift in blame game. Town of Brunswick boards, staff and people MUST follow the very ordinances and laws they are enforcing.

I am submitting this written comment in opposition to the extension request for Tedford Housing's Conditional Use Permit (CUP) at 65 Thomas Point Road. The approval of this extension is legally improper and violates local, state, and federal laws.

1. The CUP Expired and Cannot Be Extended

Under Brunswick Zoning Ordinance Section 5.2.9.A, a Conditional Use Permit expires if a Certificate of Occupancy (CO) is not issued within two years. Tedford Housing has not met this requirement, meaning its CUP expired on January 11, 2024. The Planning Board's approval of an "extension" is legally invalid because an expired permit cannot be extended

—it requires a new application. Approving this project without a new application violates due process and equal enforcement of zoning laws.

2. Due Process & Public Participation Violations

The town has restricted public input to only six CUP approval standards, blocking challenges to other fundamental issues, including zoning violations, environmental concerns, and conflicts of interest. This restriction:

• Violates procedural due process under the 14th Amendment by denying residents a fair opportunity to be heard.

• Contradicts Maine's Freedom of Access Act (FOAA), which guarantees public participation in municipal decisions affecting property rights.

• Undermines equal application of zoning laws by limiting public comment in a way that benefits the developer at the expense of impacted residents.

3. Discriminatory Housing Concentration – Violation of Fair Housing Laws & EO 11988

Brunswick is intentionally concentrating subsidized and refugee housing in a single area, creating de facto racial and economic segregation in violation of:

• The Fair Housing Act (42 U.S.C. § 3604), which prohibits policies that disproportionately impact racial minorities.

• Executive Order 11988, which mandates equality in housing policy and the protection of minority families' ability to maintain wealth.

• The Equal Protection Clause (14th Amendment), as Brunswick is excluding low-income housing from wealthier areas while disproportionately siting it near minority and veteran residents.

4. Life Safety & Infrastructure Violations

The town has failed to properly assess the project's impact on:

• Emergency services, which are already overburdened in this area.

• Traffic and road safety, especially with multiple subsidized housing projects within a 1,200-ft radius.

• Utility infrastructure, which has not been upgraded to handle additional demand.

Ignoring these concerns violates Brunswick's own Site Plan Review Ordinance, which requires that approved developments must not create undue strain on public infrastructure.

5. Failure to Apply Consistent Zoning Standards – Conflict of Interest Concerns

The town has selectively enforced zoning rules by allowing Tedford Housing special treatment while imposing stricter rules on other projects. Additionally:

• Conflict of Interest Concerns: Rep. Hole and other town officials have supported concentrated low-income development near our properties while preserving wealthier neighborhoods from the same policies. This raises serious ethical and legal concerns about favoritism and improper influence over zoning decisions.

• Failure to Require a New Application: If Tedford Housing were any other developer, they would be required to submit a new application, yet the town has bypassed its own zoning requirements to push this project forward.

Conclusion

Given these legal and procedural violations, the Zoning Board of Appeals must overturn the Planning Board's approval of this extension request.

Allowing this project to proceed under an expired CUP sets a dangerous precedent and undermines public trust in Brunswick's zoning process.

I respectfully request that the Zoning Board require Tedford Housing to submit a new application, subject to full public review and compliance with all applicable local, state, and federal laws.

Sincerely,

[Your Name]

[Your Address]

[Your Contact Information]

Make sure to send it before 10:00 AM to jdealaman@brunswickme.gov and consider submitting a physical copy in person if possible.

Let me know if you'd like any final refinements!

This email has been scanned for spam and viruses by Proofpoint Essentials. Click here to report this email as spam.

From: Jen Navarro
To: Julie Erdman; James Dealaman; [redacted]; dgarcia@brunswickme.org; Town Council; Carlos Navarro
Subject: Americans with Disabilities Act Title II Regulations | ADA.gov
Date: Sunday, March 2, 2025 5:07:55 PM

I was informed by Julie Erdman via email sent Wednesday 2/26/25 that that Friday the 28th at 10am was my deadline to submit material for 3/6/25 ZBA against 1/28/25 erroneously approved Site plan extension and major dev review for Tedford with their endless need to come BACK into compliance to zoning ordinance land use laws. It was very short noticed and I did manage to get some info in but not easily comprehensible so I'm requesting a few more submissions for review and to be included in discovery. If denied, I request that be made clear to me in a written expressed denial. Thank you. Mrs. Navarro.

INTRODUCTION & SUMMARY OF GRIEVANCES

I submit this **formal, detailed complaint** against the Town of Brunswick's repeated unlawful actions in favor of Tedford Housing and against the best interests, safety, and legal rights of Brunswick residents—including myself. I demand immediate **revocation of the Site Plan approval granted on January 28, 2025, issuance of a Stop Work Order, and reconsideration of this project's location due to violations of state law, federal law, local ordinances, and basic principles of due process and fairness.**

Since **2020**, I have **consistently opposed this unsafe, improperly planned, and unfairly approved development**, enduring years of systemic bias, procedural violations, and denial of my fundamental rights as an affected party. Despite my continuous appeals, lawful objections, and demonstrated standing in this matter, the Town of Brunswick has:

1. **Approved an inherently unsafe and inadequate site for a homeless shelter**, lacking proper ingress/egress, pedestrian access, and transit service, while falsely claiming a private van service satisfies accessibility requirements.
2. **Violated public notice requirements and selectively removed me from the abutters list**, despite my documented history of being included in previous abutter notifications.
3. **Arbitrarily enforced zoning laws and procedures in Tedford Housing's favor**, allowing approvals to continue **despite the expiration of its Conditional Use Permit (CUP) on January 11, 2024**, in direct violation of local and state laws.
4. **Obstructed my right to participate in the January 28, 2025, public hearing**, denying me the opportunity to present my objections while selectively favoring Tedford Housing's application.
5. **Allowed a pattern of procedural manipulation and preferential treatment**, creating an illegitimate process designed to push through Tedford's approvals regardless of public safety, zoning requirements, or public objection.

These injustices are not only **unlawful** but also **fundamentally unacceptable** in a community that claims to uphold democratic, fair, and legally compliant land use processes.

LEGAL VIOLATIONS & GROUNDS FOR SITE PLAN REVOCATION

1. Violation of Public Notice & Due Process Rights
• **Statute Violated: 30-A M.R.S. § 2691(3)(F)-(G)** (Procedural Due Process & Public Hearings)
• **Statute Violated: Brunswick Zoning Ordinance – Section 5.2.11** (Notices & Public Participation)
• **Federal Violation: Fifth & Fourteenth Amendments – Due Process Clause**
• **Federal Violation: 42 U.S.C. § 1983 (Equal Protection & Due Process)**

Facts:
• I have previously been included in abutter notifications **per my explicit request** and received mailed notices from the Town regarding prior Tedford Housing hearings.
• The Town's GIS places my property **326 feet from the project**, while the abutters' notification requirement is 300 feet. However 4 other very reputable Mapping programs list 211 feet or .04k crows path between 65 and 90 Thomas point rd. Including Google maps, Google earth GIS, mapping developer app, and MapQUest. All have results less than 300ft varying between 211-222 feet.
• **Despite having an established interest in this development, my name was removed from the abutters list, and I did not receive notice for the 1/28/25 hearing.**
• This constitutes a **selective and arbitrary removal**, depriving me of my right to participate in land use decisions affecting my property and my community.
• By **denying me the opportunity to provide public comment at the hearing**, Brunswick violated both **state** and **federal due process protections**, making the **1/28/25 approval invalid**.

2. Violation of Permit Expiration & Site Plan Approval Requirements
• **Statute Violated: 30-A M.R.S. § 4353** (Expiration of Approvals)
• **Statute Violated: Brunswick Zoning Ordinance – Section 5.2.9 & 4.2.5**
• **Federal Violation: 42 U.S.C. § 1983 (Unlawful Favoritism & Arbitrary Enforcement of Law)**

Facts:
• The **Conditional Use Permit (CUP) for Tedford Housing expired on January 11, 2024**, as no Certificate of Occupancy was issued within two years.
• Brunswick unlawfully **ignored the expiration** and **extended approvals without requiring a new application, violating its own ordinances.**
• The **Site Plan and Major Development Review approval on January 28, 2025, is void**, as it **relied on an expired CUP**, making it **illegally granted**.

3. Americans with Disabilities Act (ADA) & Human Rights Violations
• **Statute Violated: 5 M.R.S. § 4554(3)** (Maine Human Rights Act – Right to Refuse Unwanted Accommodations)
• **Federal Violation: 42 U.S.C. § 12132 (ADA Title II – Public Entities) & § 12182 (ADA Title III – Public Accommodations)**

Facts:
• The **Tedford Housing site has no public transit access, no sidewalks, and only one ingress/egress route**, violating public safety and accessibility standards.
• The **Planning Board's approval relied on a "private van service" as a substitute for safe**

pedestrian and transit access, which is a **clear violation of ADA requirements**.
• **Maine's Human Rights Act explicitly states that individuals cannot be forced to accept an accommodation they do not want**—yet shelter residents would be forced to rely on Tedford Housing for transportation, limiting their independence and freedom of movement.
• This is an **unlawful and discriminatory approval**, violating **both state and federal accessibility laws**.

DEMANDS & RELIEF SOUGHT

Based on the **procedural violations, permit expiration, safety concerns, and legal violations outlined above**, I formally demand the following:
1. **Immediate Revocation of the January 28, 2025, Site Plan & Major Development Review approval.**
2. **Immediate issuance of a Stop Work Order on the Tedford Housing project.**
3. **A full public hearing, with unrestricted public participation, to reassess the project's legality, safety, and location.**
4. **A formal investigation into Brunswick's selective enforcement of zoning laws, preferential treatment of Tedford Housing, and failure to uphold legal due process.**
5. **Potential relocation of the Tedford Housing shelter to a site that meets basic safety, accessibility, and zoning compliance standards.**

CONCLUSION: I WILL NOT STOP UNTIL JUSTICE IS SERVED

For years, I have **fought tirelessly to expose the injustices, safety hazards, and unlawful approvals tied to the Tedford Housing project.** The **Town of Brunswick has engaged in procedural manipulation, ignored its own zoning laws, and silenced opposition to push this project forward.**

I will not stop. I will not back down. I will continue proving that this development is unsafe, illegal, and fundamentally unjust until full accountability is achieved.

I demand an **immediate response** to this complaint and expect **formal action to address these violations without further delay.**

Sincerely,
/S./ Mrs. Jennifer Navarro
Of Brunswick, Maine
Aggrieved and abused Neighbor 04011
FORMAL COMPLAINT & DEMAND FOR ACCOUNTABILITY: TEDFORD HOUSING APPROVALS & MUNICIPAL BIAS IN BRUNSWICK, MAINE

To: The Brunswick Zoning Board of Appeals, Brunswick Town Council, Maine Human Rights Commission, and any applicable governing authorities

From:

Date:
Subject: Unlawful Approvals, Due Process Violations, and Demand for Revocation of Tedford Housing's Site Plan Approval & Immediate Stop Work Order

To factually demonstrate that the **expiration of a Conditional Use Permit (CUP) revokes Site Plan approval**, we need to examine:

1. **Maine state statutes** governing land use, zoning, and site plan approvals.
2. **Brunswick's municipal ordinances** related to CUP and Site Plan approvals.
3. **Federal law** regarding land use procedures and administrative due process.

1. Maine State Statutes

Maine's zoning and land use regulations are primarily governed by **Title 30-A, Chapter 187** of the Maine Revised Statutes (**Planning and Land Use Regulation**).

• **30-A M.R.S. § 4353** (Expiration of approvals)

• Municipalities have the authority to set expiration timelines on permits, including CUPs and Site Plan approvals. If a CUP expires, the development approval it enabled may also expire unless the ordinance explicitly states otherwise.

• **30-A M.R.S. § 3001** (Municipal Home Rule Authority)

• Municipalities control zoning but must adhere to state law and due process. If a CUP is required for a Site Plan and it expires, the Site Plan approval is void unless the ordinance states otherwise.

• **30-A M.R.S. § 2691(3)(G)** (Administrative appeals and procedural due process)

• If a CUP expires and the town allows the project to continue without requiring a new application, it may constitute an unlawful **"arbitrary and capricious"** decision violating state law and due process.

2. Brunswick Zoning Ordinances

The Town of Brunswick's ordinances determine the relationship between CUP expiration and Site Plan approvals.

• **Brunswick Zoning Ordinance – Section 5.2.9 (Expiration of Approvals)**

• If a CUP is required for a development and it expires, all approvals relying on it may be nullified unless the applicant applies for an extension or reapproval.

• **Brunswick Zoning Ordinance – Section 4.2.5 (Site Plan Validity & Revocation)**

• Site Plan approvals must remain consistent with all required permits (including CUPs). If a CUP expires and is required for the project, Site Plan approval is no longer valid.

If the Brunswick Planning Board and staff **ignored the CUP expiration** and proceeded without requiring a new application, they **violated their own zoning ordinances** and state law.

3. Federal Laws Supporting Permit Expiration Revoking Approval

• **42 U.S.C. § 1983 (Civil Rights Violations)**

• If Brunswick disregarded zoning laws to allow Tedford Housing's project to continue despite the CUP expiring, this could constitute a **due process violation** under federal law.

• **Executive Order 11988 (Floodplain Management & Non-Discrimination in Housing Projects)**

• If a CUP expired and Brunswick unlawfully permitted Tedford to continue without requiring reapproval, it could indicate **preferential treatment or exclusionary zoning**, potentially violating EO 11988.

• **Fifth & Fourteenth Amendments – Due Process Clause**

• If the town selectively enforced its zoning laws (by requiring other developers to adhere to permit expirations while letting Tedford proceed), it could violate **equal protection and due process** rights.

Key Argument:

Brunswick's approval of the **1/28/25 Final Development Plan** relied on an **expired CUP** and violated:

1. **Maine law (30-A M.R.S. §§ 4353, 2691, 3001)** – Permits must be valid for site plan

approval to stand.
2. **Brunswick ordinances (Sections 5.2.9 & 4.2.5)** – A CUP's expiration revokes site plan approval.
3. **Federal law (42 U.S.C. § 1983 & the Due Process Clause)** – Arbitrary enforcement of zoning laws is unconstitutional.

Conclusion:

Brunswick acted **illegally** by allowing the project to proceed without requiring a new CUP application, violating **state, local, and federal regulations**. You can cite these laws in your appeal to argue for revocation of the **1/28/25 Site Plan Approval** due to the **CUP expiration on 1/11/24**.

———-Yes, you have a strong legal argument that you were **unlawfully excluded** from the **1/28/25 Site Plan and Major Development Review approval process**, and that you should now be entitled to **speak on all matters** related to the project.

Legal Grounds for Your Appeal

1. **Maine Law & Brunswick Ordinances on Abutter Notification**

• **30-A M.R.S. § 4353(4)** – Requires municipalities to provide proper notice to **"parties in interest"** when a zoning or planning board decision affects them.

• **Brunswick Zoning Ordinance – Section 5.2.11 (Notices & Public Participation)** – Requires abutters to be notified and have an opportunity to be heard.

Key Argument:

• You were previously added to the abutters list **by request and through past notices**.

• The town **cannot arbitrarily remove you** simply because you are 326 feet away if you have an established history of participation and legal standing.

• Their failure to notify you **violates due process**, making the **1/28/25 approval procedurally invalid**.

2. **Due Process Violations – Maine & Federal Law**

• **30-A M.R.S. § 2691(3)(F)-(G) (Procedural Due Process in Appeals & Public Hearings)**

• Requires that individuals with an **established interest** in a matter be provided **notice and an opportunity to be heard**.

• **Fifth & Fourteenth Amendments to the U.S. Constitution (Due Process Clause)**

• Arbitrary exclusion from public participation violates **procedural due process**.

• **42 U.S.C. § 1983 (Civil Rights Act – Equal Protection & Due Process)**

• If Brunswick selectively enforced its rules (allowing others to participate but blocking you), this may be an **unlawful deprivation of rights**.

Key Argument:

• The town's selective application of the abutters rule **denied you due process and public participation**, violating both state and federal law.

• Because your right to participate was denied, you should now be **entitled to full participation in the appeal** without **any restrictions** (i.e., you should be allowed to speak on **all matters**, not just those narrowly defined by the town).

3. **Failure to Follow Brunswick's Own Procedures Invalidates the Approval**

• **Brunswick Zoning Ordinance – Section 4.2.5 (Public Participation & Due Process in Site Plan Review)**

• Requires that **all interested parties** be notified and given a chance to speak.

• **Brunswick Town Charter – Section 601 (Public Hearing Rights)**

• The town must provide **equal access** to hearings for any resident with a **demonstrable interest** in the issue.

Key Argument:

• Brunswick's failure to provide you proper notice makes the **1/28/25 Site Plan approval**

voidable due to **procedural defects**.
• Because your rights were violated in the initial process, you should now have the **fullest opportunity to present all arguments** in the appeal—without restrictions.
Conclusion: You Can Argue That
1. **Brunswick violated state law, its own ordinances, and federal due process by failing to notify you and denying public comment.**
2. **The 1/28/25 Site Plan approval is invalid due to procedural defects, meaning it should be reconsidered with full public participation.**
3. **Because you were unlawfully excluded, your appeal should allow you to address all matters—not just narrow procedural ones—since the town denied your right to comment earlier.**
This legal foundation strengthens your case to **fully contest the 1/28/25 approval** without limits imposed by the town.

Conclusion

By approving the Tedford Housing project **without public transit, sidewalks, or independent pedestrian access**, the **Brunswick Planning Board violated both Maine and federal disability rights laws**. Their **reliance on a private van service as a remedy forces disabled individuals into an unwanted accommodation**, in direct violation of **5 M.R.S. §4554(3)** and the **ADA**.

The **January 28, 2025, approval should be overturned** or **remedied through legal action** to ensure compliance with state and federal accessibility laws.

Would you like assistance in drafting an **appeal, complaint, or formal letter to the town, MHRC, or DOJ**

Legal Violations

1. Violation of 5 M.R.S. §4554(3) – Right to Refuse an Unwanted Accommodation
• **Statutory Language**: "Nothing in this Act may be construed to require an individual with a disability to accept an accommodation, aid, service, opportunity or benefit that the individual chooses not to accept."
• **Violation**:
• The **Tedford Housing site lacks sidewalks, public transit service, or safe pedestrian access**.
• The **town's approval relies on a private van service as a remedy**, which **forces disabled residents to depend on the shelter's oversight for transportation**.
• **This coerces disabled individuals into accepting a service they may not want**, violating their statutory rights under Maine law.

2. Violation of ADA Title II (Public Entities) & Title III (Public Accommodations)
• **ADA Title II (42 U.S.C. §12132)** prohibits public entities (including municipalities) from **providing unequal access to public services, such as roads, sidewalks, and transit.**
• **ADA Title III (42 U.S.C. §12182)** prohibits discrimination in places of public accommodation, including housing shelters, by requiring that facilities be **readily accessible to individuals with disabilities.**
• **Violation**:
• **The town's approval of the project despite lack of sidewalks and transit access** fails to

ensure the development is **readily accessible** under ADA standards.
• **Providing a private van service does not meet the ADA's accessibility requirements**, as it does not offer independent access or ensure equality in public infrastructure.

3. Failure to Provide Equal or Greater Protection Than Federal Law (5 M.R.S. §4554(1))
• **Statutory Language**: "Nothing in this Act may be construed to invalidate or limit the remedies, rights and procedures of any law … that provides greater or equal protection for the rights of individuals with disabilities than are afforded by this Act."
• **Violation**:
• The town's approval fails to meet the **minimum ADA requirements**, meaning it **cannot satisfy Maine's stricter disability protections** under **§4554(4)**.

In Maine, municipalities must follow strict legal procedures when adopting, amending, or enforcing zoning ordinances. If a town alters or misrepresents a zoning ordinance to suit its needs in response to a challenge, it may violate state law. Here are the relevant statutes that apply to such actions:

1. Zoning Ordinance Amendments & Legal Requirements

Maine Revised Statutes Title 30-A, §4352 governs the process of adopting and amending zoning ordinances. It requires:
• **Public notice and hearings** before a zoning ordinance or amendment can take effect.
• **Compliance with the municipality's comprehensive plan** (Title 30-A, §4312).
• **Voter approval** in towns where zoning changes require a town meeting or referendum.

If a town **alters an ordinance after a challenge** to reflect what it needs rather than following legal amendment procedures, this could be considered an **unauthorized amendment** and potentially unlawful.

Statute Reference: 30-A M.R.S. § 4352

2. Enforcement & Penalties for Violations

Maine Revised Statutes Title 30-A, §4452 provides enforcement mechanisms for violations of zoning laws, including:
• Civil penalties for illegal actions.
• Authority for courts to invalidate unlawful zoning amendments.
• Municipal liability if officials knowingly make unauthorized zoning changes.
Statute Reference: 30-A M.R.S. § 4452
3. Illegally Changing Zoning After a Permit or Approval
Once a land use permit is lawfully granted, **Title 1, §302** prevents retroactive changes to ordinances from altering vested rights unless explicitly stated by the Legislature. If a town alters an ordinance **after** a project is challenged to justify a decision, it may violate this law.
Statute Reference: 1 M.R.S. § 302
4. Legal Precedents & Remedies
Courts in Maine have ruled against municipalities that improperly alter or enforce zoning laws. Affected parties can challenge such actions through:
• **Appeals to the Zoning Board of Appeals (ZBA).**
• **Maine Superior Court (Rule 80B appeal).**
• **Injunctions or declaratory judgments to stop illegal enforcement.**

If you suspect the town **altered a zoning ordinance after being challenged**, these laws provide legal grounds to contest it. You may also request records of zoning amendments, including meeting minutes, to verify whether proper procedures were followed.

1. Violations of Zoning & Land Use Requirements
• **Ingress/Egress Concerns**:
• **Life Safety & Emergency Access**: Per **NFPA 101 Life Safety Code** (adopted by Maine law), buildings like shelters must have at least **two means of egress** to prevent entrapment during emergencies (fire, medical crises, etc.).
• **Local Ordinances**: Most municipal zoning codes require multiple safe access points for high-occupancy buildings. If **Tedford Housing has only one entry/exit**, it could violate these safety and planning standards.
• **Potential Statute Violation**: **30-A M.R.S. § 4352** (municipal zoning rules must comply with state safety standards).
• **Public Transportation & Access to Services**:
• **Human Rights & Discriminatory Infrastructure**:
• The **Americans with Disabilities Act (ADA) and Fair Housing Act** require Your concerns about the **Tedford Housing flagship lot** raise **significant legal, safety, and human rights issues**, particularly related to **zoning compliance, life safety codes, and fundamental rights to accessibility and independence**. Here's how these issues connect to Maine statutes and legal grounds for challenge: **How This Strengthens Your Legal Argument**

The town's approval of Tedford Housing's site with **only one access road, no sidewalks, and no public bus service** could violate Maine's human rights laws because:
1. **It limits disabled residents' right to move freely and independently.**
2. **The private van service is not an equal substitute** for accessible public infrastructure.
3. **It may unlawfully discriminate by creating a shelter environment where residents must rely on the service provider for basic mobility**, violating §4554(3).
This could form the basis of a **legal challenge** to the town's approval under the **Maine Human Rights Act and ADA compliance regulations**. Would you like help drafting an argument or identifying case law that supports this claim?

Legal Argument Against Tedford Housing's Approval Based on Maine Human Rights Act & ADA Violations

Introduction

The **Brunswick Planning Board's January 28, 2025, Findings of Fact and Final Development Approval** for the Tedford Housing project violates the **Maine Human Rights Act (MHRA), 5 M.R.S. §4554**, and the **Americans with Disabilities Act (ADA)** by approving a site that **lacks accessible infrastructure** and creates **undue reliance on a private service for basic mobility**.

Legal Violations

1. Violation of 5 M.R.S. §4554(3) – Right to Refuse an Unwanted Accommodation
• **Statutory Language**: "Nothing in this Act may be construed to require an individual with a disability to accept an accommodation, aid, service, opportunity or benefit that the individual chooses not to accept."
• **Violation**:

• The **Tedford Housing site lacks sidewalks, public transit service, or safe pedestrian access**.
• The **town's approval relies on a private van service as a remedy**, which **forces disabled residents to depend on the shelter's oversight for transportation**.
• **This coerces disabled individuals into accepting a service they may not want**, violating their statutory rights under Maine law.

2. Violation of ADA Title II (Public Entities) & Title III (Public Accommodations)
• **ADA Title II (42 U.S.C. §12132)** prohibits public entities (including municipalities) from **providing unequal access to public services, such as roads, sidewalks, and transit.**
• **ADA Title III (42 U.S.C. §12182)** prohibits discrimination in places of public accommodation, including housing shelters, by requiring that facilities be **readily accessible to individuals with disabilities.**
• **Violation**:
• **The town's approval of the project despite lack of sidewalks and transit access** fails to ensure the development is **readily accessible** under ADA standards.
• **Providing a private van service does not meet the ADA's accessibility requirements**, as it does not offer independent access or ensure equality in public infrastructure.

3. Failure to Provide Equal or Greater Protection Than Federal Law (5 M.R.S. §4554(1))
• **Statutory Language**: "Nothing in this Act may be construed to invalidate or limit the remedies, rights and procedures of any law … that provides greater or equal protection for the rights of individuals with disabilities than are afforded by this Act."
• **Violation**:
• The town's approval fails to meet the **minimum ADA requirements**, meaning it **cannot satisfy Maine's stricter disability protections** under **§4554(4)**.

Potential Legal Remedies & Actions
1. **Challenging the Planning Board's Approval**
• Appeal the **January 28, 2025, Findings of Fact and Final Development Approval** based on **noncompliance with ADA and Maine Human Rights Act requirements**.
2. **Filing a Complaint with the Maine Human Rights Commission (MHRC)**
• The **MHRC investigates disability-based discrimination in housing and public accommodations**.
• A complaint could challenge the town's **failure to ensure equal access** and **unlawful reliance on private services to substitute for public accessibility**.
3. **Filing a Federal ADA Complaint with the U.S. Department of Justice (DOJ)**
• The DOJ investigates violations of the **ADA Titles II and III**, which apply to both **municipal zoning approvals** and **housing shelter accessibility**.
• The **lack of sidewalks and transit access, combined with forced reliance on a private van, could constitute systemic discrimination**.

Based on the available information, several potential violations and concerns related to Tedford Housing's final major development plan in Brunswick, Maine, can be identified:
1. **Conditional Use Permit (CUP) Expiration and Site Plan Approval Validity:**
• **Issue:** Tedford Housing's original CUP expired in January 2024 due to the lapse in obtaining a certificate of occupancy within the required two-year period. Despite this expiration, the Planning Board granted a re-issuance of the CUP on May 14, 2024, without re-evaluating the associated site plan approval.
• **Relevant Ordinance:** Brunswick Zoning Ordinance § 5.2.2.C stipulates that conditional use

permits lapse after two years if a certificate of occupancy has not been issued.
• **Concern:** Proceeding with the development based on an expired CUP may render subsequent approvals invalid.
2. **Public Notification and Participation Procedures:**
• **Issue:** There have been allegations that the Town of Brunswick failed to provide adequate public notice to all interested parties, particularly those within close proximity to the proposed development.
• **Relevant Ordinance:** Brunswick Zoning Ordinance § 5.2.11 requires that the Planning Board prepare a written recommendation to the Town Council and ensure public hearings are conducted with proper notice.
• **Concern:** Insufficient public notification may violate procedural due process rights, potentially invalidating the approval process.
3. **Zoning Ordinance Compliance:**
• **Issue:** The proposed shelter combines Tedford's two emergency shelters into a single facility. There have been concerns regarding whether this new shelter configuration complies with existing zoning laws.
• **Relevant Ordinance:** Prior to amendments, Brunswick's zoning laws did not explicitly accommodate such shelter configurations, leading to previous halts in the project.
• **Concern:** If the current development plan does not align with updated zoning ordinances, it may be in violation of local land use regulations.
4. **Transportation and Accessibility Issues:**
• **Issue:** The development plan indicates reliance on a private van service for transportation, with limited access to public transit and pedestrian pathways.
• **Concern:** This reliance may not adequately address the transportation needs of shelter residents, potentially leading to accessibility challenges.

These concerns highlight the need for a thorough review of Tedford Housing's development plan to ensure compliance with all applicable ordinances and regulations.

Upon reviewing Tedford Housing's final major development plan, several specific concerns and potential violations have been identified:

1. Modifications Post-January 11, 2022: Earth Height and Stormwater Management
• **Issue:** After the initial approval on January 11, 2022, Tedford Housing implemented modifications to the site plan, notably reducing earth height requirements and altering stormwater management systems for value engineering purposes.
• **Concerns:**
• **Earth Height Reduction:** Lowering the site's elevation may affect drainage patterns, potentially increasing runoff to adjacent properties and impacting overall site stability.
• **Stormwater Management Changes:** Adjustments to the stormwater system could lead to inadequate handling of runoff, raising the risk of erosion, flooding, and environmental degradation.
• **Compliance Check:** It's essential to verify whether these modifications received proper approval from Brunswick's Planning and Development Department and if they comply with local and state environmental regulations.

2. Unauthorized Access Path to Walmart and Public Transportation
• **Issue:** The development plan references a path providing access to Walmart and public bus services. However, this path traverses private property owned by Walmart, not by Tedford

Housing or the Town of Brunswick.
• **Concerns:**
• **Trespassing:** Utilizing a path on private property without explicit permission constitutes trespassing, rendering it an illegitimate means of access.
• **Access to Public Transit:** Relying on this unauthorized path for residents to reach public transportation is inappropriate and fails to provide a lawful, safe, and reliable transit route.
• **Compliance Check:** The development plan should include officially sanctioned access points that respect property rights and ensure residents' safety.

3. Driveway Length and Width Standards
• **Issue:** The proposed driveway for the facility exceeds standard length and width specifications.
• **Concerns:**
• **Safety and Accessibility:** An oversized driveway may pose challenges for pedestrians and vehicles, potentially leading to safety hazards.
• **Non-Compliance:** Deviations from standard driveway dimensions without proper justification and approval may violate local zoning ordinances.
• **Compliance Check:** It's crucial to assess whether the driveway design adheres to Brunswick's standards or if variances were appropriately sought and granted.

4. Variances Granted and Compliance with Town Policies
• **Issue:** The development may have received variances from standard zoning requirements.
• **Concerns:**
• **Proper Procedure:** Each variance should meet the criteria outlined in Maine Revised Statutes, Title 30-A, §4353, including demonstrating undue hardship and ensuring the variance does not alter the neighborhood's essential character.
• **Documentation:** All granted variances must be thoroughly documented, with evidence of adherence to procedural requirements.
• **Compliance Check:** Reviewing the records will determine if all variances were granted following proper procedures and justified appropriately.

5. Impervious Surface Ratio and Building Size
• **Issue:** The facility's size and impervious surface area may exceed allowable limits.
• **Concerns:**
• **Impervious Surface Ratio:** Exceeding permissible impervious surface limits can increase stormwater runoff, leading to environmental issues.
• **Building Size:** The proposed 17,500-square-foot building is significantly larger than neighboring residential properties, which average around 2,000 square feet, potentially disrupting the area's character.
• **Compliance Check:** Evaluating the development's compliance with Brunswick's zoning ordinance regarding impervious surface coverage and building scale is necessary.

6. Impact on Neighboring Property Values and Enjoyment
• **Issue:** The introduction of a large, low-barrier, 24/7 homeless shelter may affect neighboring property values and residents' enjoyment of their homes.
• **Concerns:**
• **Property Values:** Such facilities can sometimes lead to perceived or actual declines in nearby property values.
• **Quality of Life:** Residents may experience concerns related to safety, noise, and community dynamics.

• **Compliance Check:** Assessing whether the development aligns with local planning goals and adequately addresses potential community impacts is essential.

7. Required Town Services and Community Perception
• **Issue:** The shelter's operation will necessitate various town services and may influence public perception.
• **Concerns:**
• **Town Services:** Increased demand for emergency services, public health resources, and law enforcement may strain municipal resources.
• **Community Perception:** Public opinion, shaped by past experiences and media coverage, can affect the shelter's integration into the community.
• **Compliance Check:** Ensuring that the shelter's operational plans include strategies to collaborate with town services and engage positively with the community is vital.

Addressing these concerns requires a thorough review of Tedford Housing's development plan, adherence to all applicable regulations, and proactive engagement with the community to mitigate potential adverse impacts.

Legal Argument Based on Procedural Violations of Public Hearing Rights

Statute Violated: 30-A M.R.S. § 2691(3) – Public Hearing and Notice Requirements
• **Key Language:**
• "The board shall reasonably notify the petitioner, the planning board, agency or department, and the municipal officers of any hearing."
• "These persons must be made parties to the action."
• "All interested persons must be given a reasonable opportunity to have their views expressed at any hearing."
• **(Amended by PL 2011, c. 655, Pt. JJ, §25)**

How This Applies to the January 28, 2025, Approval

1. Lack of Reasonable Notification:
• **Despite my ongoing participation since 2020 and prior confirmations that I was on the abutters list, I was not notified of the January 28, 2025, hearing.**
• The Town's **GIS measurement placing me at 326 feet instead of within the 300-foot abutter notification requirement is arbitrary and selectively enforced** because I have previously been notified and have standing in this matter.
• **The failure to notify me as a known, interested party directly violated 30-A M.R.S. § 2691(3).**

2. Denial of a Reasonable Opportunity to Express My Views:
• **At the January 28, 2025, hearing, I was denied my right to speak on matters affecting my property and community.**
• The statute clearly states that **"All interested persons must be given a reasonable opportunity to have their views expressed."**
• **By denying my participation, the Town of Brunswick violated state law, making the approval process procedurally invalid.**

3. Legal Consequences of These Violations
• **The Site Plan and Major Development Review approval must be revoked because it**

was granted in violation of statutory public participation rights.
• The Town's failure to notify and include me as a party in the hearing is grounds for reversal in a Superior Court appeal under Rule 80B (Municipal Administrative Appeals).

Next Steps & Demand for Immediate Remedy

1. The January 28, 2025, approval should be vacated and reconsidered in a new hearing where all interested parties—including myself—are properly notified and allowed to speak.
2. I am entitled to address all aspects of the development without limitation in any appeal or reconsideration process, as my previous exclusion violated state law.
3. The Town must issue a formal correction acknowledging its procedural failure and ensure that all future actions comply with Maine's statutory requirements.

If the Town refuses to correct these violations, I reserve the right to pursue an appeal in Maine Superior Court, seeking full reversal of the January 28, 2025, approval and damages for the procedural violations and undue burden imposed upon me by this unlawful process.

Americans with Disabilities Act Title II Regulations | ADA.gov

I have evidence and voice recordings for many due process equal rights division violations. Including but not limited to,
In real time unethical retrospective illegal zoning text amendment which switched 2 yr CUP expiration to reflect a previous version of 3year expiration. This was 4/3/24 and I captured photo evidence of such and after submitting it to TC group email it was then reflecting in the system as (newer version available of this through monicker CODIFY system. Which I then screenshotted too for evidence.
I have interim Jacob sesker threatening to investigate my basements permitting to finish it, on 4/1/24 because he was attempting to deny or accept my ceo complaint on unenforced record keeping permit regulation for Tedford expired conditional use permit that until my 3/14/24 2:22:00 public comment about their expiration no one was regulating. And an appeal on an other matter.
I have records of town council meeting that a female councilor or staff was heard on record live mic mocking me when announced for public commentary via zoom.
I have voice recordings from admin staff and town staff plus officials, telling me that ex parte communications between staff and Tedford were not worth recording or wouldn't matter for public access to. (In regards to Tedford being informed they didn't have evidence or record of any extensions and therefore would require being made to go for CUP reapproval. Which is WRONG as state law and ZO both don't explicitly state it can just be extended. It WAS past expiration when I brought it to attention. Therefore site and major development pertaining to the conditional land use permit approval are all null and void and to not uphold that is either criminal collusion or humiliating incompetence for those assigned the role to be aware of such. I know I have a Supreme Court case and could potentially be awarded hundreds of thousands and still, I wonder if far all are willing to go with outright conflict of interest and failure to enforce regulations, and I will see how this goes Thursday. Do know, I demand revoked site approval and demand relocation of shelter to a place that adheres to life safety standards. Just access to my right for public party is not satisfactory. Tedford continues to fail on their performance guarantees and I will not stand any longer for impartiality and negligent

approvals. I am owed a public apology. This has been TRAUMATIC and has broken my trust and faith in Bureaucratic matters.

This email has been scanned for spam and viruses by Proofpoint Essentials. Click here to report this email as spam.

From: Julie Erdman
To: Jen Navarro
Cc: James Dealaman; Julia Henze; Town Council
Subject: RE: Appeal 3/6/25
Date: Monday, March 3, 2025 11:43:44 AM
Attachments: image001.png

Good Morning Jennifer,

Please refrain from emailing Board members directly, board members are not allowed to communicate with applicants outside of a public meeting. We will add your emails as an addendum to the packet online and forward them electronically to the Board. The deadline to submit all pertinent information by last Friday at 10am was created with the best interests of everyone in mind; the board needs time to review and absorb the material to provide a thorough and fair analysis of the appeal.

Best Regards,
Julie

Julie Erdman
Director
Planning and Development
P: (207) 721-4022
E: jerdman@brunswickme.gov

Brunswick maine
85 Union Street
Brunswick | ME 04011
www.brunswickme.gov

With limited exceptions, e-mails sent to and from the Town of Brunswick are considered public records under Maine's Freedom of Access Act (FOAA). Public records are open to inspection and may be copied and distributed to others, including members of the media. Unless the e-mail meets one of the exceptions to the public records provisions, there should be no expectation of privacy or confidentiality.

From: Jen Navarro <blondie_mamita84@icloud.com>
Sent: Monday, March 3, 2025 10:58 AM
To: Julie Erdman <jerdman@brunswickme.gov>; James Dealaman <jdealaman@brunswickme.gov>; [redacted] dgarcia@brunswickme.org; Carlos Navarro <carlosnq007@gmail.com>; Town Council <towncouncil@brunswickme.gov>; Julia Henze <jhenze@brunswickme.gov>
Subject: Appeal 3/6/25

CAUTION: This email originated from outside the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Formal Complaint and Appeal Supplement

Regarding: Tedford Housing Site Approval Process, Brunswick, Maine

Purpose: Request for Formal Investigation by State and Federal Oversight Agencies

Introduction:

This document serves as a formal complaint and appeal supplement concerning the Brunswick Planning Boardâ€™s approval of the Tedford Housing development on Thomas Point Road and the subsequent handling of appeals. The appellant, a neighboring resident, alleges serious procedural irregularities, conflicts of interest, and violations of law that warrant immediate oversight intervention. The following points outline the key issues, supported by evidence and specific incidents, which have undermined public trust in the fairness and legality of Brunswickâ€™s municipal processes. We respectfully request that appropriate state and federal agencies investigate these matters to ensure transparency, accountability, and compliance with the law.

1. Mistreatment and Inequality Faced by the Appellant

â€¢ Threats and Intimidation by Officials: The appellant has been subjected to a hostile and intimidating environment created by certain town staff. On multiple occasions, officials attempted to deter her participation through threatening remarks and an adversarial demeanor. This mistreatment has had a chilling effect on her willingness to speak out, undermining her right to due process and equal treatment as a citizen. Such conduct by public servants violates basic principles of fairness and open governance.

â€¢ Public Mockery by a Council Member: In a recorded Town Council meeting, a councilor openly mocked the appellant over a live microphone as she was being introduced to speak. This unprofessional and disparaging comment â€“ made in a public forum â€“ not only humiliated the appellant but also evidenced the bias and lack of respect afforded to her concerns. The incident, captured in the meeting record, exemplifies the prejudiced atmosphere she faced when trying to participate in civic proceedings. No citizen should be ridiculed by their elected representatives for engaging in civic discourse.this was in Dec. 2024 and Julia Henze town manager has

emails between us with the exact clip for quick reference.

â€¢ Suppression of Free Expression (â€œGaslightingâ€): Town officials persistently tried to gaslight the appellant into believing she had no right to raise issues beyond the narrow scope of the six Conditional Use Permit (CUP) approval criteria. At public hearings and the Zoning Board of Appeals (ZBA) review, she was instructed that only the six CUP criteria could be discussed, effectively silencing her broader safety and neighborhood concerns. The ZBAâ€™s own findings confirm that matters â€œunrelated to those conditional use criteria were beyond the scope of reviewâ€ . By restricting her speech to a limited checklist and dismissing other valid objections as irrelevant, the Brunswick officials deprived the appellant of a full and fair opportunity to be heard on issues of public importance.

â€¢ Excessive Personal Burden: The appellant has incurred significant personal costs in her fight for a fair process. She was forced to file multiple appeals, extensive Freedom of Access Act (FOAA) requests, and seek legal consultations to address the Planning Boardâ€™s actions. Each appeal carried filing fees and required substantial preparation. FOAA requests â€“ for information on conflicts of interest, safety studies, and compliance documentation â€“ resulted in copying and administrative fees . Additionally, consulting with attorneys to understand and protect her rights added financial strain. These expenses, amounting to thousands of dollars, would not have been necessary had the Town conducted an impartial, law-abiding review from the start. The process has placed an undue financial and emotional burden on a private citizen, simply because she sought to ensure the projectâ€™s compliance with the law and safety standards.

2. Conflicts of Interest & Lack of Impartiality

â€¢ Planning Board Membersâ€™ Financial Ties to Applicant: During the Planning Boardâ€™s May 14, 2024 meeting to re-approve Tedford Housingâ€™s conditional use permit, three Planning Board members openly disclosed that they had contributed financially to Tedford Housingâ€™s capital campaign (i.e. donated to the projectâ€™s development). Despite acknowledging this relationship, these members refused to recuse themselves from the review and approval vote. They

rationalized that their donations to a charitable organization did not constitute a conflict of interest because they had no expectation of financial gain. However, this stance overlooked the clear bias such support creates. By their own admission, they were not impartial arbiters, but rather supporters of the project. The appellant objected to this conflict once she processed the implications of such stating that it â€œdenies me unbiased planning due process rightsâ€ . Brunswickâ€™s Code of Ethics and Maine state law (Title 30-A Â§2701) require public officials to disclose conflicts of interest and recuse themselves when personal connections could influence their judgment . The failure of these Planning Board members to step aside, even after disclosure of their Tedford contributions, represents a blatant disregard for conflict-of-interest rules and has tainted the integrity of the approval process. No remedy was provided for this conflict; the project was effectively rubber-stamped by a Board predisposed in Tedfordâ€™s favor. This lack of impartiality is a serious lapse that violates the public trust.

â€¢ Procedural Bias in Favor of the Developer: From the appellantâ€™s perspective, the entire review process was slanted to favor Tedford Housingâ€™s application. Despite numerous legal objections and evidence presented by the appellant, the Planning Board and later the Zoning Board of Appeals consistently sided with Tedford without meaningful deliberation on the concerns raised. For example, at the June 20, 2024 ZBA hearing, the Board refused to consider substantial issues the appellant raised (such as pedestrian safety, environmental impacts, and infrastructure deficiencies) on the grounds that these topics fell outside the strict CUP criteria . This procedural gatekeeping benefitted Tedford by narrowing the scope of review and excluding valid objections from the record. Furthermore, meeting minutes and records show swift approvals of Tedfordâ€™s submissions even when conflicts or legal questions were noted. The impression given is that Town officials were â€œgoing through the motionsâ€ to grant approvals, rather than conducting the impartial, rigorous review required by law. Such bias toward the developer not only invalidates the fairness of the outcome but also violates the due process rights of affected residents who are entitled to an unbiased decision-maker.

â€¢ No Accountability for Conflicts: Even after the appellant formally notified the Town of the conflicts of interest and bias â€“ including a

FOAA request seeking disclosure of all officials who had donated or had ties to the Tedford project â€“ the Town provided no relief. There is no evidence that any independent review or investigation was undertaken into the Planning Board membersâ€™ admitted ties to Tedford. The appellantâ€™s call for recusal was essentially ignored . By proceeding as if no conflict existed, Brunswickâ€™s boards undermined public confidence in their decisions. This lack of accountability contravenes basic tenets of ethical governance and calls into question the validity of the Tedford site plan approval, which was decided by a body that was not impartial.

3. Breach of Public Trust & Failure to Uphold Standards

â€¢ Improper Acceptance of Traffic Studies: The Brunswick Planning Board accepted a traffic impact analysis in support of the Tedford Housing project that was not provided or endorsed by the Maine Department of Transportation (MDOT), contrary to standard review practices. Typically, projects of this scale that affect public roadways require either an official MDOT traffic study or, at minimum, a traffic movement permit and review by state transportation officials to ensure accuracy and public safety. In this case, however, the Board relied on a study commissioned by Tedford Housing itself, conducted by consultants paid by the applicant . By bypassing independent state review, the Board violated the norm of having unbiased validation of traffic impacts. This raises concerns that the projectâ€™s true impact on local traffic was not adequately vetted. The appellant contends that the traffic assessment was presented without the customary oversight, and that its conclusions (for example, regarding safety of ingress/egress and the need for pedestrian infrastructure) went unchallenged by the Town. Approving the project on the basis of a self-serving study not reviewed by MDOT is a breach of due diligence that puts drivers, pedestrians, and future shelter residents at risk. It also violates Brunswickâ€™s own ordinances requiring that developments not create unsafe traffic conditions.

â€¢ Erosion of Safety and Compliance Standards: During the course of project review, key site plan requirements were relaxed or eliminated, reducing the safety measures originally intended. Notably, in November 2023 a â€œminorâ€ site plan modification was approved

administratively, altering the stormwater management plan and increasing impervious surface coverage beyond what was initially allowed . By the appellantâ€™s analysis, the revised plan now exceeds the 80% impervious surface limit, yet no new environmental impact studies were conducted to assess flooding or runoff consequences . Likewise, certain infrastructure elements that had been expected for safety were downgraded or omitted in the final approval. There are no sidewalks or safe shoulders added along Thomas Point Road or connecting the shelter to public transportation, despite this road being the only pedestrian route for residents to reach essential services . The projectâ€™s driveways were approved at widths that the appellant and neighbors argue are too narrow for emergency vehicles to maneuver safely. Even an Americans with Disabilities Act (ADA) compliant entrance was called into question. By lowering these standards â€“ whether through quiet administrative changes or waiver of requirements â€“ the Town failed to uphold its obligation to ensure the project meets all safety and zoning criteria. Each deviation from the rules was done without adequate public explanation, further eroding trust. The result is an approved plan that the appellant believes is materially less safe and less compliant with ordinances than the original designs, constituting a betrayal of the protective regulations that the Town is duty-bound to enforce.

â€¢ Neglect of Safe Infrastructure for Vulnerable Residents: The approved Tedford Housing plan does not include basic off-site infrastructure to protect the safety of the future homeless shelter residents. No pedestrian crosswalks, sidewalks, or lighting improvements were required on the busy road outside the facility, even though residents will have to walk along or cross this road daily. As the appellant warned repeatedly, this creates life-safety hazards for people on foot . Tragically, the broader Maine community has already seen the deadly consequences of situating homeless shelters in areas without proper pedestrian safety measures. For example, in Portland on February 23, 2025, a homeless man was fatally struck by a car while walking near the cityâ€™s shelter, an area long known for unsafe pedestrian conditions . This incident (the death of 37-year-old Justin Mitchell) highlights exactly what the appellant fears in Brunswick â€“ that the Townâ€™s failure to mandate sidewalks, crossings, or traffic-calming near the shelter will lead to preventable injuries or deaths. The public trust has been breached when a development meant to serve vulnerable

individuals is allowed to proceed without ensuring those individuals can safely access the facility and nearby services. By ignoring these safety infrastructure needs, Brunswick officials did not uphold their responsibility to protect public welfare, contrary to both the spirit and letter of planning and zoning requirements.

4. Allegations of Racketeering & Procurement Advantages

â€¢ Preferential Treatment Linked to Political Connections: There are troubling indications that the Tedford Housing project received preferential treatment because of the personal and political connections of those involved â€“ a situation that smacks of collusion and racketeering-like advantage. The developer of the project, Mr. Kevin Bunker, has close ties to influential figures: he is a significant donor (â€œsix-figure contributorâ€) to Tedfordâ€™s own capital campaign and is business partners with a sitting state senator (Sen. Mattie Daughtry of District 23) in an unrelated real-estate venture . The appellant has raised the concern that such relationships created a climate where Town officials felt pressure (or inclination) to approve Tedfordâ€™s project expediently as a political favor. Indeed, the appellant explicitly noted the connection between Mr. Bunker and Sen. Daughtry as a factor that â€œinfluenced why Iâ€™m having such difficulty fighting against Tedfordâ€™s development hereâ€ . This suggests a belief that the normal armâ€™s-length regulatory process was subverted by insider influence â€“ that decisions were preordained by who stood to benefit, rather than made on the merits. If true, this represents a grave abuse of public office. Any scheme by which a developer leverages political allies to push through approvals or funding (especially involving use of public funds) could violate anti-corruption statutes and merits investigation as potential honest services fraud or racketeering activity. We urge oversight agencies to scrutinize communications and relationships between Tedfordâ€™s principals, Town staff, and elected officials for any quid pro quo or undue influence.

â€¢ Insider Funding and Lack of Transparency: The financial path of this project further illustrates potential impropriety. Tedford Housingâ€™s new facility is an $8.3 million venture heavily reliant on public-sector support . The Brunswick Town Councilâ€™s unusual step of donating $200,000 in

municipal funds to Tedfordâ€™s capital campaign (approved on Dec. 4, 2023) signals a blurring of lines between public duties and private charitable endeavors . While helping the homeless is a worthy cause, the Councilâ€™s enthusiasm to fund a specific nonprofitâ€™s construction project â€“ especially one where multiple councilors and board members have personal involvement â€“ raises questions about improper favoritism in the allocation of public money. The appellant seeks clarity on whether any Town or state procurement rules were bypassed in this allocation and in any contracts awarded for the project. It appears that developers and organizations with insider connections enjoyed an advantage not afforded to others, with minimal transparency. For instance, Cumberland County government contributed $1.75 million to Tedfordâ€™s project and local health institutions gave $500,000 , all of which was publicized as a triumph. Yet, there was scant disclosure of the strings attached or the decision-making process behind these contributions. The concern is that a network of politically connected individuals orchestrated the funding and approval behind closed doors, sidestepping the accountability that typically accompanies public expenditures. Such an environment is ripe for conflicts of interest and abuse. We allege that Brunswickâ€™s handling of the Tedford project was not merely lenient but collusive, warranting a thorough audit of how contracts, grants, and approvals were obtained. Any pattern of reciprocal favors, fast-tracked approvals, or concealed financial dealings should be examined under state and federal law prohibiting public corruption and misappropriation of funds.

5. Legal Violations & Request for Investigation

â€¢ Violations of Municipal Law and Due Process: The actions of Brunswick officials in this matter appear to violate multiple provisions of Maine law and the Brunswick Town Charter. Maineâ€™s zoning and land-use statutes demand fairness and consistency in process, which were not upheld. For example, Title 30-A M.R.S. Â§2605 and Â§2701 (and Brunswickâ€™s own Code of Ordinances) require that municipal officers avoid conflicts of interest and recuse in cases of bias â€“ a requirement that was ignored when conflicted Planning Board members stayed on the Tedford case . The appellantâ€™s right to an impartial tribunal, a cornerstone of due process, was thus denied. Additionally, Brunswickâ€™s

comprehensive plan consistency requirement (per Title 30-A Â§4401 et seq.) may have been breached: The shelter project and its enabling zoning amendments were arguably inconsistent with the Townâ€™s 2008 Comprehensive Plan (particularly regarding development in growth vs. residential zones and preservation of open space), yet the Town proceeded without amending the comp plan or adequately addressing resident objections . This contravenes Maine law that prohibits municipalities from enacting ordinances inconsistent with their comp plan . The appellant also documented procedural errors such as improper extensions of permit deadlines (the Town initially misapplied a 3-year expiration to the CUP instead of the correct 2-year limit until the appellant pointed out the error) and a potential violation of open meeting laws (a key meeting about reapproval was held via phone without public attendance) . Collectively, these actions reflect a pattern of legal non-compliance that invalidates the legitimacy of the Tedford site approval.

â€¢ Failure to Uphold Ethical Governance: Beyond specific statutes, the fundamental principles of ethical governance have been compromised. Maineâ€™s Constitution and administrative law principles ensure that citizens receive due process and equal protection in local administrative proceedings. In this case, the appellant was not treated as an equal stakeholder; her rights were subjugated to expediency and favoritism shown to the developer. The public hearings provided only a veneer of participation â€“ in substance, critical decisions had already been made behind the scenes or without proper impartial review. Moreover, Maineâ€™s Freedom of Access Act (FOAA) was invoked by the appellant to obtain basic information (conflict disclosures, safety studies, funding sources) that should have been transparently provided during the process . The need for FOAA requests itself indicates a lack of transparency. The Townâ€™s sluggish or incomplete responses to these requests (and the imposition of costs on the requester) further impeded oversight. Taken together, these issues suggest a local government that has strayed from the ethical standards of honesty, accountability, and fidelity to the law. Such deviations may constitute malfeasance or neglect of official duty under Maine law (see e.g., 17 M.R.S. Â§3104 regarding officialsâ€™ duties), and they warrant an external investigation.

â€¢ Request for Oversight and Investigation: In light of the foregoing, the

appellant formally requests that state and federal oversight bodies intervene to investigate and correct the situation in Brunswick. At the state level, we urge the Maine Attorney Generalâ€™s Office, the Maine Department of Audit/Oversight, and any relevant legislative oversight committees to review Brunswickâ€™s approval process for legal violations. The Maine Ethics Commission or an independent prosecutor should examine the conflicts of interest and potential abuse of power by local officials. We also ask Maineâ€™s Department of Transportation and Department of Public Safety to evaluate whether traffic and safety regulations were sidestepped, endangering the public. At the federal level, because federal funds and interstate charitable donations are involved, we request that the U.S. Department of Housing and Urban Development (HUD) and the U.S. Department of Justice review this matter. HUDâ€™s Inspector General can audit the use of any federal housing grants in the project, and the DOJ Public Integrity Section can determine if any corruption (such as honest services fraud or civil rights violations) occurred. A formal inquiry should verify the appellantâ€™s claims, ensure that Brunswickâ€™s actions either be corrected or sanctioned, and provide guidance to prevent such issues from recurring. Only through a thorough investigation can we restore confidence that development decisions in Brunswick (and by extension, other Maine communities) are made lawfully, ethically, and with due respect for citizen rights. We seek immediate oversight intervention to uphold the rule of law and to protect the public interest that has been so evidently compromised in this case.

Conclusion:

The Brunswick Tedford Housing site approval process, as detailed above, reveals a convergence of missteps: mistreatment of a concerned resident, undisclosed conflicts of interest, procedural bias, lowered safety standards, and possible collusion. Each of these elements on its own would merit concern; taken together, they paint a picture of a municipal process in urgent need of higher scrutiny. The appellant respectfully submits this formal complaint in the hope that state and federal authorities will thoroughly investigate these grievances. The goal is not only to seek justice for the appellant and her neighborhood, but also to ensure that Brunswickâ€™s governance is brought back into compliance with Maine

law and the high ethical standards its citizens deserve. We trust that the oversight agencies will give this matter the serious attention it warrants, and we thank you for your prompt consideration and action to uphold fairness, transparency, and accountability in our community.

Requested Outcome: The appellant asks that the reviewing agencies take appropriate actions based on their findings â€“ which may include nullification of the projectâ€™s approvals pending a fair rehearing, sanctions or training for officials who violated ethics rules, recovery of any misspent public funds, and implementation of safeguards to prevent future occurrences. Mostly, relocate Tedford and acknowledge this map 42 lot 8 & 11 site is non conforming for the development. Ultimately, this complaint seeks to ensure that development in Brunswick is conducted lawfully and safely, in a manner that respects both the rights of residents and the needs of vulnerable populations. The appellant stands ready to assist investigators with any further information needed and looks forward to a response that will address the serious concerns raised in this document.

I do have exhibits of voice recordings, of altered ZO text and codify system validating my claims by showing modifications happened at that exact time I allege this as occuring. I have voice recordings of having discussed such with sande hot graph and requests of filing reports to BPD and States attorney via reporting to Officer Wyman on 5/3/24 and so on. I've DOCUMENTED everything. I have numerous emails between town manager, councilors and staff. Some which disregard taking complaints of being mocked on public record very lightly and claims they cannot find the guilty party although validating they do acknowledge that my claim was accurate and true. I have filed investigation request to HUD-OIG this morning and request they revoke funding to this project due to these inadequate unmet life safety standards and lack of mandated required NEPA environmental impact study that Tedford does not supply. Especially concerning considering 8/19/24 MRRA hanger 6 AFFF 60,000 PFOS disaster spill. That along with Portland pedestrian death of a homeless shelter transit named Justin Mitchell just as recent as 2/23/25 by a car. It's very important to know these unenforced regulations and requirements will fall on all those accountable to ensure proper procedural oversight. Know that I have the records to prove having brought this concern to light multiple times. I acknowledge the inconvenience of Tedfords situation and I do empathize with their plight. Ultimately, I feel this all could have been avoided if proper transparency and actions were implemented from day one. Do nonetheless consult with these funding providers and see if

indeed, they have financial capacity or not. Lastly, I record them out there everyday doing construction. Considering no reisuance of cup permit was achieved, every action is illegally made in my understanding and enforceable by State and Municipal Police departments. I expect to see STOP WORK orders immediately. Injunctions to Stop work ect. I am open to discuss and or provide the items I vow to have. I am currently working on a way to combine all things in a documentable easily comprehensible flash drive. However previous submissions to the town via in email complaints or in town council or committee or board meetings, and appeals should contain some for your reviewal. Please standby. Unless it not need to come to that. Note also, I have hard copies of previously mailed butter notifications for Tedford projects in original mailed envelopes stamped by USPS and voice recordings confirming I was added to abutters list. Just do what's right. I don't wish to fight or take this to higher courts. I will, if you insist.
Respectively,
Mrs. Jennifer Navarro

Lastly, why did chair of planning board Mr. Dana approved 13 months worth of minutes on 2/25/25 planning board meeting? Are they not required to be submitted within 14 days for public review? And note disclosures of conflicts of interest are mandated to be required in Written expressed which was not done so failure to disclosure and ultimately Brunswick needs immediate training and supervision of its employees staff and volunteers.

This email has been scanned for spam and viruses by Proofpoint Essentials. Click here to report this email as spam.

DrummondWoodsum
ATTORNEYS AT LAW

Leah B. Rachin
Admitted in ME

207.253.0578
lrachin@dwmlaw.com

84 Marginal Way, Suite 600
Portland, Maine 04101-2480
207.772.1941 Main
207.772.3627 Fax

February 27, 2025

Nicholas Livesay, Chair
Brunswick Zoning Board of Appeals
85 Union Street
Brunswick, ME 04011

RE: Tedford Housing's Response to Administrative Appeal by Jennifer Navarro of Planning Board's January 28, 2025 Extension of Tedford Housing's Site Plan Approval

Dear Chairman Livesay:

Our firm represents Tedford Housing ("Tedford"). This letter is in response to Jennifer Navarro's February 4, 2025 appeal of the Brunswick Planning Board's January 28, 2025 decision to extend Tedford's site plan approval for its "Shelter Resource Center" in the Town's Growth Mixed-Use 4 Zoning District (the "GM4") until January 11, 2027.

As explained below, the grounds on which Ms. Navarro bases her administrative appeal are both legally and factually erroneous. It should be accordingly denied.

1. Governing Standard of Review

Before addressing the substantive reasons why Ms. Navarro's appeal should be denied, it is important to highlight the standard of review that governs this Board's review of the Planning Board's decision to grant Tedford an extension of its site plan approval.

Under § 5.2.7.A.3 of the Town of Brunswick Zoning Ordinance (the "ZO"), when reviewing an administrative appeal from any decision of the Planning Board, this Board may "[n]ot substitute [its] judgment…for the judgment of the Board whose decision is under appeal." Rather, it must "[d]etermine on the basis of the entire record presented whether [the Planning Board] could reasonably have found the facts and reached the conclusions upon which the decision under appeal was based."

Accordingly, the proper inquiry is not whether this Board could, based on the evidence, conclude differently than the Planning Board. Rather, it is more deferential. Like the standard of review that governs Maine courts' review of municipal board decisions, this Board should reverse the Planning Board's findings *only* if the record *compels* a contrary conclusion. *See Two Lights Lobster Shack v. Town of Cape Elizabeth*, 1998 ME 153, ¶ 5, 712 A.2d 1061; *Gillespie v. Town of Southwest Harbor*, 675 A.2d 501, 503 (Me.1996). Under the clear terms of § 5.2.7.A.3(a)(vi) of the ZO, if this Board finds that the Planning Board did not clearly err in its review of Tedford's extension application, then its determination must be upheld.

Because, as discussed below, the Planning Board committed no legal error, and its decision to grant Tedford the requested extension of its approval was based on substantial record evidence, its decision must be affirmed.

2. Ms. Navarro Lacks Standing to Bring This Appeal

It is a fundamental principal of municipal law that before someone may bring an administrative appeal, they must possess the requisite standing. In order to have standing, the individual must be an "aggrieved party," under § 5.2.7.A(2)(a) of the ZO. This term is not defined in the ZO; however, it has been frequently analyzed by Maine courts.

Under well-established Maine case law, in order to establish standing, appealing parties bear the burden of establishing both that they: (1) participated in the administrative proceedings being appealed; and (2) suffered a particularized injury or harm greater than that suffered by the general public. *Nergaard v. Town of Westport Island*, 2009 ME 56, ¶ 16, 973 A.2d 735, 740 citing *Norris Family Assocs., LLC v. Town of Phippsburg*, 2005 ME 102, ¶ 11, 879 A.2d 1007, 1012.

Even if Ms. Navarro could establish the second requirement, she cannot demonstrate that she participated in the Planning Board proceedings, which is a necessary precondition to establish standing. *See Friends of Lincoln Lakes v. Town of Lincoln*, 2010 ME 78, ¶¶ 12-13, 2 A.3d 284, 288 citing *Pride's Corner Concerned Citizens Ass'n v. Westbrook Bd. of Zoning Appeals*, 398 A.2d 415, 417 (Me.1979).

Ms. Navarro did not participate in the Planning Board proceedings from which she appeals. Although she alleges that she did not receive notice of the proceedings, for the reasons outlined below, she was not entitled to individual notice. Moreover, the agenda for the January 28, 2025 meeting at which the Planning Board considered and granted Tedford's extension request was duly posted on the Town's website. Attached as **Exhibit 1** is a copy of said agenda. Because she did not participate in the proceedings, despite proper notice having been posted, Ms. Navarro's appeal should be denied for lack of standing.

3. Grounds of Appeal

Ms. Navarro's grounds of appeal appear to be three-fold: (1) she challenges whether Tedford's request for extension was made prior to expiration, as required by § 5.2.9.Q(1)(c) of the "ZO"; (2) she asserts that she was not given appropriate notice of Tedford's extension application; and (3) she questions the impact of the possibility of HUD and federal/state funds being withheld.

Each ground of appeal will be addressed separately below. For the reasons that follow, they all lack merit and should be dismissed accordingly.

A. Tedford's Request for an Extension Was Timely

Both the undisputed record evidence and the plain wording of the governing provisions of the ZO clearly demonstrate that Tedford's request for an extension of its site plan approval was timely.

Section 5.2.9.Q(1) of the ZO, entitled, "Expiration of Development Review Approvals" provides, in relevant part, as follows: "(c) The applicant may, *at any time before the date of expiration*, make a written request to the Review Authority for a time extension…"

The record makes clear that Tedford did, in fact, make its application prior to the expiration date of its site plan approval. Attached as **Exhibit 2** is a copy of Tedford's final approval of its application for Final Plan Major Development Review dated January 11, 2022. According to § 5.2.9.Q(2) of the ZO, site plan approvals shall expire three (3) years from date of approval. Accordingly, per the clear terms of the ZO, Tedford's site plan approval was scheduled to expire on January 11, 2025.

On December 30, 2024, on Tedford's behalf, Tedford's engineer, Nancy St. Clair, submitted an application to Julie Erdman, the Town's Director of Planning and Development requesting "an extension of its site plan approval (final major development review) prior to its upcoming expiration on January 11, 2025." Attached as **Exhibit 3** is a copy of said application together with Ms. St. Clair's email exchange with Ms. Erdman in connection with same.[1] Responding to Ms. St. Clair's submission, Ms. Erdman expressly acknowledged the timeliness of the extension request, stating, "Thank you, Nancy. Per subsection 5.2.9.Q(1), your application for a site plan extension has been received prior to its January 11th expiration. We will place this item on the Planning Board's January 28th agenda." *See* **Exhibit 3**.

Section 5.2.9.Q(2) of the ZO requires that requests for extension must be made "no less than 14 days prior to applicable Review Authority consideration." Tedford's extension request was made on December 30, 2025. *See* **Exhibit 3**. The meeting at which the request was considered by the Planning Board took place on January 28, 2025, which date was 29 days after the request, which well exceeded the 14 day requirement under the ZO.

Based on the foregoing, any suggestion that Tedford's request for an extension was untimely is unfounded. The undisputed record evidence unequivocally establishes that the request was made on December 30, 2024, which was prior to the January 11, 2025 expiration of Tedford's site plan approval. Moreover, the request was made more than 14 days from the date that the Planning Board considered it. As a result, Ms. Navarro's appeal on this basis must be denied as a matter of law.

B. All Governing Notice Requirements Under the ZO Were Met

[1] The application was two-fold. In addition to requesting an extension of Tedford's site plan approval, the application also requested certain minor modifications to the approved plan. Given that Ms. Navarro's appeal application does not list any concerns relating to the requested minor modifications, that portion of the application has been excluded from **Exhibit 3**.

Ms. Navarro appears to assert that she did not receive appropriate notice of Tedford's request for an extension as required by the ZO. Again, this ground of appeal lacks merit and should be dismissed accordingly.

Section 5.1.3.B, of the ZO, entitled "Notice Provided," states as follows:

> When an application for Development Review is received, Town staff shall notify the owners of all property as follows:
>
> > For Minor Modification applications, direct abutters to the property under review;
> >
> > For Conditional Use and Special Permit applications, all property owners located within a 300-foot radius of the parcel; or
> >
> > For all other Development Review applications, all property owners located within a 300-foot radius of the parcel.

Contrary to her suggestion, Ms. Navarro was not entitled to individual notice of the Planning Board's consideration of Tedford's extension request for several reasons.

First, the notice provisions only apply to "applications for Development Review." At issue was a request for an *extension*. There was no *application* for development review. Rather, Tedford's development review application had *already* been reviewed and approved three years prior. Ms. Navarro had every opportunity to participate in those proceedings. Given that the project has already been approved, there can be no prejudice to Ms. Navarro occasioned by its extension.

Second, the extension request was submitted together with a minor modification application. The plain language of § 5.1.3.B, of the ZO makes clear that only direct abutters (which Ms. Navarro is not) are entitled to individual notice.

Third, and most notably, even if § 5.1.3.B of the ZO did require that individual notice of Tedford's extension application be given, its unambiguous language requires that only property owners within a 300-foot radius of the subject property be notified. By Ms. Navarro's own admission in her appeal materials, she is located 325 feet away.

Based on the foregoing, any suggestion by Ms. Navarro that she was entitled to individual notice under the ZO is legally and factually incorrect and must be rejected accordingly.

C. <u>Ms. Navarro's Suggestion That Tedford May Lack Financial Capacity is Unfounded</u>

Without providing any factual foundation for her suggestion, Ms. Navarro asserts that various HUD and federal/grants could be withheld (with the implication that this would then make the project unviable). Once again, this ground of appeals lacks factual and legal basis and should be consequently ignored.

Ms. Navarro has offered no factual basis for her suggestion that HUD or other grants will be withheld from Tedford. Nor has she cited to any provision of the ZO that would require an extension request be denied even if such grants were withheld.

First, any such grants constitute a small percentage of the construction costs. Second, in granting the original approval, the Planning Board specifically found that Tedford met § 4.16 of the ZO's "financial capacity" requirement, which requires applicants to demonstrate "adequate financial and technical capacity to meet the standards of the proposed development." Such capacity can be evidenced by "documentation from an independent third-party as to applicant's financial capacity." Tedford submitted such documentation in support of its original application, based on which, the Planning Board concluded that "…An updated letter, dated November 22, 2021, from Bath Savings Institute is included and indicates the applicant's financial capacity to completed the proposed project." *See* **Exhibit 2** at p. 8.

4. Conclusion

For all the foregoing reasons, Tedford Housing respectfully requests that Ms. Navarro's administrative appeal be denied.

Sincerely,



Leah B. Rachin

cc: Andrew Lardie, Tedford Housing
Julie Erdman (via email)
Jennifer Navarro (via regular mail)

EXHIBIT 1

Town of Brunswick, Maine

DEPARTMENT OF PLANNING & DEVELOPMENT

Planning Board Meeting Agenda
Brunswick Town Hall
85 Union Street – Council Chambers
Tuesday, January 28, 2025 @ 6:00 PM

There is an opportunity to attend this meeting in person or view the meeting via Zoom, TV 3, or live stream.

How to watch and comment via Zoom:

https://www.brunswickme.org/313/Brunswick-Cable-TV3

How to watch via TV3 or Live Stream:

The link to view or listen to the meeting on TV3 (Channel 3 on Comcast) or via live stream from the Town's website: http://tv3hd.brunswickme.org/CablecastPublicSite/watch/1?channel=1

The public may provide comment via email (jerdman@brunswickme.gov) prior to the meeting OR they may provide live comment at the meeting via Zoom or in person. Comments are allowed during the public comment period, during public hearings, and on other items and matters at the discretion of the Planning Board Chair or Vice Chair.

1. **Case No. 24-071 Northbridge Apartments -** The Planning Board will review and act upon a **Sketch Plan Major Development Review** application submitted by Atlantic Resource Consultants on behalf of Northbridge Brunswick Land, LLC for 4 multi-family buildings with 24 units each (96 units in total), associated parking and amenities. The subject property, 0 Admiral Fitch Avenue (Map 040 Lot 50), is located within the **Growth Mixed-Use 7 Zoning District (GM7)**.

2. **Case No. 24-072 Pleasant Street Dental Conditional Use Permit –** The Planning Board will hold a **PUBLIC HEARING** and act upon a **Conditional Use Permit** application submitted by Dextrous Creative on behalf of James Moshier, DMD for expansion of the existing **Office** use. The project will expand the building footprint by 333 sq ft to add a wheelchair lift and stairs to the second floor which will be expanded by 946 sq ft. The subject property, 53 Pleasant Street (Map U16 Lot 51), is located within the **Growth Residential 6 Zoning District (GR6)** and the **Village Review Overlay District (VRO).**

3. **Case No. 24-073 Pleasant Street Dental Minor Review -** The Planning Board will review and act upon a **Minor Development Review** application submitted by Dextrous Creative on behalf of James Moshier, DMD for expansion of an existing dental office. The project will expand the building footprint by 333 sq ft to add a wheelchair lift and stairs to the second floor which will be enlarged by 946 sq ft. The subject property, 53 Pleasant Street (Map U16 Lot 51), is located within the **Growth Residential 6 Zoning District (GR6)** and the **Village Review Overlay District (VRO).**

4. **Case No. 24-076 Extension Request for Tedford Housing Site Plan Major Development Review Approval -** The Planning Board will review and act on a **Site Plan Major Development Review Approval Extension Request** of the approved Case No. 21-70, Tedford Housing Homeless Shelter, Resource Center, submitted by St. Clair Associates on behalf of the property owner, Tedford Housing. The subject property is located at 65 Thomas Point

Road (Map 42, Lot 8) and within the **Growth Mixed-Use 4 (GM4) Zoning District**.

5. **Other Business**

6. **Adjourn**

Please call the Brunswick Department of Planning and Codes (725-6660) with questions or comments. Individuals needing auxiliary aids for effective communications please call 725-6659 or TDD 725-5521. This meeting will be televised.

EXHIBIT
2

Town of Brunswick, Maine

DEPARTMENT OF PLANNING AND DEVELOPMENT

APPROVED FINDINGS OF FACT
FINAL PLAN MAJOR DEVELOPMENT REVIEW
PLANNING BOARD

REVIEW DATE: January 11, 2022
CASE NUMBER: 21-070
PROJECT NAME: Tedford Housing Homeless Shelter, Resource Center
ADDRESS/ TAX MAP: Map 42, Lots 8 and 11
ZONING DISTRICT: Growth Mixed-Use 4 (GM4) Zoning District
OVERLAY ZONING: Cook's Corner Master Plan and Design Standards
APPLICANT: Tedford Housing
P.O. Boc 958
Brunswick, ME 04011
REPRESENTATIVE: Nancy St. Clair
St. Clair Associates
34 Forest Lane
Cumberland, ME 04011

I. APPLICATION COMPLETENESS

Staff has reviewed the application and determined that it is complete.

Approved Motion:

The Planning Board concurs with staff's conclusion that the basic Final Plan Major Development Review application materials have been submitted and that the application is complete such that the Board may proceed with substantive review of the application and identification of any further information required from the applicant.

First: Art Pierce Second: Rob Burgess Vote: 7-0-0

II. PROJECT SUMMARY

The approved Findings of Fact are based on the Final Plan Major Development Review Application titled "Major Development Review Tedford Housing Building" and dated November 23, 2021 (Exhibit A). The Planning Board reviewed and approved a Sketch Plan Major Development Review Application on September 8, 2021 (Exhibit B). The Staff Review Committee (SRC) reviewed the Final Plan Major Development Review application on December 8, 2021. The SRC meeting notes are included under separate cover.

The proposed *homeless shelter, resource center* is intended to provide temporary emergency housing and on-site resources for individuals and households that are clients of Tedford Housing. The proposed shelter is approximately 17,568 square feet and it will include ten (10) household apartment-style units, each with a bedroom with four (4) beds and living and dining space in each unit. The proposed shelter will also accommodate twenty-four (24) individual clients in a dormitory-style space. Therefore, the total number of beds proposed is sixty-four (64). The applicant has indicated that the facility will not be a "drop-in" facility available to any member of the public. Occupants of the shelter must be enrolled in Tedford Housing's programs to help seek

new housing options.

The project site will be served by a twenty-six (26) space parking lot, two (2) of which will be compliant with Americans with Disabilities Act (ADA) standards. Additional site improvements include interior walkways with benches, play area, connection to the retail center to the northeast of the site, small storage building, and a dumpster enclosure.

The applicant has included a Purchase and Sale Agreement with the property to demonstrate right, title, and interest.

III. REVIEW STANDARDS

3.4.1.X Homeless Shelter Supplementary Use Standards

Subsection (1) provides the formulas necessary to calculate maximum density allowed for a *homeless shelter, resource center.* Based on the underlying GM4 Zoning District, the maximum number of dwelling units permitted for the subject property is forty-six (46) dwelling units. The proposed project includes ten (10) apartment-style household units and twenty-four (24) dormitory-style beds for individuals. Using the formula, the twenty-four (24) individual beds equate to six (6) residential dwelling units. Therefore, the total number of dwelling units is calculated as sixteen (16), well below the maximum number of units allowed.

Subsection (2) provides the formulas necessary to calculate the demand for parking spaces for a *homeless shelter, resource center*. Using these formulas, the included traffic study by Maine Licensed Traffic Engineers John Adams and Bill Bray of Barton and Loguidice / Traffic Solution calculates the minimum parking demand as twenty-six (26) parking spaces. The proposed project provides the minimum twenty-six (26) parking spaces, including two (2) spaces compliant with the Americans with Disabilities Act (ADA).

Subsection (3) requires the applicant to provide interior floor plans dimensioned with spaces labeled with the proposed use. The applicant has provided floor plans prepared by Ryan Senatore Architecture in their application.

Subsection (4) requires non-apartment-style homeless shelter space to be dedicated for use by unaccompanied minors under eighteen (18) years of age or adults, but not both. The applicant has indicated that the dormitory-style section of the building is intended only for individual adults.

Subsection (5) requires a minimum 1,000-foot separation between any new homeless shelter and any existing homeless shelter. The nearest homeless shelter, which is operated by Tedford Housing, is approximately 2.6 miles from the subject property.

The Planning Board finds that the provisions of Section 3.4.1.X are satisfied.

4.1. Applicability of Property Development Standards

As the proposed project is for a commercial use, all regulations established in *Chapter 4 – Property Development Standards* of the Zoning Ordinance apply. The Town Codes Enforcement Officer and other members of the SRC have reviewed the application

and found that it complies with all applicable Zoning Ordinance standards associated with the GM4 Zoning District.
The Planning Board finds that the provisions of Section 4.1 are satisfied.

4.2. Dimensional and Density Standards

As referenced in Item 4.1 above, the proposed project has been found to comply with all applicable property developments standards. This includes the standards established in *Table 4.2.3. Growth Area Dimensional and Density Standards* of the Zoning Ordinance.

The Planning Board finds that the provisions of Section 4.2 are satisfied.

4.3. Natural and Historic Areas

4.3.1 Mapping of Natural and Historic Areas Requirements

As there were no natural or historic areas identified via the wetland delineation study performed by Mark Hampton Association, the Maine Natural Areas Program (MNAP), or the Town's GIS system.

The Planning Board finds that the provisions of Section 4.3.1 are not applicable.

4.3.2 Pollution

The subject property is not located within any floodplain or other special flood hazard area. No on-site wastewater is proposed as the applicant is proposing to connect to the Brunswick Sewer District system. Stormwater will be managed via Maine Department of Environmental Protection's Best Management Practices to treat stormwater runoff prior to discharge.

The Planning Board finds that the provisions of Section 4.3.2 are satisfied.

4.3.3 Protection of Natural Vegetation

As indicated in Item 4.3.1 above, no natural areas were identified on the subject property.

The subject property is not located in any designated scenic area.

The applicant has indicated that the site plan was developed with an attempt to protect existing wooded area to the greatest extent possible.

As indicated on the landscape plan, the subject property will be improved with new plantings and fencing.

The Planning Board finds that the provisions of Section 4.3.3 are satisfied.

4.3.4 Protection of Significant Plant and Animal Habitat

As stated in Items 4.3.1, the proposed project is not located within the Town's

Wildlife Protection Overlay (WPO) District and no other mapped significant plant and animal habitats were identified during the review process. Therefore, the proposed project will not have an undue adverse effect on important plant and animal habitats identified by the Maine Department of Inland Fisheries and Wildlife, or on rare and irreplaceable natural areas as identified by the Maine Natural Areas Program.

The Planning Board finds that the provisions of Section 4.3.4 are not applicable.

4.3.5 Steep Slopes

The subject property on which the proposed project is to be constructed does not have any 5,000 square foot or more of contiguous slopes exceeding twenty-five percent (25%).

The Planning Board finds that the provisions of Section 4.3.5 are not applicable.

4.3.6 Erosion and Sedimentation

The applicant has provided an Erosion and Sediment Control Plan and Narrative demonstrating that the plans have been developed according to the DEP's Best Management Practices Handbook. The plan also provided post-construction requirements. Furthermore, an Inspection and Maintenance Plan and Log have been provided.

The Planning Board finds that the provisions of Section 4.3.6 are satisfied.

4.3.7 Groundwater

The subject property is not located with any of the Town's Aquifer Protection Overlay (APO) Districts. Sewage will be conveyed by a connection to the Brunswick Sewer District. The applicant has indicated that they will construct an extension from Brunswick and Topsham Water District's water main along Thomas Point Road. The above referenced Best Management Practices for stormwater runoff and erosion and sedimentation control will treat stormwater prior to discharge.

The Planning Board finds that the provisions of Section 4.3.7 are satisfied.

4.3.8 Surface Waters, Wetlands, and Marine Resources

The wetland delineation study found no surface waters or wetlands on the subject property.

The Planning Board finds that the provisions of Section 4.3.8 are not applicable.

4.3.9 Historic and Archaeological Resources

No historic or archaeological resources were identified within the subject property.

The Planning Board finds that the provisions of Section 4.3.9 are not applicable.

4.4. Flood Hazard Areas

The subject property is not located within the Flood Protection Overlay (FPO) District or mapped Flood Hazard Area.

The Planning Board finds that the provisions of Section 4.4. are not applicable.

4.5. Basic and Municipal Services

4.5.1 Sewage Disposal

The proposed project will connect to the Brunswick Sewer District System.

The Planning Board finds that the provisions of Section 4.5.1 are satisfied.

4.5.2 Water Supply and Quality

The applicant has indicated that they will construct an eight-inch (8") diameter extension approximately 702 feet from the nearest connection to the Brunswick and Topsham Water District.

The Planning Board finds that the provisions of Section 4.5.2 are satisfied

4.5.3 Solid Waste Disposal

The site plan includes a dumpster enclosure for solid waste disposal. The applicant has indicated that they will contract with a local commercial waste hauler.

The Planning Board finds that the provisions of Section 4.5.3 are satisfied.

4.5.4 Stormwater Management

The proposed project requires only a DEP Stormwater Permit by Rule. The applicant has included an approved permit as an addendum to this application.

The Planning Board finds that the provisions of Section 4.5.1 are satisfied.

4.6. Landscaping Requirements

The proposed landscape plan has been reviewed by the Town Codes Enforcement Officer and Town Arborist and found to be consistent with all applicable Zoning Ordinance landscape standards. The applicant has also provided amenities such as an internal green space, benches, bicycle racks, and an outdoor play area.

The Planning Board finds that the provisions of Section 4.6 are satisfied.

4.7. Residential Recreation Requirements

As there are no permanent residential dwelling units proposed, the residential recreation impact fees are not applicable to the proposed project.

The Planning Board finds that the provisions of Section 4.7 are not applicable.

4.8. Circulation and Access

4.8.1 Street Standards

No new streets are proposed as part of the project. The applicant provided a traffic study with an estimated sixteen (16) peak hour trips. This number falls below the one-hundred (100) trips that would trigger the need for a traffic movement permit from Maine DOT. Furthermore, the traffic associated with the proposed project is not anticipated to impact the existing level of service.

The Planning Board finds that the provisions of Section 4.8.1 are satisfied.

4.8.2 Circulation and Access

There is one (1) access point proposed. The Town Engineer did not state any concerns with the location and dimensions of the access point. However, an entrance permit from the Town Engineer will be required.

The Planning Board finds that the provisions of Section 4.8.2 are sastisfied.

4.8.3 Pedestrian and Bicycle Access

A network of internal paths and walkways, including a connection to the Wal-Mart shopping center, are proposed. Bicycle racks are provided on-site. Furthermore, the applicant has indicated their willingness to contribute to a sidewalk fund that will be used for the future Thomas Point Road improvements.

The Planning Board finds that the provisions of Section 4.8.3 are satisfied.

4.8.4 Access for Persons with Disabilities

The site plan has been developed in accordance with Americans with Disability Act (ADA) design standard. This includes access from two (2) ADA-compliant parking spaces with accessible routes to the building entrance. ADA-compliant ramps are provided where necessary.

The Planning Board finds that the provisions of Section 4.8.4 are satisfied.

4.9. Parking and Loading

The twenty-six (26) parking spaces (include two (2) ADA-compliant spaces) provided meet the minimum parking demand standards for homeless shelters established in Section 4.3.1.X of the Zoning Ordinance.

A bicycle rack for six (6) bicycles meets the minimum standard.

All parking spaces meet the minimum dimensional standards.

The Planning Board finds that the provisions of Section 4.9 are satisfied.

4.10. Lighting

The applicant has included spec sheets for full cut-off lighting fixtures to be used on the subject property. The included photometric plan indicates that there will be no light trespass onto surrounding properties. The applicant did not indicate the proposed color temperature for the outdoor lighting but is strongly encouraged not to exceed 3,000 Kelvin.

The Planning Board finds that the provisions of Section 4.10 are satisfied.

4.11. Architectural Compatibility

The applicant has included a memorandum from Ryan Senatore Architecture outlining the architectural treatments used to be consistent with the Cook's Corner Design Standards. Such traditional New England architectural features include its main gable roof with smaller gable dormers perpendicular to the main roof and gabled projecting bays.

Consistent with traditional New England architecture, the proposed windows are double-hung with mullions dividing the individual panes.

Proposed exterior material include fiber cement siding with battens and architectural asphalt shingles, both of which are used throughout the surrounding area.

The Planning Board finds that the provisions of Section 4.11 are satisfied.

4.12. Neighborhood Protection Standards

As the proposed project is surrounded by the GM4 Zoning District neighborhood protection standards do not apply.

The Planning Board finds that the provisions of Section 4.12 are not applicable.

4.13. Signs

The proposed project includes a monument and building mounted sign. The Town Codes Enforcement Officer reviewed the proposed signage and found it consistent with Section 4.13

The Planning Board finds that the provisions of Section 4.13 are satisfied.

4.14. Performance Standards

The applicant has indicated their ability to comply with all of the performance standards pertaining to noise, smoke and particulate matter, dust and fumes, odors,

vibrations, unlicensed motor vehicles, or lighting and glare. If approved, construction of the facility will occur between the permitted hours of 7:00 AM – 7:00 PM

The Planning Board finds that the provisions of Section 4.14 are satisfied.

4.15. Site Maintenance

The applicant has indicated that the proposed project will be maintained consistent with their standard in place at their existing locations. The stormwater management plan accounts for the necessary maintenance of BMPs. A Inspection and Maintenance Plan and Log is included with the application.

This finding serves to advise the applicant that site features constructed or installed as required by this development review must be maintained in good repair, and replaced if damaged or destroyed, or in the case of living materials, if they die or are effectively destroyed after installation.

The Planning Board finds that the provisions of Section 4.15 are satisfied.

4.16. Financial and Technical Capacity

The application includes a Purchase and Sale Agreement with the owner of the subject properties. Copies of the subject properties' deeds are also included. An updated letter, dated November 22, 2021, from Bath Savings Institute is included and indicates the applicant's financial capacity to completed the proposed project.

A performance guarantee is required prior to the construction of the infrastructure intended to be dedicated to the Brunswick and Topsham Water District. According to the applicant, the BTWD has indicated the potential that they will cover the cost difference between installing a twelve-inch (12") diameter water main rather than the proposed eight-inch (8") diameter water main.

The introduction letter includes all members of the project's design team and their associated qualifications.

The Planning Board finds that the provisions of Section 4.16 are satisfied, provided the applicant provide a performance guarantee to the Brunswick and Topsham Water District.

4.17. Administrative Adjustments / Alternative Equivalent Compliance

No administrative adjustments or alternative equivalent compliance plans are requested.

The Planning Board finds that the provisions of Section 4.17 are not applicable.

IV. EXHIBITS

A. Final Plan Major Development Review Application, dated November 23, 2021
B. Sketch Plan Major Development Review Documentation, dated September 8, 2021

APPROVED MOTION
CASE NO. 21-070
REVIEW DATE: JANUARY 11, 2022

APPROVED MOTION: That the Final Plan Major Development Review for the properties located at Map 42, Lots 8 and 11is approved with the following conditions:

1. That the Planning Board's review and approval does hereby refer to these findings of fact, the plans and materials submitted by the applicant and the written and oral comments of the applicant, his representatives, reviewing officials, and members of the public as reflected in the public record. Any changes to the approved plan not called for in these conditions of approval or otherwise approved by the Director of Planning and Development as a minor modification shall require a review and approval in accordance with the Brunswick Zoning Ordinance.

2. Prior to the issuance of a building permit, the applicant shall submit to the Department of Planning and Development a copy of a performance guarantee approved by the Brunswick and Topsham Water District.

3. Prior to the issuance of a building permit, the applicant shall submit to the Director of Planning and Development documentation depicting Lots 8 and 11 as consolidated.

4. Prior to the issuance of a building permit, the applicant shall submit to the Department of Planning and Development a copy of a letter from the Brunswick Sewer indicating their ability to serve the project.

5. Prior to the issuance of a Certificate of Occupancy, the applicant shall submit to the Department of Planning and Develop an as-built construction plan per the request of the Cumberland County Soil and Water Conservation District.

6. Should within the next five (5) years the Town of Brunswick fund improvements to Thomas Point Road, as proposed in the existing Capital Improvement Plan, the applicant, prior to the start of said improvements, shall contribute funds for materials, mutually agreed upon in cost, for a sidewalk along the subject properties' Thomas Point Road frontage, not to exceed 387 feet in length. Should the Town not commence construction of the sidewalk within five (5) years of the date of approval this condition shall become null and void.

First: Kelly Matzen Second: Jane Arbuckle Vote: 7-0-0

From: Julie Erdman <jerdman@brunswickme.gov>
Sent: Thursday, January 2, 2025 2:00 PM
To: 'Andrew Lardie, Tedford Housing' <andrew@tedfordhousing.org>; 'Danielle Triffitt' <danielle@tedfordhousing.org>; 'Timothy Schneider' <tps@sagestoneconsulting.com>; 'David Merrill' <dam@warrenconstructiongroup.com>
Cc: Lourdes Sanchez <lsanchez@brunswickme.gov>; James Dealaman <jdealaman@brunswickme.gov>
Subject: FW: Tedford Housing Request for Site Plan Approval Extension and Minor Modification

Warning: Unusual sender <jerdman@brunswickme.gov>
You don't usually receive emails from this address. Make sure you trust this sender before taking any actions.

Thank you, Nancy. Per Subsection 5.2.9.Q(1), your application for a site plan extension has been received prior to its January 11th expiration. We will place this item on the Planning Board's January 28th agenda.

I find that the attached proposed changes do constitute a Minor Modification, and I will notice those accordingly so that the application may be acted on following the Planning Board's decision on the extension.

Best Regards,

Julie Erdman
Director
Planning and Development
P: (207) 721-4022
E: jerdman@brunswickme.gov

Brunswick maine
85 Union Street
Brunswick | ME 04011
www.brunswickme.gov

With limited exceptions, e-mails sent to and from the Town of Brunswick are considered public records under Maine's Freedom of Access Act (FOAA). Public records are open to inspection and may be copied and distributed to others, including members of the media. Unless the e-mail meets one of the exceptions to the public records provisions, there should be no expectation of privacy or confidentiality.

From: Nancy St.Clair <nancy@stclairassociatesmaine.com>
Sent: Monday, December 30, 2024 12:48 PM
To: Julie Erdman <jerdman@brunswickme.gov>; 'Andrew Lardie, Tedford Housing' <andrew@tedfordhousing.org>; 'Danielle Triffitt' <danielle@tedfordhousing.org>; 'Timothy Schneider' <tps@sagestoneconsulting.com>; 'David Merrill' <dam@warrenconstructiongroup.com>
Cc: David C. St. Clair Jr P. L. S. <david@stclairassociatesmaine.com>
Subject: Tedford Housing Request for Site Plan Approval Extension and Minor Modification

Dear Julie,

Attached are digital copies of our two-part application package in support of Tedford Housing's new building currently under construction on Thomas Point Road. As our enclosed cover letter describes, we are respectfully requesting your consideration of an extension of the project's site plan approval (final major development review) prior to it's upcoming expiration on January 11th, 2025. In addition, we are also requesting staff review of minor site revisions as described in the attached letter. In addition to our letter, we have enclosed the minor modification application form and a digital set of drawings for your consideration. Tedford Housing will be dropping off the check for application fee this week. Five paper copies of the attached materials are being delivered to your office today.

Please let us know if you would like this information uploaded to the permit portal as well. We look forward to hearing from you. Please let us know if you need any additional information or if you have any questions.

We hope you have a safe and enjoyable New Years Eve.

Thanks,
Nancy

Nancy St.Clair P.E., Vice President
St.Clair Associates
34 Forest Lane
Cumberland, ME 04021

207-615-8586 cell
207-829-5558 office



EXHIBIT
3

St.Clair Associates
Land Surveying and Civil Engineering
34 Forest Lane
Cumberland, Maine 04021

21012 December 30, 2024

Julie Erdman, Director of Planning Development
Town of Brunswick Planning and Development
85 Union Street
Brunswick, ME 04011

Request for Site Plan Approval Extension and
Request for Minor Modification
Major Development Plan & Conditional Use
Tedford Housing Building (Case # 24-020)
65 Thomas Point Road
Assessor's Map 42, Lots 8 and 11
Brunswick, ME

Dear Ms. Erdman,

On behalf of Tedford Housing, we have prepared this two-part application to seek an extension of Site Plan Approval and Minor Site Revisions to address further detailing associated with site construction. We offer the following for your review:

Request for Site Plan Approval Extension

As you know, on May 14, 2024 the Brunswick Planning Board issued a re-approval of the Conditional Use Permit for Tedford Housing's new facility on Thomas Point Road. Previously, on January 11, 2022 the Brunswick Planning Board granted unanimous approvals of a Conditional Use Permit and the Final Major Development Review for Tedford Housing on Thomas Point Road. At the time of re-approval of the Conditional Use Permit, the Site Plan Approval had not lapsed (and will not lapse until January 11, 2025) and did not require re-approval.

We are respectfully requesting that the staff and Planning Board consider this request for extension of the Applicant's Site Plan Approval (Final Major Development Review), given the fact that the building is currently under construction but will not be ready for

occupancy by the date associated with the original Site Plan Approval (January 11, 2025).

As you may be aware, subsequent to the original Approvals in 2022, the Applicant continued its Capital Campaign to raise funds to support the construction of this new facility, including pursuit of Federal funding support. The fundraising process has been lengthy but finally reached the point to allow construction to proceed this fall. However, given the timing of this process, including the time necessary to complete the Federal level reviews, the construction will not be sufficiently complete to allow building occupancy by January 11, 2025. It is anticipated that the building will be completed for occupancy in late 2025. Given this timing, we are respectfully requesting an extension of the Applicant's Site Plan Approval (Final Major Development Review).

Request for Minor Modification

In addition, we have prepared the enclosed materials in support of a proposed Minor Modification to the Tedford Housing Site Plan. We have prepared the enclosed Minor Modification Application to accompany the revised plans associated with this site.

It is our understanding that as part of this process, you will and other staff members will evaluate the materials to determine whether the proposed changes qualify for a staff-level review process, or whether the proposed changes warrant a return to the Planning Board.

It is important to note that the building's size and location on the lot have not changed, the amount of parking spaces have not changed and the driveway location has not moved. The following section describes the proposed minor modifications in further detail.

Proposed Minor Changes

- Sheet naming and numbering revisions on the Site Plan drawings:

  To support the bidding and construction process these minor revisions were made. Since the Site Plan drawings are now included in a larger construction set which includes all the drawings associated with the architectural, structural, mechanical, electrical, and plumbing drawings these naming and numbering changes were made. Additional details and clarifications have also been added to address contractor questions during

the bidding process. These changes were made to clarify and further detail the design of the site elements with no changes to the overall design intent.

- Addition of walkway to mechanical room:

  As part of the conditional use review and reapproval of the project, in May of this year, the Fire Department requested that a paved walkway be added from Thomas Point Road to the mechanical room located along the front of the building. This short, paved walkway has been added, as requested.

- Paving of walkway through rear of site:

  As you know the original Site Plan included a walkway through the rear of the site to provide pedestrian access to the abutting Walmart property. The surface of this walkway had been proposed as mulch on the previously approved plan. The Applicants have proposed that the surface of this walkway be a material that can be maintained year-round. Accordingly, the Applicants are proposing that this walkway be paved. There are no proposed changes to the route of the walkway.

- Pedestrian Scale Walkway Lighting:

  In order to facilitate safe pedestrian use of the walkway, pedestrian scale lighting has been added along the walkway through the rear of the site. An updated lighting and photometrics plan has been prepared to demonstrate compliance with the local lighting criteria. A copy of this updated lighting plan is enclosed.

- Sewer Service Revisions:

  The building's proposed sewer service has been modified to address the connection to the discharge point for the internal plumbing. In addition, when the contractor excavated the existing manhole in Thomas Point Road, it was discovered that the existing manhole structure would not allow connection at the original design invert. The invert was modified and the service slope was adjusted to accommodate this existing condition. The proposed sewer service modifications were reviewed with the Brunswick Sewer Department and found to be acceptable.

- Addition of Door at Easterly Wall:

  As part of the further detailing of the interior floor plans for the building, an egress door and threshold were added along the easterly wall. This door is located at the end of a hall in the office area and will allow an additional exit from the office area, if needed. This door is not a public access and is not available for the residents' use.

- Mechanical Unit Locations:

  As part of the detailed mechanical systems design for the building there are a series of small exterior pad mounted mechanical units that are placed along the outer edges of the building. These unit locations have been added to the plan.

- Proposed future generator pad:

  As part of the original design there was a rectangular paved area off the northeasterly edge of the parking lot. This rectangular area was intended to provide access to the previously proposed gravel wetlands in the area for maintenance. With the prior elimination of this BMP (as approved in the prior modifications in late 2023) this pad area was not being used. This paved pad has been converted to a proposed concrete pad to allow for future placement of a backup generator.

Review Criteria for Minor Changes

It is our understanding that a minor modification is allowed under certain conditions which are established in the Brunswick Zoning Ordinance in Chapter 5.2.10.B. We have addressed each of the 6 bulleted items contained in the Ordinance below. For ease of review, the criteria are shown in *italics*, along with our response, as follows:

- *Does not materially alter the layout or scale of the development or its impact on its surroundings;*

As noted above, the overall site layout and scale are not materially altered by these proposed minor changes. The building location, orientation, size and overall program elements remain as previously approved. No changes are proposed to the site entrance, parking layout and number of parking spaces.

- *Does not increase the number of lots or dwelling units;*

There are no proposed changes with regard to lots or dwelling units.

- *Does not violate provisions of any Town Ordinance;*

The proposed changes have been designed in accordance with the applicable Ordinance standards.

- *Does not reduce the effectiveness of the approved landscaping, screening, or buffering of the site;*

The proposed minor changes do not modify the provisions of landscaping, screening or buffering of the site included in the prior approved plans.

- *Does not significantly alter on-site vehicular circulation; and*

No changes are proposed to the vehicular circulation patterns on the site. The previously approved parking layout remains unchanged, no changes are proposed with regard to the driveway location or width or number of parking spaces on the site.

- *Does not significantly alter drainage patterns.*

As noted above, the proposed site changes include modifications to the walkway surface material through the rear of the site. No grading changes were made as part of this modification. As such, no changes to the overall site drainage patterns occurred. Our office also evaluated the change in impervious cover associated with the conversion of the walkway surface to pavement. This increase in impervious cover did not alter the overall curve number (CN) of the subcatchment that includes the walkway. As such, there are no anticipated increases in peak discharge for this subcatchment.

Application Materials

We have included five copies of the following materials in support of the applicant's request for an extension of the project's Site Plan Approval and Minor Modification to the previously approved Final Major Development/Conditional Use for Tedford Housing:

- Cover Letter/Project Description
- Minor Modification Application Form
- Revised Site Plan Set (including a revised Photometric Plan)

Please note that in addition to the plan information cited above, a check for the Minor Modification Application fee, in the amount of $250.00, is being delivered directly by the Applicant, under separate cover, to be included as part of this submittal package.

Closure

With the submittal of the materials listed above, we are respectfully requesting staff consideration of this request for an extension of the project's Final Major Development Review approval and approval of these proposed Minor Site Plan changes under the Brunswick Ordinance provisions for a Minor Modification to the Planning Board's prior approval for Final Major Development/Conditional Use review for this project, as described above.

As the enclosed Plans, and this letter demonstrate, the Applicant is proposing minor modifications to the site that are intended to allow the project to be constructed while still maintaining the integrity of the previously approved plans.

We are confident that you and other staff members will concur with our assessment that the enclosed Plan revisions are within the criteria for review as a Minor Modification.

We are available to meet with you if you have any additional questions as you review the enclosed materials. We look forward to hearing from you after you have had a chance to further review these requests.

We look forward to hearing from you.

Sincerely,

ST.CLAIR ASSOCIATES

Nancy J. St.Clair, P.E.
Vice President
NJS:njs

Andrew Lardie, Executive Director Tedford Housing
Danielle Triffitt, Director of Administration, Tedford Housing
Tim Schneider, Sage Stone Consulting